



Treasury Metals  
Revised EIS Report  
Goliath Gold Project  
August 2017



## **APPENDIX H**

### **ACOUSTIC ENVIRONMENT STUDY**

- H-1 RWDI Memorandum**
- H-2 Noise Baseline Study**
- H-3 Acoustic Assessment Report**
- H-4 Environmental Noise Assessment**



## NOTE TO READER APPENDIX H

In April 2015, Treasury Metals submitted an Environmental Impact Statement (EIS) for the proposed Goliath Gold Project (the Project) to the Canadian Environmental Assessment Agency (the Agency) for consideration under the Canadian Environmental Assessment Act (CEAA), 2012. The Agency reviewed the submission and informed Treasury Metals that the requirements of the EIS Guidelines for the Project were met and that the Agency would begin its technical review of the submission. In June 2015, the Agency issued a series of information requests to Treasury Metals regarding the EIS and supporting appendices (referred to herein as the Round 1 information requests). The Round 1 information requests included questions from the Agency, other federal and provincial reviewers, First Nations and other Aboriginal peoples, as well as interested stakeholders. As part of the Round 1 information request process, the Agency requested that Treasury Metals consolidate the responses to the information requests into a revised EIS for the Project.

Appendix H to the revised EIS (Acoustic Environment Study) includes information related to the effects of the Project on noise. The appendix includes the following four components:

- H-1: A memorandum from RWDI Air, dated May 5, 2017, which provides an opinion of the implications of refinements to the Project layout to the noise levels predictions presented as part of the original EIS. The expected changes should be relatively minor, resulting in slightly higher predicted noise levels for those receptors located along East Thunder Lake Road. The predicted noise levels at the closest receptors, located to the south of the Project near Tree Nursery Road are expected to be slightly lower as a result of the changes to the Project since the filing of the original EIS.
- H-2: Noise Baseline Study: This study presents the results of the monitoring program to measure and record background ambient sound levels at receptors in proximity to the Project, and to describe baseline noise conditions. The information contained in this report was relied on to prepare Section 5.3.1 of the revised EIS.
- H-3: Acoustic Assessment Report (AAR): This study demonstrates the Project will be able to achieve compliance with provincial permitting requirements. The information contained in this report was relied on as the primary source of information for the assessment of the effects of the Project on blasting noise and vibration levels (Section 6.4 of the revised EIS). The provincial permitting required to obtain a noise ECA is a separate process that will require Treasury Metals submit an updated AAR reflecting the final design specifications for the Project.
- H-4: Environmental Noise Assessment: This study provides an evaluation of the effects of the Project on noise levels throughout the life of the Project. The information presented in this report is the primary source of information used for describing the effects of the Project on noise levels (Section 6.4 of the revised EIS).



No changes have been made to the portions of this appendix presented in the original EIS issued in April 2015 (i.e., H-2, H-3 and H-4). To aid the reader, bookmarks for each component are provided in the electronic copy of this appendix.

As part of the process to revise the EIS, Treasury Metals has undertaken a review of the status for the various appendices. The status of each appendix to the revised EIS has been classified as one of the following:

- **Unchanged:** The appendix remains unchanged from the original EIS, and has been re-issued as part revised EIS.
- **Modified:** The appendix remains relatively unchanged from the original EIS, and has been re-issued with relevant clarification.
- **Re-written:** The appendix has been substantially changed from the original EIS. A re-written appendix has been issued as part of the revised EIS.
- **Discarded:** The appendix is no longer required to support the EIS. The information in the original appendix has been replaced by information provided in a new appendix prepared to support the revised EIS.
- **New:** This is a new appendix prepared to support the revised EIS.

The following table provides a listing of the appendices to the revised EIS, along with a listing of the status of each appendix and their description.

List of Appendices to the Revised EIS		
Appendix	Status	Description
Appendix A	Modified	Table of Concordance
Appendix B	Unchanged	Optimization Study
Appendix C	Unchanged	Mining Study
Appendix D	Re-written	Tailings Storage Facility
Appendix E	Unchanged	Traffic Study
Appendix F	Re-written	Water Management Plan
Appendix G	Discarded	Environmental Baseline
Appendix H	Unchanged	Acoustic Environment Study
Appendix I	Unchanged	Light Environment Study
Appendix J	Unchanged	Air Quality Study
Appendix K	Unchanged	Geochemistry
Appendix L	Discarded	Geochemical Modelling
Appendix M	Unchanged	Hydrogeology
Appendix N	Unchanged	Surface Hydrology
Appendix O	Discarded	Hydrologic Modeling
Appendix P	Unchanged	Aquatics DST



List of Appendices to the Revised EIS		
Appendix	Status	Description
Appendix Q	Re-written	Fisheries and Habitat
Appendix R	Re-written	Terrestrial
Appendix S	Re-written	Wetlands
Appendix T	Unchanged	Socio-Economic
Appendix U	Unchanged	Heritage Resources
Appendix V	Unchanged	Public Engagement
Appendix W	Unchanged	Screening Level Risk Assessment
Appendix X	Re-written	Alternatives Assessment Matrix
Appendix Y	Unchanged	EIS Guidelines
Appendix Z	Unchanged	TML Corporate Policies
Appendix AA	Modified	List of Mineral Claims
Appendix BB	Unchanged	Preliminary Economic Assessment
Appendix CC	Unchanged	Mining, Dynamic And Dependable For Ontario's Future
Appendix DD	Re-written	Aboriginal Engagement Report
Appendix EE	Unchanged	Country Foods Assessment
Appendix FF	Unchanged	Photo Record Of The Goliath Gold Project
Appendix GG	Modified	TSF Failure Modelling
Appendix HH	Unchanged	Failure Modes And Effects Analysis
Appendix II	Unchanged	Draft Fisheries Compensation Strategy and Plans
Appendix JJ	New	Water Report





Treasury Metals  
Revised EIS Report  
Goliath Gold Project  
August 2017



## **APPENDIX H-1**

### **RWDI MEMORANDUM**



600 Southgate Drive  
Guelph, ON N1G 4P6  
Canada

Tel: +1.519.823.1311  
Fax: +1.519.823.1316  
E-mail: [solutions@rwdi.com](mailto:solutions@rwdi.com)

## MEMORANDUM

<b>DATE:</b>	2017-05-05	<b>RWDI REFERENCE #:</b> 1602163
<b>TO:</b>	Mark Wheeler	<b>EMAIL:</b> <a href="mailto:mark@treasurymetals.com">mark@treasurymetals.com</a>
<b>FROM:</b>	John DeYoe	<b>Email:</b> <a href="mailto:john.deyoe@rwdi.com">john.deyoe@rwdi.com</a>
<b>RE:</b>	<b>Air Quality and Noise Impact Changes Related to Proposed Mill Location Treasury Metals</b>	


RWDI has previously completed an Air Quality<sup>i</sup> and Noise<sup>ii</sup> assessment for the Environmental Impact Statement (Federal) as well as an Air Quality<sup>iii</sup> and Noise<sup>iv</sup> assessment for the Environmental Compliance Assessment (Provincial). There were numerous air quality and noise sources examined for the project and their impact was assessed at receptors around the site.

Treasury Metals has asked RWDI to review the impact of moving the mine mill and associated activities to a location roughly 500 metres the northwest of the previously proposed location as shown in Figure 1, attached. Relatively few of the air quality and noise sources are associated with the mill. Generally speaking, this move would be an improvement or neutral in terms of air quality and noise. The mill activities are now farther from the closest receptors to the site and will improve. The receptors to the west, near Thunder Lake, are all over two kilometers away from the mill activity and will now be approximately 250 metres closer to the mill activities and will be neutrally affected. The following sections examine the air quality and noise impacts related to the proposed relocation of the mill.

## AIR QUALITY

### Air Quality Sources

The locations of the sources used in the air quality modelling are shown in the figure following. The red rectangles indicate the approximate positions of the previously proposed position of the mill and the newly proposed location of the mill.



The following sources associated with the mill were evaluated in the EIS and/or ECA assessments:

Source	Label	Percentage Emissions
Road to ore stock pile (shorter)	ROAD2	2% of Airborne metals
Unloading from ore trucks	ORE2	< 1% of particulate
Loader feeding ore crusher	LOADER	< 1% of particulate
Dozer on ore pile	DOZER1	3% of particulate

**Insignificant Sources**


500 KW Emergency generator	Gen1
150 kW Emergency Generator	Gen2
Baghouse emissions -ore crusher	BAGHOUSE
Kiln Burner	KILN
Elution Heater	ELUTION
Carbon Leach Tanks	MILL



The insignificant sources listed above will continue to be insignificant if the location of the mill is changed. For a further discussion of the significance of the sources we would direct the reader to the Air Quality Environment Compliance Assessment<sup>iii</sup>. The only significant emission from the mill area that were assessed are related to particulate emissions.

### Air Quality Receptors

The only receptors that could possibly be negatively affected by moving the mill are the receptors to the west of the mine site, towards Thunder Lake. The receptor locations are shown in the figure below which also shows the worst case 24-hour total suspended particulate (TSP) emissions:




The closest residential receptors are roughly 2500 metres from the initially proposed location of the mill. The newly proposed mill location will be approximately 300 metres closer to the western receptors.



## Air Quality Impact Frequency

The receptors located to the west of the site are also only infrequently impacted by emissions from the mill. The figure below shows the distribution of wind angles for the area:



As can be seen from the wind rose above the western receptors will be downwind of the mill area less than 10 % of the time.


## Air Quality Discussion

The mill site will be roughly 12% closer to the closest residential receptors to the west of the site. The receptors are well past the point of maximum ground level concentrations for the mill emissions. Numerical modelling of the mill emission would show concentrations at these points would increase less than 12%. Since mill area emissions only represent 7% of the total emissions, even if the predicted concentrations related to the emissions from the mill area doubled, they would only represent a 7% increase in the predicted concentration of particulate. The most critical air quality impacts modelled for the western receptors are related to the 24-hour TSP concentrations. Under worst-case conditions, at the closest





The next figure shows the noise modelling results with mill located in the previously proposed location as well as a number of critical receptors.



The receptor that will be most negatively affected by moving the mill related noise sources 500 metres to the northwest will be NR30. The mill will be roughly 300 metres closer to NR30. The table following shows the impact of all the mill related noise sources at NR30.



The impact of all the mill related sources at NR30 is 17 and 28 decibels for regular and emergency operations respectively. The new proposed mill location is roughly 300 metres closer to NR30. The average distance of the mill related sources is 2515 metres from the previously proposed mill location. The simple noise to distance attenuation is calculated by the formula:

$$20 \log (R2/R1)$$

Where: R1 is the distance to the first receptor from the source  
R2 is the distance to the second receptor from the source

Thus:

$$20 \log (2515/2215) \\ = 1.1 \text{ dBA}$$

The approximate impact at NR30 from the sources related to the new mill location is 29 dBA. The modelled noise impact from all sources at NR30 was 34 dBA with the mill in the new location the impact from all sources will be below 35 dBA which is still well below the provincial nighttime guideline of 40 dBA.

Please note that the 1.1 dBA increase is only related to the mill sources. The impacts at NR30 are still dominated by other sources so the cumulative increase is much less than 1.1 dBA.

The previously modelled impact at NR3, which is the closest receptor to the site, was 40 dBA. The old mill location was within one kilometer to NR3 and the new location will be roughly 1200 metres away. The noise impact will likely be below 40 dBA at this location now.

In conclusion, the proposed new mill location will not cause any of the critical receptors to be above noise criteria values and may improve conditions at the worst-case receptor.





## CLOSING

In general, the new proposed mill location will have benefits in terms of air quality and noise at the most greatly impacted receptors.

Those receptors that will now be closer to the mill will have imperceptible changes in noise impacts. All receptors will be below noise criteria.

In terms of Air Quality (particulate) impacts, the receptors to the west will infrequently experience very small increases in particulate levels over what was predicted with the old mill location. The predicted levels will still be well below Air Quality criteria.

Yours very truly,  
<Original signed by>

John DeYoe, B.A., d.E.T.   
Senior Consultant / Air Quality Specialist / Principal

JD/klm


---

<sup>i</sup> Goliath Gold Project, Wabigoon, Ontario, Final Report, Environmental Air Quality Assessment, RWDI #1401701  
October 16, 2014.

<sup>ii</sup> Treasury Metals Inc. – Goliath Gold Project, Wabigoon, Ontario, Final Report, Environmental Noise Assessment, RWDI #1401701, October 16, 2014.

<sup>iii</sup> Treasury Metals Incorporated, Goliath Gold Project, Wabigoon, Ontario, **Final Report Emission Summary and Dispersion Modelling Report**, RWDI #1401701, October 16, 2014.

<sup>iv</sup> Treasury Metals Incorporated, Goliath Gold Project, Wabigoon, Ontario, Final Report, Acoustic Assessment Report, RWDI #1401701, October 16, 2014.



**LEGEND**

- Plant\_Site\_Old
- Plant\_Site\_New
- - - Hydro Line
- · · · · Natural Gas Pipeline
- Railway
- Expressway / Highway
- Local Road
- Resource / Recreation Road
- ▨ Provincial Parks
- Contours (10 meters)
- Waterbody
- · - · - Intermittent Watercourse
- Permanent Watercourse

**GOLIATH GOLD PROJECT  
DRYDEN, ON, CANADA**

**RWDI GA Changes**

FIGURE: TBD      REV.00

SCALE:7500

**TREASURY METALS INC.**

DESIGN: MP 26 JAN. 2017  
 GIS: MP 26 JAN. 2017  
 CHECK: MW 26 JAN. 2017  
 REVIEW: DB 26 JAN. 2017

0      200      400      600      800      1,000

Meters

N

**REFERENCE AND NOTES**

Data by Treasury Metals Inc.  
 Projection: NAD83 UTM Zone 15N  
 Note: Project details are subject to change during final engineering design

**Figure 1**



Treasury Metals  
Revised EIS Report  
Goliath Gold Project  
August 2017



**APPENDIX H-2**  
**NOISE BASELINE STUDY**





CONSULTING ENGINEERS  
& SCIENTISTS

Tel: 519.823.1311  
Fax: 519.823.1316

RWDI AIR Inc.  
650 Woodlawn Road West  
Guelph, Ontario, Canada  
N1K 1B8



## Treasury Metals Inc. - Goliath Gold Project Dryden, Ontario

# Final Report

## Noise Baseline Study

RWDI #1300747  
January 23, 2014

### SUBMITTED TO:

**Mark Wheeler, P.Eng.**  
Senior Mining Engineer  
[mark@treasurymetals.com](mailto:mark@treasurymetals.com)

**Treasury Metals Inc.**  
130 King Street West, Suite 3680  
PO Box 99, The Exchange Tower  
Toronto, ON M5X 1B1

T: (416) 214-4654

### SUBMITTED BY:

**Nicole Korba**  
Project Manager  
[Nicole.Korba@rwdi.com](mailto:Nicole.Korba@rwdi.com)

**RWDI AIR Inc.**  
650 Woodlawn Road West  
Guelph, ON N1K 1B8

T: (519) 823-1311 x 2081  
F: (519) 823-1316

This document is intended for the sole use of the party to whom it is addressed and may contain information that is privileged and/or confidential. If you have received this in error, please notify us immediately.

© RWDI name and logo are registered trademarks in Canada and the United States of America



## TABLE OF CONTENTS

---

<b>1. INTRODUCTION.....</b>	<b>1</b>
1.1 Overview of Goliath Gold Project.....	1
<b>2. ENVIRONMENTAL NOISE.....</b>	<b>1</b>
<b>3. ASSESSMENT CRITERIA .....</b>	<b>3</b>
<b>4. BASELINE SOUND LEVEL ASSESSMENT .....</b>	<b>3</b>
4.1 Equipment.....	3
4.1.1 Data Validation .....	4
<b>5. BASELINE MONITORING RESULTS AND DISCUSSION .....</b>	<b>4</b>
<b>6. CONCLUSION .....</b>	<b>5</b>
<b>7. REFERENCES.....</b>	<b>6</b>

### Tables

---

Table 1:	Typical Ranges of Commonly Encountered Sound Levels
Table 2:	Acceptable Meteorological Conditions
Table 3:	2011 Baseline Monitoring Results
Table 4:	2013 Baseline Monitoring Results

### Figures

---

Figure 1:	Monitoring Station Locations Near the Project Site
Figure 2:	Noise Monitoring Locations
Figure 3:	Long-Term Measurement Results Measured Ambient Sound Levels From Dec 5, 2011 to Dec 6, 2011
Figure 4:	Long-Term Measurement Results Measured Ambient Sound Levels From Dec 6, 2011 to Dec 6, 2011
Figure 5:	Long-Term Measurement Results Measured Ambient Sound Levels From Dec 7, 2011 to Dec 7, 2011
Figures 6a-c:	Long-Term Measurement Results - Site 1 Measured Ambient Sound Levels From July 3, 2013 to July 9, 2013
Figures 7a-c:	Long-Term Measurement Results - Site 2 Measured Ambient Sound Levels From July 3, 2013 to July 9, 2013
Figures 8a-c:	Long-Term Measurement Results - Site 3 Measured Ambient Sound Levels From July 3, 2013 to July 9, 2013



CONSULTING ENGINEERS  
& SCIENTISTS

## 1. INTRODUCTION

---

Treasury Metals Incorporated (Treasury) has been exploring and developing the Thunder Lake Gold deposit known as the Goliath Gold Project (the Project), located near Dryden, Ontario in the Kenora Mining District (Figures 1 and 2). Treasury continues to develop the Project towards Feasibility Status through: Environmental Baseline Studies which were initiated in Fall of 2010 and are ongoing.

The purpose of this report is to summarize the existing baseline conditions in the study area of the Project in terms of environmental noise.

### 1.1 Overview of Goliath Gold Project

The Project is located in northwestern Ontario, approximately 125 kilometers (km) east of the City of Kenora, 20 km east of the City of Dryden and 325 km northwest of the City of Thunder Bay. The total area of the Project is 4,991 hectares (50 km<sup>2</sup>) covering portions of Hartman and Zealand townships east of the city of Dryden, Ontario.

Treasury has undertaken a 30,000 meter diamond drill program and has several development stage programs underway at the Project. In 2010, A.C.A. Howe International completed an Independent Preliminary Economic Assessment on the deposit and made recommendations for the further project development.

Treasury began an exploration program in 2008 and has not previously undergone any environmental or advanced exploration/mine permitting processes. No other exploration work has been completed on the Thunder Lake Property or the Laramide Property since 1999 and 1994, respectively. Underground and diamond drill hole sampling has previously taken place at both properties (A. C. A. Howe, 2010).

The proposed mining development is focused on the Thunder Lake Deposit. Operations will start initially with surface methods and follow with underground mining production from Year 3 to Year 10. A mill with gravity separation followed by carbon-in-leach circuit (CIL) is proposed for mineral processing (A. C. A. Howe, 2012).

## 2. ENVIRONMENTAL NOISE

---

Environmental sound levels vary continuously over time. To account for both daily and short-term variations in sound levels, several single numerical descriptors have been developed based on large-scale psycho-acoustic studies of annoyance with environmental noise. These allow sound monitoring to be conducted for a constantly varying sound environment over an extended period, with the results described as a single number that accurately describes the environment.

The single number descriptor commonly used in most international standards for environmental sound measurements is the energy equivalent sound level ( $L_{EQ}$ ). The  $L_{EQ}$  value, expressed in dBA, is the energy-averaged, A-weighted sound level for the complete measurement interval. It is the steady, continuous sound level over a given period that has the same acoustic energy as the actual varying



CONSULTING ENGINEERS  
 & SCIENTISTS

sound levels occurring over the same period in the measured environment. It is one of the most common and useful predictors of human response to noise, and is also one of the noise descriptor that is used in the majority of environmental sound level criteria. The A-weighting accounts for the frequency content of the measured sound based on a frequency response similar to that perceived by the human ear.

The descriptors specific to this study are  $L_{EQ\ 1-hr}$ ,  $L_{MAX}$  and  $L_{MIN}$ . The  $L_{EQ\ 1-hr}$  is the 1-hour A-weighted energy equivalent sound level,  $L_{EQ\ 1-hr}$ , referred to as the hourly sound level. The  $L_{MAX}$  is the maximum sound level experienced during the monitoring program. The  $L_{MIN}$  is the minimum sound level experienced during the monitoring program.

Ranges of typical everyday sounds are presented in Table 1.

**Table 1:** Typical Ranges of Commonly Encountered Sound Levels

Sound Level	dBA	Common Everyday Sources
Deafening	120	Threshold of pain
	115	Maximum noise level at a hard rock concert
	110	Accelerating motorcycle at 1 m
	105	Loud auto horn at 3 m
Very Loud	100	Dance club; Maximum human vocal output at 1 m
	95	Jackhammer at 15 m
	90	Inside a noisy factory
	85	Heavy truck pass-by at 15 m
Loud	80	School cafeteria; Noisy bar
	75	Near edge of major highway; Inside automobile travelling at 60 km/h
	70	Vacuum cleaner at 1.5 m
	65	Normal human speech, i.e., an un-raised voice, at 1 m
Moderate	60	Typical background noise levels in a large department store; Hair dryer
	55	Running tap water
	50	Clothes dryer; Air conditioner
	45	Typical background noise level in an office caused by HVAC; Flowing stream
Faint	40	Typical background noise level in a library; EUB guideline for noise at 1.5 km
	35	Average whisper; Typical quiet outdoors
	30	Broadcast studio
	25	
Very Faint	20	Deep woods on a calm day
	15	
	10	
	5	Human breathing
	0	Threshold of hearing, i.e., quietest sound that can be heard

### 3. ASSESSMENT CRITERIA

---

In Class 3 areas, described as rural or recreational, the applicable MOE “Stationary Source” guidelines are those set out in MOE Publication NPC-232 (MOE, 1995). These guidelines state that one-hour sound exposures ( $L_{EQ, 1-hr}$  dBA values) from stationary noise shall not exceed that of the background, where the background is defined as the sound level present in the environment produced by noise sources other than those associated with the facility under assessment. The MOE Publication NPC-232 sound level limits are outlined as follows:

- The higher of 45 dBA or background noise, during the daytime hours (0700-1900h);
- The higher of 40 dBA or background noise, during the evening hours (1900-2300h); and
- The higher of 40 dBA or background noise, during the night-time hours (2300-0700h).

The applicable guideline limit is the higher of the measured background sound level and the MOE’s minimum sound level limit. The above default sound level limits are the applicable for the receptors surrounding the Project. Background ambient sound level measurements were conducted and are summarized in Section 4.

### 4. BASELINE SOUND LEVEL ASSESSMENT

---

The basic procedures for the baseline assessment consists of long-term background sound level measurements of receptors near the Project, validation of measured hourly data based on weather information, and comparing the validated lowest hourly sound level data to the default guideline limits.

Long-term measurements of background ambient sound levels at one location was conducted from December 5 to December 7, 2011, near the Project Site noted in Figure 1. Additional monitoring at three representative locations was conducted from July 3 to July 9, 2013, shown in Figure 2. All measurements were conducted in accordance with the applicable requirements of MOE Publication NPC-103 (MOE, 1977b).

#### 4.1 Equipment

Sound level readings were obtained using a Larson-Davis Model 820 precision integrating sound level meters, configured to log  $L_{EQ}$  (5 minute) levels during the 2011 monitoring and configured to log  $L_{EQ}$  (1 hour) levels during the 2013 monitoring. This unit meets IEC 61672 (IEC, 2002) Class I sound level meter requirements, and Ontario Ministry of the Environment Publication NPC-102 requirements (MOE, 1977a). The sound level meters were field-calibrated at the beginning and end of measurements to ensure accuracy for all monitoring events.

A PCB Model 377A60 microphone was used at each monitoring location to ensure adequate low-level response (with a “noise floor” of approximately 20 dBA). Each microphone was mounted on a tripod, with the microphone located approximately 1.5 m above grade. Environmental microphone kits were used to provide protection from wind and rain. Each kit includes a wind screen with bird spikes to reduce wind





CONSULTING ENGINEERS  
& SCIENTISTS

noise and interference from birds. Desiccants were used to sustain dryness of the environmental kit to prevent damage from rain.

Weather data were obtained from the nearest Environment Canada meteorological station located in Dryden, Ontario. This station recorded wind speed, wind direction, temperature and relative humidity on an hourly basis.

#### 4.1.1 Data Validation

Data collected from the sound level meters were analyzed to determine the baseline conditions. Only data with meteorological conditions complying with MOE NPC-103 criteria during the measurement period have been used in the analysis of background sound levels. Acceptable meteorological conditions are shown in Table 2.

**Table 2:** Acceptable Meteorological Conditions

Parameter	Lower Limit	Upper Limit
Temperature	-20°C	40°C
Wind Speed	-	20 km/h
Relative Humidity	-	95 %
Precipitation	-	0 mm/h

Periods of short duration high-level events resulting from human activity or wind gust are excluded from the analysis. Audio recording was not conducted as part of this program and, therefore validation of the activities during these short duration high-level events was not possible. The measured sound levels from these events were excluded from the analysis. This is a conservative approach to determining the lowest background sound levels. Highway traffic noise from the Trans-Canada Highway was steady resulting in a continuous background sound and was therefore not excluded for the 2011 analysis.

## 5. BASELINE MONITORING RESULTS AND DISCUSSION

The study area is in a rural location outside a small northern community with low levels of human activity. Background ambient sound levels in remote areas are typically low, ranging from about 25 to 40 dBA. These values are similar to those measured for the Project. Tables 3 and 4 show the measured ambient noise values for each monitoring event. Each table summarizes the measured ambient sound levels and the resultant guideline limits. The sound from these levels would be described as faint (see Table 1). The measured ambient sound levels are lower than the NCP-232 guideline minima; therefore, for the purposes of this study, the NCP-232 guideline minima will be used as the sound level criteria for the detailed impact assessment.



**Table 3:** 2011 Baseline Monitoring Results

	$L_{EQ}$ (1hr)	Min	Max	NPC-232 Guideline Minima	Resultant Limit
Day	28	20	54	45	45
Evening	34	23	50	40	40
Night	30	19	66	40	40

Noise observed during the study consisted of most wind, small animals, bird noise and noise from the TransCanada Highway which runs in near proximity to the study area. The difference between daytime and nighttime sound levels were generally small, and are attributed mainly to very low level of noise from human activity which could not be screened out. Figures 3 through 5 graphically display the measured  $L_{EQ}$ ,  $L_{MIN}$  and  $L_{MAX}$  for the duration of the 2011 study.

**Table 4:** 2013 Baseline Monitoring Results

Location	Time Period	$L_{EQ}$ (1hr)	$L_{MIN}$ (1hr)	$L_{MAX}$ (1hr)	MOE NPC-232 Guideline Minima	Resultant Limit
Site 1	Day	39	30	70	45	45
	Evening	38	30	66	40	40
	Night	35	29	67	40	40
Site 2	Day	38	20	68	45	45
	Evening	37	27	63	40	40
	Night	32	19	68	40	40
Site 3	Day	32	21	69	45	45
	Evening	35	24	69	40	40
	Night	28	20	62	40	40

**Notes:** Daytime time period – 0700-1900 hours  
 Evening time period – 1900-2300 hours  
 Night time period – 2300-0700 hours

Figures 6a through 8c graphically display the measured  $L_{EQ}$ ,  $L_{MIN}$  and  $L_{MAX}$  with weather exclusions for the duration of the 2013 study at each of the three locations.

## 6. CONCLUSION

This report has presented a summary of the current noise levels in the vicinity of the Project site. The noise measurement results indicate that the existing baseline sound levels did not exceed the sound level limits as outlined in the MOE Publication NPC-232. Based on our review of the data, it appears that the existing baseline conditions are typical of Northwestern Ontario conditions.



CONSULTING ENGINEERS  
& SCIENTISTS

## 7. REFERENCES

---

A. C. A. Howe International Limited. 2010. *Technical Report and Preliminary Economic Assessment on the Goliath Gold Project*.

A. C. A. Howe International Limited. 2012. *Preliminary Economic Analysis of the Goliath Gold Project*.


Ontario Ministry of the Environment (MOE), 1995, Publication NPC-232 "Sound Level Limit for Stationary Sources in Class 3 Areas (Rural)".

Ontario Ministry of the Environment (MOE), 1977b, Publication NPC-103 "Procedures".

International Electrotechnical Commission (IEC), 2002, IEC Standard 61672-1 "Electroacoustics – Sound level meters – Part 1: Specifications".

Ontario Ministry of the Environment (MOE), 1977a, Publication NPC-102 "Instrumentation".

# FIGURES



**Legend**

- ★ Project Site
- ⊙ Environment Canada Monitoring Station
- ⊙ RWDI Noise Monitoring Station

**Monitoring Station Locations  
Near the Project Site**

Goliath Gold - Zealand Township, Ontario

Source: Basemap and Town Locations from ESRI and its Licensor(s) 2011



Drawn by: JFV Fig: 1


Approx. Scale: 1:428,633

Date Revised: Jan. 30, 2012



Project #1200542





Noise Monitoring Locations


Map Projection: NAD 1983 UTM Zone 15N.



Drawn by: CAM	Figure: 2
Approx. Scale: 1:40,000	
Date Revised: July 30, 2013	



# Long-Term Measurement Results



////// Excluded (Met. or Other) — Lmin — Lmax —▲— L(1) —▲— L(5) —●— L(10) —○— L(50) —■— L(90) —□— L(99) ——— Leq

## Measured Ambient Sound Levels

From Dec 5, 2011 to Dec 6, 2011

Goliath Gold


Figure No. **3**

Date: Jan 18, 2012

Project # 1200542

# RWDI

# Long-Term Measurement Results



////// Excluded (Met. or Other)    — Lmin    — Lmax    —▲— L(1)    —△— L(5)    —●— L(10)    —○— L(50)    —■— L(90)    —□— L(99)    ——— Leq

**Measured Ambient Sound Levels**

From Dec 6,2011 to Dec 6,2011

Goliath Gold

Project # 1200542


Figure No. **4**

Date: Jan 18, 2012





# Long-Term Measurement Results



////// Excluded (Met. or Other) — Lmin — Lmax —▲— L(1) —△— L(5) —●— L(10) —○— L(50) —■— L(90) —□— L(99) ——— Leq

**Measured Ambient Sound Levels**

From Dec 7, 2011 to Dec 7, 2011

Goliath Gold


Figure No. **5**

Date: Jan 18, 2012

Project # 1200542



# Long-Term Measurement Results Site 1



Exclude
  Minimum Sound Levels
  Leq
  Lmax
  Lmin

**Measured Ambient Sound Levels**  
From 03/07/2013 12:58:27 PM to 05/07/2013 2:00:00 PM


Figure No. 6a

Date: Aug. 01, 2013

Project # 1300747



# Long-Term Measurement Results Site 1



Exclude
  Minimum Sound Levels
  Leq
  Lmax
  Lmin


**Measured Ambient Sound Levels**  
From 05/07/2013 2:00:00 PM to 07/07/2013 4:00:00 PM

Figure No. **6b**  
Date: Aug. 01, 2013



Project # 1300747

# Long-Term Measurement Results Site 1



Exclude
  Minimum Sound Levels
  Leq
  Lmax
  Lmin

**Measured Ambient Sound Levels**  
From 07/07/2013 4:00:00 PM to 09/07/2013 1:00:00 PM


Figure No. 6C

Date: Aug. 01, 2013

Project # 1300747



# Long-Term Measurement Results Site 2



Exclude
  Minimum Sound Levels
  Leq
  Lmax
  Lmin

**Measured Ambient Sound Levels**  
From 03/07/2013 12:17:12 PM to 05/07/2013 2:00:00 PM


Figure No. 7a

Date: Jul. 26, 2013

Project # 1300747



# Long-Term Measurement Results Site 2



Exclude
  Minimum Sound Levels
  Leq
  Lmax
  Lmin


**Measured Ambient Sound Levels**  
From 05/07/2013 2:00:00 PM to 07/07/2013 4:00:00 PM

Figure No. 7b  
Date: Jul. 26, 2013



Project # 1300747

## Long-Term Measurement Results Site 2



Exclude
  Minimum Sound Levels
  Leq
  Lmax
  Lmin

**Measured Ambient Sound Levels**  
From 07/07/2013 4:00:00 PM to 09/07/2013 1:00:00 PM


Figure No. 7C

Date: Jul. 26, 2013

Project # 1300747



## Long-Term Measurement Results Site 3



Exclude
  Minimum Sound Levels
  Leq
  Lmax
  Lmin

**Measured Ambient Sound Levels**  
From 03/07/2013 11:13:41 AM to 05/07/2013 1:00:00 PM

Figure No. 8a

Date: Aug. 01, 2013


Project # 1300747







## Long-Term Measurement Results Site 3



Exclude
  Minimum Sound Levels
  Leq
  Lmax
  Lmin

**Measured Ambient Sound Levels**  
From 07/07/2013 3:00:00 PM to 09/07/2013 12:00:00 PM

Figure No. 8C

Date: Aug. 01, 2013

Project # 1300747





Treasury Metals  
Revised EIS Report  
Goliath Gold Project  
August 2017



### **APPENDIX H-3**

## **ACOUSTIC ASSESSMENT REPORT**



CONSULTING ENGINEERS  
& SCIENTISTS

Tel: 519.823.1311  
Fax: 519.823.1316

RWDI AIR Inc.  
650 Woodlawn Road West  
Guelph, Ontario, Canada  
N1K 1B8



Treasury Metals Incorporated  
Goliath Gold Project  
Wabigoon, Ontario

# Final Report

## Acoustic Assessment Report

RWDI #1401701  
October 16, 2014

### SUBMITTED TO:

**Mark Wheeler, P.Eng.**  
Senior Mining Engineer  
[mark@treasurymetals.com](mailto:mark@treasurymetals.com)

**Treasury Metals Incorporated**  
130 King Street West, Suite 3680  
PO Box 99, The Exchange Tower  
Toronto, ON M5X 1B1

### SUBMITTED BY:

**Melissa Annett, d.E.T.**  
Project Manager / Associate  
[melissa.annett@rwdi.com](mailto:melissa.annett@rwdi.com)

**John DeYoe, B.A., d.E.T.**  
Senior Specialist / Principal  
[john.deyoe@rwdi.com](mailto:john.deyoe@rwdi.com)

**Kyle Hellewell, P.Eng.**  
Senior Engineer  
[kyle.hellewell@rwdi.com](mailto:kyle.hellewell@rwdi.com)

**Khalid Hussein, B.Eng.**  
Project Scientist  
[khalid.hussein@rwdi.com](mailto:khalid.hussein@rwdi.com)

This document is intended for the sole use of the party to whom it is addressed and may contain information that is privileged and/or confidential. If you have received this in error, please notify us immediately.

© RWDI name and logo are registered trademarks in Canada and the United States of America



## EXECUTIVE SUMMARY

---

Treasury Metals Incorporated retained RWDI AIR Inc. to complete an Acoustic Assessment Report in support of the Goliath Gold Project. The Project is a proposed gold mine near Wabigoon, Ontario. This assessment has been completed in support of an application for an Environmental Compliance Approval with Limited Operational Flexibility.

This assessment focuses on sound emissions from sources at the facility and their potential effect on worst-case sensitive receptors surrounding the facility. Sources at the facility include: ventilation equipment, process exhausts, mobile heavy equipment, and rock crushing equipment. Data for the predictable worst-case operations were described using one operating scenario representative of a predictable worst-case hour during the worst-case project year. Sound levels from the facility were assessed by detailed modelling using the Cadna/A software package. Airborne and Ground-borne vibrations due to blasting activities were assessed using guidance from NPC-119 (MOE, 1977) and Guidelines on Information Required for the Assessment of Blasting Noise and Vibration (MOE, 1985).

Modelling inputs include source type and locations, and sound levels. Source types and locations were taken from information provided in the Goliath Gold project description, and from Treasury Metals personnel. Sound levels were taken from information on file at RWDI, or were calculated based on equipment specifications. At this early stage of development, information can be limited therefore, where necessary, modelling has been conducted using sound levels for typical sources at a mine.

Noise sensitive receptors identified in the area are houses (seasonal or otherwise). Forty-four individual receptors were identified. Noise modelling software was used to predict the effects of the Project at the nearest receptors, representing the worst case impacts.

In some circumstances, sound levels of specific sources were found to cause noncompliance at noise sensitive receptors. Quieter than average equipment will be required for some pieces to achieve compliance. This equipment is commercially available. Treasury Metals has committed to ensuring that sound levels from these pieces of equipment meet these requirements.

Vibrations from blasting activities is predicted to be in compliance with NPC-119 at all sensitive receptors. Based on the commitment described above to limit sound levels of certain equipment, the Goliath Gold Project is predicted to be in compliance with the Ministry of Environment and Climate Change guidelines at all receptors.



## TABLE OF CONTENTS

---

<b>1. INTRODUCTION.....</b>	<b>1</b>
<b>2. FACILITY DESCRIPTION .....</b>	<b>1</b>
<b>3. NOISE SOURCE SUMMARY .....</b>	<b>2</b>
3.1 Insignificant Sources .....	2
3.2 Continuous Sources .....	2
3.3 Identifiable Source Characteristics.....	4
3.4 Operating Scenarios .....	5
<b>4. POINT OF RECEPTION SUMMARY .....</b>	<b>5</b>
<b>5. ASSESSMENT CRITERIA .....</b>	<b>6</b>
5.1 Exclusion Limits.....	6
5.2 Blasting.....	7
<b>6. IMPACT ASSESSMENT.....</b>	<b>8</b>
6.1 Assessment of Sound Levels.....	8
6.1.1 Continuous Sources .....	8
6.1.2 Blasting Noise.....	8
6.2 Assessment of Vibration Levels .....	10
<b>7. CONCLUSIONS.....</b>	<b>10</b>
<b>8. REFERENCES.....</b>	<b>11</b>

## Tables

---

Table 1:	Noise Source Summary
Table 2:	Point of Reception Noise Impact
Table 3A:	Acoustic Assessment Summary for Continuous Sources
Table 3B:	Acoustic Assessment Summary for Emergency Sources
Table 3C:	Acoustic Assessment Summary for Blasting Sources
Table 3D:	Vibration Assessment Summary for Blasting Sources

## Figures

---

Figure 1:	Source Locations
Figure 2:	Sensitive Receptor Locations
Figure 3:	Predicted Sound Level Contours for Normal Operations
Figure 4:	Predicted Sound Level Contours for Emergency Source Testing





## Appendices

---

- Appendix A: Acoustic Assessment Report Checklist  
Noise Screening Process for S.9 Applications
- Appendix B: Noise Source Data  
Source Level Data and SPL to PWL Conversions  
Manufacturer's Sound Data  
Engineering Calculations
- Appendix C: Sound Level Measurement Equipment Information  
Measurement Weather Conditions
- Appendix D: Key Parameters Included in Cadna/A Noise Modelling  
Sample Cadna/A Modelling Output



CONSULTING ENGINEERS  
& SCIENTISTS

## 1. INTRODUCTION

---

Treasury Incorporated has retained RWDI AIR Inc. (RWDI) to complete an acoustic assessment and Acoustic Assessment Report (AAR) for the Goliath Gold Project (the Project) located near Wabigoon, Ontario. This AAR is completed using the applicable MOE guidance documents (MOE, 2012 and MOE, 1995). A copy of the Acoustic Assessment Report checklist is included in Appendix A. This assessment has been completed in support of an application for an Environmental Compliance Approval with Limited Operational Flexibility.

The MOECC Primary Noise Screening has been completed for this facility, and is included in Appendix A. The NAICS code for this facility is 21222. A detailed assessment is required because sensitive receptors are located within the setback distance provided by the Primary Noise Screening. All land within several kilometers of the Project is crown land, or is unincorporated land, and therefore has no zoning information available.

This assessment focuses on sound levels due to the Project at surrounding worst-case sensitive receptors. Sources at the facility include: ventilation equipment, building exhausts, on site vehicle traffic, and rock crushing equipment.

Operations at the Project do not include large sources of vibration, with the exception of blasting activities. An evaluation of blasting activities is included in section 6.

## 2. FACILITY DESCRIPTION

---

Treasury Metals Incorporated (Treasury) has been exploring and developing the Thunder Lake Gold deposit known as the Goliath Gold Project (the Project), located near Wabigoon, Ontario. The Project involves the construction, operation, closure, and reclamation of a 4.5 million tonne-per-annum (Mt/a) open pit and underground mine that will operate for approximately 15 years. The site includes three open pits that will be mined sequentially, a mill building for ore processing and a tailings area. With the exception of blasting and generator testing, which will occur during daytime hours only, all noise sources associated with the Project may operate 24 hours a day, seven days a week.

Construction and Site Preparation phases will include tree clearing, grubbing, stripping of overburden, crushing of aggregate for road construction, blasting, and construction of project facilities. The duration of the Site Preparation and the Construction phase is estimated to be 3 years. The majority of noise sources during this phase will be mobile equipment operating at grade.

The operations phases will include both underground and open face mining activities. The open face mining activities include drilling, blasting, dozing, excavating and the transportation of rock material around site. The underground activities include the operation of intake and exhaust vent raises and the transportation of rock material to the surface. The processing plant, or mill, will include several stationary noise sources related to ventilation and process exhausts. Emergency power generators are to be tested only during the daytime hours. The duration of the operations phase is estimated to be 10 years.



CONSULTING ENGINEERS  
& SCIENTISTS

Closure, Decommissioning and Restoration phases will include backfilling and flooding of the open pits and underground mine area, disassembling of infrastructure and equipment as well as overall site maintenance. The duration of the Closure, Decommissioning and Restoration phase is estimated to be 2 years. The majority of noise sources during this phase will be mobile equipment operating at grade.

### 3. NOISE SOURCE SUMMARY

---

Details regarding types of equipment used during the operations phase were limited at the time of this assessment. Best-available data regarding noise sources for future construction, operations, and decommissioning were collected from Treasury Metals, and used to predict sound levels for the Project. The significant sources were identified from drawings and the project description provided to RWDI by Treasury. No significant impulsive sources were identified with the exception of blasting which is assessed separately.

#### 3.1 Insignificant Sources

At the time of assessment, detailed drawings for construction had not been developed. Details of small exhausts serving areas such as break rooms, washrooms, and storage areas were therefore not available. Such sources typically have sound power levels less than 80 dBA and were considered to be insignificant. A small amount of comfort heating and cooling has also been considered to be insignificant.

Movements of light vehicles (pickup trucks, vans, cars, etc.) traveling on site are unpredictable. With the limited operating times of these vehicles, and relatively low power levels compared to other sources on site, these sources have been considered insignificant. A weekly armored vehicle trip removing gold from the site has similarly been considered insignificant.

A summary of modelled sources is included in Table 1 in the tables section; detailed source information is included in Table B.1 of Appendix B. Source locations are shown in Figure 1.

#### 3.2 Continuous Sources

Sound power level data for continuous sources was obtained by measurements, engineering calculations, manufacturer's data, and sound levels for similar equipment on file at RWDI.

Sound pressure level (SPL) measurements were conducted for the operation of an exploration drill during a site visit on April 22, 2014. This data was used to represent the operations drills, sources OP\_DRILL1\_o and OP\_DRILL2\_o). Sources (OP\_DRILL1\_o and OP\_DRILL2\_o) were both time-weighted to operate for 30 minutes per hour in order to provide a realistic representation of drilling operations on site. All measurements were consistent with ISO 3744:1994(E) (ISO, 1994a), and ISO 3746:1995(E) (ISO, 1995) measurement standards, and the applicable portions of the MOE Publication NPC-103 (MOE, 1978). The measured SPLs were converted into PWLs based on measurement distances and the size of the equipment being measured, as appropriate.



CONSULTING ENGINEERS  
& SCIENTISTS

The sound power levels for the dewatering pump, and aeration tank blower (sources OP\_Dpump1\_o, and ML\_Blwr\_o) were calculated based on typical specifications and information provided by Treasury. The dewatering pump was calculated with the pump operating at 180m water column of static pressure. This is the representative sound level of the pump when the pit is at its deepest level of excavation, and conservative for when the pump is near ground level. Calculations of source sound power level and octave band spectra for the aeration tank blower and the dewatering pump were made using equations provided by Crocker (Crocker, 2007) and Bies and Hansen (Bies, 2009) respectively. Calculations are shown in Appendix B.

The sound power level for the exhaust louvers on the mill building (sources ML\_ExLvr01\_o through ML\_ExLvr14\_o) were calculated assuming an indoor sound power level of 85 dB within the mill facility. This is a typical objective for indoor sound levels in order to comply with occupational health and safety regulations. The locations of these sources were unknown and thus the sources were distributed evenly around the building. The number of exhaust openings was calculated based on a minimum of 6 air changes per hour, and based on the approximate volume of the building. The sound power level of these sources includes the sound from a fan in each opening, sized to accommodate the required air changes. The fan sound power level was calculated using equations from Crocker (Crocker, 2007). Each modelled point source includes indoor noise radiating through an intake, indoor noise radiating through an exhaust, and the sound from a fan at the exhaust opening.

The PWLs for the generators, kiln fan and intake and exhaust vent raises (sources Gen150\_e, Gen600\_e, ML\_KF\_o, UG\_ExVentRaise1\_o, UG\_ExVentRaise2\_o and UG\_VentRaise1\_o respectively) were approximated based on the manufacturer's PWL data for similar equipment. The sound power level data for UG\_VentRaise1\_o and UG\_ExVentRaise1\_o was taken from a manufacturer data sheet for a fan similar to that which would typically be used for this purpose. At UG\_ExVentRaise2\_o these sound power levels were found to result in noncompliance. The sound level of the fan has been reduced by 5 dB for UG\_ExVentRaise2\_o. Treasury Metals is committed to selecting equipment which is less than or equal to the sound power level used in the modelling for this source. The manufacturer's PWL data is included in Appendix B.

The sound data used for following sources were taken from measurements of similar equipment on file at RWDI.

- Rock drop from trucks and loaders (sources ML\_Rckdrp\_o, OP\_Rckdrp\_lowgrade\_o, OP\_Rckdrp\_overburden\_o, and OP\_Rckdrp\_waste\_o);
- Front End Loader (source ML\_ldr\_o);
- Bulldozers (source OP\_DZR\_lowgrade\_o, OP\_DZR\_overburden\_o, OP\_DZR\_waste\_o);
- Jaw crusher (source Crshr);
- Hydraulic Excavators (sources OP\_Excvt1\_o, OP\_Excvt2\_o); and
- 50 Ton Haul Trucks (sources Htruck1\_o, Htruck2\_o, Htruck3\_o).



CONSULTING ENGINEERS  
& SCIENTISTS

The evaluation of noise impacts is based on the principle of worst-case hour. Where sources operate for less than an hour, the sound level of the source is weighted to account for reduced operation. Sources (OP\_DZR\_lowgrade\_o and OP\_DZR\_overburden\_o) were time-weighted at 30 minutes per hour to account for the dozer operating at both the low grade and overburden stockpiles in a given worst-case hour. The front end loader at the run of mine pad is limited to operating 30 minutes per hour. This is due to the periodic nature of rock material drops offs at the pad. Rock drop noise represents the noise from rocks being dumped from trucks and loaders. This activity was time weighted, as it is periodic. Details on time weighting for all sources are provided in Table B.1.

In some circumstances, sound levels of specific sources modelled from data on file were found to cause noncompliance at noise sensitive receptors. This data is representative of average equipment, and does not represent quieter equipment currently available. Quieter than average equipment will be required for some pieces of heavy equipment to achieve compliance. Treasury Metals has committed to ensuring that sound levels from these pieces of equipment meet these requirements. PWLs of all equipment are outlined in Appendix B, and every effort will be made to ensure that selected equipment has sound emissions equal to or lower than the PWLs specified there.

Haul trucks traveling on site were modelled using a moving point source calculation method. A total of 14 round trips are expected in a worst case hour between the open pit, and any combination of the waste rock stockpile, low grade stockpile, and run of mine pile. The route to the waste rock stockpile is considerably longer than all other routes, and results in the highest sound level at all receptors. These trips were conservatively weighted towards having most trips in a predictable worst-case hour routed to the waste rock stockpile. Ten trucks were modelled travelling round trip between the open pit and waste rock stockpile for a total of 20 truck movements along this route. Two trucks were modelled travelling round trip between the open pit and the low grade stockpile. Two trucks were modelled travelling round trip between the open pit and run of mine pile in any worst-case hour for a total of 4 truck movements along the route. Trucks are expected to travel on the site at a speed of 30 km/h.

Measurement data and details of the SPL to PWL conversions, octave band sound power data, and manufacturer's data are included in Appendix B. Weather conditions and measurement equipment for measurements of exploration drilling are in compliance with the requirement set out in MOE Publication NPC-103 (MOE, 1978). The measurement weather conditions are summarized in Appendix C. Measurement equipment model and serial information is provided in Appendix C.

### **3.3 Identifiable Source Characteristics**

Sources that have characteristics considered to be particularly annoying receive additional consideration in accordance with NPC-104 guidelines (MOE, 1978). The adjustment is based on assessment at the point of reception, as described in Publication NPC-103. No sources were identified to exhibit annoying sound emissions.



CONSULTING ENGINEERS  
& SCIENTISTS

### 3.4 Operating Scenarios

The assessment of noise focuses on the predictable worst-case hour, during a worst-case year in the life of the Project. Based on modelling conducted for the federal Environmental Assessment, it is expected that the worst-case phase is the operating phase; the construction and decommissioning phases are predicted to generate lower sound levels. The early years which occur during the operations phase are the worst-case in the operations phase, due to an increase in activity related to the construction of the underground mine and a lack of screening from pit sources.

As an absolute worst-case during the early years of the operations phase, all sources related to the open pit mine have been modelled at grade, along with the vent raises for the underground mine operating. This discounts all shielding effects from the ultimately 180 m deep pit, and conservatively assumes that the vent raises will be operational while open pit mining is still near the surface. These conservative estimates of the worst-case operations were chosen to account for unknowns such as remediation of the open pit during underground mining activities. Those sorts of activities are anticipated to generate lesser noise than the modelled scenario.

Two emergency generators located at the site will be tested on a regular basis, during daytime hours only. With the exception of blasting, all other sources as described above may operate 24 hours per day. Two scenarios have therefore been modelled: operating phase, excluding generators, and including both open pit and underground sources, and generator testing.

## 4. POINT OF RECEPTION SUMMARY

---

Sound levels from sources at the Project were determined at points of reception (PORs) located on noise-sensitive land uses. Noise-sensitive land uses are defined in the MOECC's environmental noise guideline, publication NPC-300 (MOE, 2013), as the property of a person that accommodates a dwelling, a noise-sensitive commercial building or a noise-sensitive institutional building. Vacant lots are considered noise-sensitive, provided they are zoned to allow a sensitive use and are accessible by road. A noise-sensitive land use may have one or more receptors.

PORs for an acoustic assessment are those locations where sound from the facility is received and assessed against the applicable limits. Sound levels may be assessed at the façade of the building and/or outdoor areas, depending on the type of sensitive land use assessed. Outdoor PORs are only assessed for dwellings and are not assessed for commercial and institutional noise-sensitive land uses.

Residential receptors include houses, cottages, and the like, whether continuously occupied or seasonal. For existing residential properties, sound levels are assessed at the façade of the building at a height of 4.5 m above local grade and an outdoor POR at a height of 1.5 m. The point of assessment for the outdoor receptors is a point 30 m from the building façade, or the property line in cases where the 30 m setback would exceed the size of the property.





CONSULTING ENGINEERS  
& SCIENTISTS

Commercial and institutional receptors include hotels, churches, daycares, schools, clinics, and the like. The point of assessment for these types of receptors is at the façade of the building only; Outdoor receptors are not assessed for commercial and institutional noise-sensitive land uses.

Properties that are zoned to permit a noise-sensitive land use, but are currently vacant need to be assessed as if a noise-sensitive land use exists at that location. For these noise sensitive areas, the receptors are typically considered in a location consistent with typical local building patterns, at a height of 4.5 m above local grade. In the case of unincorporated land without a minister's zoning order, the land is generally understood to allow noise-sensitive uses, and would be assessed in the same way as land that is zoned for a noise sensitive use. All land within the vicinity of the Project is either crown land, or unincorporated land. No zoning information is available for these areas.

There is currently a house located to the West of the low grade stockpile which is owned by Treasury Metals, and will not be occupied during the life of the Project. A house located on the north west corner of Normans Rd and Nursery Rd is also owned by Treasury Metals and will not be occupied during the life of the Project. The house located approximately 400 m east of the intersection of Normans Rd and Nursery Rd, on the North side of Normans Rd is currently occupied, and will be vacated prior to the commencement of the Project.

Vacant land on the south side of Normans Rd, immediately to the south of the low grade stockpile is apparently accessible by road as judged from aerial photographs. This section of Normans Road, west of Nursery Rd, is controlled by Treasury Metals, and will result in this land being inaccessible for the life of the Project.

Forty-four individual noise-sensitive receptors were identified within the local study area. Where the surface mining rights have been secured by Treasury Metals, land use was assumed to be non-noise-sensitive and no receptors were identified. All other vacant lands in the vicinity of the Project that were found to be inaccessible (except by a rough cut-in through the forest) were not considered as receptors. Forty-two of the receptors were identified as houses. One was identified as the campground at Aaron Provincial Park. One receptor is a trailer located on otherwise vacant land. There are no receptors identified roughly within 2 km to the north or 8 km to the east, because Treasury Metals has surface rights to all land in those directions.

Since noise impacts decrease with distance from the source, the nearest receptors to the Project are considered the worst-case, and are evaluated explicitly. Other receptors are not evaluated explicitly, but effects can be seen noise contour maps. Figure 2 presents receptors that are explicitly evaluated.

## 5. ASSESSMENT CRITERIA

---

### 5.1 Exclusion Limits

The applicable guideline limits for the receptors in the vicinity of the Project are the "Stationary Source" guidelines for Class 3 area, set out in MOE Publication NPC-300. These guidelines state that one-hour sound exposures (A-Weighted hourly  $L_{EQ}$  values) from stationary sources in Class 3 area shall not



CONSULTING ENGINEERS  
& SCIENTISTS

exceed that of the background, where the background is defined as the sound level present in the environment produced by sources other than those associated with the project under assessment. The MOE Publication NPC-300 minimum sound level limits at the façade (or plane of window) are summarized as follows:

- The higher of 45 dBA or background sound, during the daytime hours (0700-1900h);
- The higher of 40 dBA or background sound, during the evening hours (1900-2300h); and
- The higher of 40 dBA or background sound, during the nighttime hours (2300-0700h).

The MOE Publication NPC-300 sound level limits at an outdoor POR are applicable during the daytime and evening hours only. These limits are summarized as follows:

- The higher of 45 dBA or background sound, during the daytime hours (0700-1900h); and
- The higher of 40 dBA or background sound, during the evening hours (1900-2300h).

The applicable criterion is the higher of the background sound level and the default minimum sound level limit. Background sound level measurements showed levels below the exclusionary limits. The minimum sound level limits are therefore applicable.

Sound from the operation of emergency equipment, such as generators, is not considered except during planned testing. Sound levels of planned testing of emergency equipment are evaluated separately from all other noise from the Project. In the case where multiple pieces of emergency equipment are tested together, their combined impact is evaluated against the limit. The sound level limits for emergency equipment operating in a testing scenario are 5 dB greater than the sound level limits presented above.

## 5.2 Blasting

Blasting is evaluated separately under MOECC guidelines. Guidance for noise from blasting is taken mainly from two publications, NPC-119 (MOE, 1978) and Guidelines on Information Required for the Assessment of Blasting Noise and Vibration (MOE, 1985).

Blasting activities are identified as a source for sound due to airborne vibration (concussion). The level of sound experienced at a receptor is assessed using the peak pressure level measured in linear (un-weighted) decibels (dB). MOE publication NPC-119 introduces two limits, the cautionary limit, and the peak pressure level limit. The cautionary limit is 120 dB and can be applied in cases where there is no monitoring of sound levels from blasting. The peak pressure limit is 128 dB, and can only be used when sound level monitoring is conducted during blasting. The cautionary limit is used as the criteria for airborne blast noise for the Project.

Blasting activities are also identified as a source of groundborne vibration. Groundborne vibration is evaluated as a peak particle velocity measured in cm/s. NPC-119 limits vibration from blasting to 1.00 cm/s at a sensitive receptor location. For this assessment, sensitive receptors for vibration impacts are considered to be the same as those described in section 4 for noise.



CONSULTING ENGINEERS  
& SCIENTISTS

## 6. IMPACT ASSESSMENT

---

### 6.1 Assessment of Sound Levels

The facility sound emissions were modelled based on the normal facility operations and emergency equipment testing operating scenarios as described in Section 3. The Sound Pressure Level (SPL) at surrounding PORs were calculated by modelling the sound propagation from the significant sources at the facility. The modelled SPLs at the PORs were assessed against the applicable sound level limits.

#### 6.1.1 Continuous Sources

Modelling of sound level propagation for continuous sources to the receptors was conducted using Cadna/A, a commercially available implementation of the ISO 9613 (ISO, 1994b and ISO, 1996) algorithms. Cadna/A is produced by Datakustik GmbH. The modelling took into account the following factors:

- Source sound power level and directivity;
- Distance attenuation;
- Source-receptor geometry including heights, elevations and topography;
- Barrier effects of the site and surrounding buildings;
- Duration of events;
- Ground and air (atmospheric) attenuation; and
- Meteorological effects on sound propagation.

A sample calculation showing step-by-step calculation parameters is provided for receptor NR03, and is included in Appendix D. Key modelling parameters are summarized in Appendix D.

The individual contributions of each source at the modelled PORs are presented in Table 2. Sound level contours (isopleths of equal sound level) were generated for normal facility operations and for generator testing and are presented in Figures 3 and 4 respectively.

The SPLs at PORs under regular facility operations and emergency equipment testing scenarios were assessed using the applicable sound level limits, as shown in Table 3a and 3b, respectively. The predicted facility-attributable levels at each POR are in compliance with the applicable limits.

#### 6.1.2 Blasting Noise

Modelling of blasting sound levels was conducted using numerical modelling techniques presented in the International Society of Explosives Engineers Blaster's Handbook (ISEE, 2011). Airborne vibration due to blasting activities attenuates from a site at a slower rate than ground vibrations. The distribution of this air vibration energy from a blast is also strongly influenced by the prevailing weather conditions during the blast. Other factors influencing airborne vibration propagation include:



CONSULTING ENGINEERS  
& SCIENTISTS

- charge-weight per delay;
- depth of burial;
- volume of displaced rock;
- delay time intervals;
- type of explosive;
- atmospheric conditions; and,
- topography.

Further definition of these terms is provided in Appendix B.

The rate at which blast noise decays or attenuates from a blast site is dependent upon the scaled distance as follows:

- scaled distance ( $SD_3$ ) =  $R / \sqrt[3]{W}$ 
  - where R = distance (metres) from the blast to a point of interest; and,
  - W = charge-weight (kilograms) detonated within any 8-millisecond delay period.

Prediction of maximum blast noise was based on the following equation which assumes average burial of the explosive:

- $P = 37.1 \times SD_3^{-0.97}$ 
  - where P = peak air pressure (Pascals); and,
  - $SD_3$  = scaled distance (metres per kilogram [ $m/kg^{1/3}$ ]).

This equation produces a pressure in pascals, which is then converted to decibels (dB) as shown in the following equation:

- $dB = 20 \log(P/P_0)$ 
  - where  $P_0$  is the reference pressure ( $2 \times 10^{-5}$  Pa).

Sound levels from blasting were evaluated separately from sounds due to continuous noise sources as per the guidance. Levels were assessed at the five worst-case receptors as discussed in section 5.2. A radius of influence was also determined, which is the distance from a blast where the sound levels will fall off to the precautionary limit. The radius of influence is 95 m in all directions from the blasting. Any receptor further than 95 m from a blast will therefore experience effects lower than the NPC-119 precautionary limit.

All levels at receptors are predicted to be in compliance with the NPC-300 minimum sound level limits for a class 3 area. The predicted sound levels and applicable limits are presented in Table 3C.



CONSULTING ENGINEERS  
& SCIENTISTS

## 6.2 Assessment of Vibration Levels

Ground vibration was calculated to determine the peak particle velocity in mm/s due to the blast. The rate at which ground vibrations decay or attenuate from a blast site can be expressed by the scaled distance, which is defined as:

- scaled distance ( $SD_2$ ) =  $R/\sqrt{W}$ 
  - where R = distance (m) from the blast to a point of interest; and,
  - W = charge-weight (kilogram) detonated within any 8-millisecond delay period.

The prediction of maximum ground vibrations can be calculated based on the following equation (ISEE 2011) for upper bound construction industries:

- $PPV = 1730 (SD_2)^{-1.6}$ 
  - where PPV = peak particle velocity (mm/s); and,
  - $SD_2$  = scaled distance (meter per kilogram [ $m/kg^{1/2}$ ]).

Vibration levels for blasting are presented in NPC-119 and are limited to 1.00 cm/s. Using this limit, the area of vibration influence for blasting was determined to be 457 m. The nearest receptors are located more than this distance away from areas where blasting is likely to occur, so blasting vibration is predicted to be in compliance with NPC-119 at all sensitive receptors. Details of the blasting vibration calculation are included in Appendix B.

## 7. CONCLUSIONS

---

A detailed assessment of the Project sound levels was completed by modelling the individual contributions of the significant sources at the representative receptors. Predicted facility sound levels and vibration levels from blasting are in compliance with the applicable guideline limits at each of the receptors for daytime, evening and nighttime operations with the inclusion of reduced sound level equipment for some sources. This assessment predicts that the Project is in compliance with the requirements of the NPC-300 and NPC-119 guidelines.



CONSULTING ENGINEERS  
& SCIENTISTS

## 8. REFERENCES

---

Bies, David A. and Hansen, Colin H., 2009. *Engineering Noise Control: Theory and Practice, Fourth Edition*. New York: Taylor & Francis.

Crocker, Malcolm J. (ed.), 2007. *Handbook of Noise and Vibration Control*. Hoboken, NJ: John Wiley & Sons Inc.

International Organization for Standardization (ISO), 1994a, International Standard ISO-3744:1994(E). *Acoustics – Determination of sound power levels of noise sources using sound pressure. Engineering method in an essentially free field over a reflecting plane*

International Organization for Standardization (ISO), 1994b, International Standard ISO 9613-1:1994, *Acoustics – Attenuation of Sound during propagation outdoors. Part 1: Calculation of the absorption of sound by the atmosphere.*

International Organization for Standardization (ISO), 1995, International Standard ISO-3746:1995(E). *Acoustics – Determination of sound power levels of noise sources using sound pressure. Survey method of using a reference sound source*

International Organization for Standardization (ISO), 1996, International Standard ISO 9613-2:1996, *Acoustics – Attenuation of sound during propagation outdoors – Part 2: General method of calculation*

International Society of Explosives Engineers (ISEE), 2011. *Blaster's Handbook*, 18th edition, Stiehr, J.F., Ohio USA.

Ontario Ministry of the Environment (MOE), 1978, *Model Municipal Noise Control Bylaw*, which includes *Publication NPC-103 – Procedures, Publication NPC-104 – Sound Level Adjustments, and NPC-119 – Blasting.*

Ontario Ministry of the Environment (MOE), 1985, *Guidelines on Information Required for the Assessment of Blasting Noise and Vibration*

Ontario Ministry of the Environment (MOE), August 2013, Publication NPC-300, *Environmental Noise Guideline Stationary and Transportation Sources – Approval and Planning*



# TABLES

**Table 1: Noise Source Summary**

Treasury Metals Inc. – Goliath Gold Project, 1401701

## Notes to Table:

- "Table A1" in Appendix A of Basic CCofA Guide.
1. Wherever possible, the Source ID matches the identifiers used in the ESDM report.
2. Sound Power Level of Source, in dBA, not including sound characteristic adjustments per NPC-104.
3. Source Location: O = Outside of building, including the roof, I = Inside of building
4. Sound Characteristic, per NPC-104:  
 - S = Steady - I = Impulsive - T = Tonal  
 - Q = Quasi-Steady Impulsive - B = Buzzing - C = Cyclic  
 Where annoying characteristics are audible at the source, but not at receptors, no penalty is applied and the characteristic in this table is shown as "S". See section 3 of the report text for further details.
5. Noise control measures currently in place or specified in construction drawings:  
 - S = Silencer/Muffler - L = Lagging - O = Other  
 - A = Acoustic lining, plenum - E = Acoustic enclosure - U = Uncontrolled  
 - B = Barrier
- Where noise control measures are specified in construction drawings or were found on existing equipment, octave band sound power levels include the effects of the noise control measures. Noise control measures recommended in the mitigation section of this report are not included in this table.

Source ID <sup>[1]</sup>	Source Description	Sound Power Level <sup>[2]</sup>	Source Location <sup>[3]</sup>	Sound Characteristics <sup>[4]</sup>	Noise Control Measures <sup>[5]</sup>
		(dBA)	(I or O)	(S,Q,I,B,T,C)	(S,A,B,L,E,O,U)
Gen150_e	150 kW Emergency Generator	113	O	S	E,S
Gen600_e	600 kW Emergency Generator	114	O	S	E,S
ML_Blwr_o	Blower	91	O	S	U
ML_Crshr_o	Jaw Crusher	99	O	S	U
ML_FEx_o	Furnace Exhaust	74	O	S	U
ML_KF_o	Kiln Fan	94	O	S	U
ML_ldr_o	Front End Loader	100	O	S	U
ML_Rckdrp_o	Rock Drop	119	O	S	U
OP_Dpump1_o	Dewatering Pump at 180m Head	101	O	S	U
OP_DRILL1_o	Drill	107	O	S	U
OP_DRILL2_o	Drill	107	O	S	U
OP_DZR_lowgrade_o	CAT D8N dozer	100	O	S	U
OP_DZR_overburden_o	CAT D8N dozer	110	O	S	U
OP_DZR_waste_o	CAT D8N dozer	110	O	S	U
OP_Excvt1_o	Hydraulic Excavator	101	O	S	U
OP_Excvt2_o	Hydraulic Excavator	106	O	S	U
OP_Rckdrp_lowgrade_o	Rock Drop	112	O	S	U
OP_Rckdrp_overburden_o	Rock Drop	112	O	S	U
OP_Rckdrp_waste_o	Rock Drop	112	O	S	U
UG_ExVentRaise1_o	Exhaust Vent Raise 1	116	O	S	U
UG_ExVentRaise2_o	Exhaust Vent Raise 2	111	O	S	U
UG_VentRaise1_o	Fresh Air Intake Vent Raise	116	O	S	U
ML_ExLvr01_o	Building Vent 1	90	O	S	U
ML_ExLvr02_o	Building Vent 2	90	O	S	U
ML_ExLvr03_o	Building Vent 3	90	O	S	U
ML_ExLvr04_o	Building Vent 4	90	O	S	U
ML_ExLvr05_o	Building Vent 5	90	O	S	U
ML_ExLvr06_o	Building Vent 6	90	O	S	U
ML_ExLvr07_o	Building Vent 7	90	O	S	U
ML_ExLvr08_o	Building Vent 8	90	O	S	U
ML_ExLvr09_o	Building Vent 9	90	O	S	U
ML_ExLvr10_o	Building Vent 10	90	O	S	U
ML_ExLvr11_o	Building Vent 11	90	O	S	U
ML_ExLvr12_o	Building Vent 12	90	O	S	U
ML_ExLvr13_o	Building Vent 13	90	O	S	U
ML_ExLvr14_o	Building Vent 14	90	O	S	U
Htruck1_o	Haul Truck #1	107	O	S	U
Htruck2_o	Haul Truck #2	107	O	S	U
Htruck3_o	Haul Truck #3	107	O	S	U

**Table 2: Point of Reception Noise Impact**  
Treasury Metals Inc. – Goliath Gold Project, 1401701

## Notes to Table:

- "Table A2" in Appendix A of Basic CCoFA Guide.
- 1. "Continuous" noise sources includes operating time corrections and sum of steady, quasi-steady impulsive, tonal, cyclical and buzzing noise sources, with appropriate penalties applied, in accordance with documents NPC-104 and NPC-300.
- 2. Wherever possible, the Source ID matches the identifiers used in the ESDM report.
- 3. Sound Level units:  
- dBA = 1-hour energy equivalent sound level (L<sub>eq</sub>(1-hr)), in terms of A-Weighted decibels.  
- dBA1 = Logarithmic mean impulsive noise level (L<sub>10</sub>), in terms of A-Weighted decibels incorporating an impulsive time weighting.
- Noise and vibration receptors representative of worst-case potential impacts have been selected. For the purposes of noise and vibration impact assessment, the following land uses (existing or zoned for future use) have been considered:
 

- permanent, seasonal, or rental residences	- hospitals and clinics
- hotels, motels and campgrounds	- schools, universities, libraries and daycare centres
- nursing / retirement homes	- churches and places of worship

Point of Reception ID NR03	Point of Reception ID NR03_O	Point of Reception ID NR04	Point of Reception ID NR04_O	Point of Reception ID NR30	Point of Reception ID NR30_O	Point of Reception ID NR44	Point of Reception ID NR44_O	Point of Reception ID NR47	Point of Reception ID NR47_O
<b>Point of Reception Description</b> House - owned by Mckelish	<b>Point of Reception Description</b> Outdoor receptor- Mckelish	<b>Point of Reception Description</b> House - owned by Nyström	<b>Point of Reception Description</b> Outdoor receptor- Nyström	<b>Point of Reception Description</b> House - East Thunder Lake Road	<b>Point of Reception Description</b> Outdoor receptor - East Thunder Lake Road	<b>Point of Reception Description</b> House - Near Trans-Canada Highway	<b>Point of Reception Description</b> Outdoor receptor - Near Trans-Canada Highway	<b>Point of Reception Description</b> House - East Thunder Lake Road	<b>Point of Reception Description</b> Outdoor receptor - East Thunder Lake Road
<b>Point of Reception Coordinates</b>	<b>Point of Reception Coordinates</b>	<b>Point of Reception Coordinates</b>	<b>Point of Reception Coordinates</b>	<b>Point of Reception Coordinates</b>	<b>Point of Reception Coordinates</b>	<b>Point of Reception Coordinates</b>	<b>Point of Reception Coordinates</b>	<b>Point of Reception Coordinates</b>	<b>Point of Reception Coordinates</b>
X Y Z	X Y Z	X Y Z	X Y Z	X Y Z	X Y Z	X Y Z	X Y Z	X Y Z	X Y Z
528986 5511403 398	528971 5511427 393	528702 5510566 395	528697 5510595 392	526424 5512462 385	526443 5512441 383	527992 5509946 385	527987 5509977 382	525866 5512101 385	525884 5512089 382

Source ID <sup>(1)</sup>	Source Description	Point of Reception 1			Point of Reception 2			Point of Reception 3			Point of Reception 4			Point of Reception 5			Point of Reception 6			Point of Reception 7			Point of Reception 8			Point of Reception 9			Point of Reception 10		
		Distance (m)	Sound Level at PoR	Units <sup>(1)</sup> (dBA)	Distance (m)	Sound Level at PoR	Units <sup>(1)</sup> (dBA)	Distance (m)	Sound Level at PoR	Units <sup>(1)</sup> (dBA)	Distance (m)	Sound Level at PoR	Units <sup>(1)</sup> (dBA)	Distance (m)	Sound Level at PoR	Units <sup>(1)</sup> (dBA)	Distance (m)	Sound Level at PoR	Units <sup>(1)</sup> (dBA)	Distance (m)	Sound Level at PoR	Units <sup>(1)</sup> (dBA)	Distance (m)	Sound Level at PoR	Units <sup>(1)</sup> (dBA)	Distance (m)	Sound Level at PoR	Units <sup>(1)</sup> (dBA)	Distance (m)	Sound Level at PoR	Units <sup>(1)</sup> (dBA)
Gen150_e	150 kW Emergency Generator	730	42	dBA	704	42	dBA	1577	31	dBA	1570	30	dBA	2514	26	dBA	2492	25	dBA	2371	26	dBA	2344	26	dBA	3050	23	dBA	3032	23	dBA
Gen600_e	600 kW Emergency Generator	729	35	dBA	703	34	dBA	1578	30	dBA	1551	29	dBA	2523	24	dBA	2501	22	dBA	2374	24	dBA	2348	23	dBA	3059	21	dBA	3041	20	dBA
ML_Blow_o	Blower	724	-2	dBA	699	-2	dBA	1578	-9	dBA	1551	-11	dBA	2543	-2	dBA	2522	-2	dBA	2379	-11	dBA	2353	-15	dBA	3080	-14	dBA	3061	-15	dBA
ML_Crshr_o	Jaw Crusher	627	29	dBA	598	29	dBA	1388	15	dBA	1360	14	dBA	2320	7	dBA	2297	7	dBA	2126	9	dBA	2099	8	dBA	2826	4	dBA	2807	4	dBA
ML_FEx_o	Furnace Exhaust	668	5	dBA	643	4	dBA	1526	-3	dBA	1499	-5	dBA	2572	-13	dBA	2550	-13	dBA	2337	-8	dBA	2311	-12	dBA	3100	-15	dBA	3082	-15	dBA
ML_KF_o	Kiln Fan	667	25	dBA	642	24	dBA	1522	16	dBA	1494	14	dBA	2551	5	dBA	2529	4	dBA	2327	11	dBA	2301	6	dBA	3079	2	dBA	3060	2	dBA
ML_ldr_o	Front End Loader	650	27	dBA	621	23	dBA	1396	15	dBA	1367	14	dBA	2286	9	dBA	2263	8	dBA	2122	10	dBA	2094	9	dBA	2792	7	dBA	2774	5	dBA
ML_Rckdtp_o	Rock Drop	634	33	dBA	605	32	dBA	1389	24	dBA	1360	19	dBA	2308	14	dBA	2284	13	dBA	2122	15	dBA	2095	14	dBA	2813	12	dBA	2795	10	dBA
OP_Dpump1_o	Dewatering Pump at 180m Head	1524	14	dBA	1502	14	dBA	1727	12	dBA	1703	12	dBA	1268	17	dBA	1241	15	dBA	1940	11	dBA	1909	10	dBA	1679	13	dBA	1659	12	dBA
OP_DRILL1_o	Drill	1265	25	dBA	1240	24	dBA	1628	17	dBA	1602	17	dBA	1511	18	dBA	1486	18	dBA	2011	14	dBA	1980	14	dBA	1967	14	dBA	1967	14	dBA
OP_DRILL2_o	Drill	1535	18	dBA	1512	18	dBA	1769	16	dBA	1745	16	dBA	1245	21	dBA	1218	21	dBA	2001	15	dBA	1970	14	dBA	1678	17	dBA	1659	16	dBA
OP_DZR_lowgrade_o	CAT D8N dozer	662	27	dBA	635	26	dBA	1273	19	dBA	1244	18	dBA	2145	7	dBA	2121	7	dBA	1933	9	dBA	1904	8	dBA	2620	5	dBA	2601	4	dBA
OP_DZR_overburden_o	CAT D8N dozer	1438	27	dBA	1421	22	dBA	1480	22	dBA	1459	22	dBA	1483	22	dBA	1456	22	dBA	1612	21	dBA	1582	21	dBA	1790	20	dBA	1769	19	dBA
OP_Excvt1_o	CAT D8N dozer	1618	24	dBA	1592	24	dBA	2005	21	dBA	1978	21	dBA	1200	28	dBA	1177	28	dBA	2331	19	dBA	2300	19	dBA	1744	23	dBA	1727	23	dBA
OP_Excvt2_o	Hydraulic Excavator	1174	27	dBA	1149	26	dBA	1564	24	dBA	1537	23	dBA	1604	20	dBA	1580	19	dBA	1986	17	dBA	1956	17	dBA	2079	17	dBA	2060	17	dBA
OP_Excvt2_o	Hydraulic Excavator	1498	25	dBA	1476	25	dBA	1705	24	dBA	1681	24	dBA	1293	27	dBA	1267	27	dBA	1928	23	dBA	1897	23	dBA	1705	24	dBA	1685	24	dBA
OP_Rckdtp_lowgrade_o	Rock Drop	679	23	dBA	651	20	dBA	1289	15	dBA	1260	14	dBA	2132	7	dBA	2107	5	dBA	1945	9	dBA	1916	6	dBA	2609	5	dBA	2590	3	dBA
OP_Rckdtp_overburden_o	Rock Drop	1375	13	dBA	1357	11	dBA	1450	12	dBA	1428	10	dBA	1515	12	dBA	1487	10	dBA	1626	11	dBA	1596	9	dBA	1842	9	dBA	1822	7	dBA
OP_Rckdtp_waste_o	Rock Drop	1563	11	dBA	1537	9	dBA	1961	8	dBA	1934	6	dBA	1256	14	dBA	1234	12	dBA	2305	6	dBA	2274	4	dBA	1797	10	dBA	1779	7	dBA
UG_ExVentRaise1_o	Exhaust Vent Raise 1	1380	25	dBA	1361	24	dBA	1527	24	dBA	1503	22	dBA	1451	24	dBA	1424	22	dBA	1745	23	dBA	1713	21	dBA	1819	22	dBA	1798	21	dBA
UG_ExVentRaise2_o	Exhaust Vent Raise 2	906	27	dBA	879	26	dBA	1734	20	dBA	1706	19	dBA	2196	14	dBA	2196	13	dBA	2496	14	dBA	2469	13	dBA	2975	12	dBA	2958	11	dBA
UG_VentRaise1_o	Fresh Air Intake Vent Raise	988	29	dBA	963	27	dBA	1440	25	dBA	1411	23	dBA	1795	23	dBA	1770	21	dBA	1943	21	dBA	1913	20	dBA	2268	20	dBA	2249	19	dBA
ML_ExLv01_o	Building Vent 1	737	17	dBA	712	15	dBA	1596	-4	dBA	1569	-6	dBA	2572	-13	dBA	2551	-14	dBA	2404	-9	dBA	2378	-12	dBA	3111	-15	dBA	3093	-15	dBA
ML_ExLv02_o	Building Vent 2	763	16	dBA	738	16	dBA	1622	-1	dBA	1595	-2	dBA	2569	-10	dBA	2548	-11	dBA	2428	-6	dBA	2402	-9	dBA	3111	-12	dBA	3093	-12	dBA
ML_ExLv03_o	Building Vent 3	670	22	dBA	645	16	dBA	1532	-8	dBA	1505	-10	dBA	2591	-16	dBA	2569	-17	dBA	2348	-15	dBA	2322	-15	dBA	3120	-18	dBA	3102	-19	dBA
ML_ExLv04_o	Building Vent 4	697	15	dBA	672	11	dBA	1557	-7	dBA	1530	-9	dBA	2578	-15	dBA	2556	-16	dBA	2368	-11	dBA	2342	-14	dBA	3110	-17	dBA	3092	-17	dBA
ML_ExLv05_o	Building Vent 5	718	17	dBA	693	13	dBA	1578	-6	dBA	1551	-7	dBA	2575	-14	dBA	2553	-15	dBA	2387	-10	dBA	2361	-13	dBA	3110	-16	dBA	3092	-16	dBA
ML_ExLv06_o	Building Vent 6	656	22	dBA	631	21	dBA	1515	12	dBA	1488	7	dBA	2572	-16	dBA	2550	-17	dBA	2326	-2	dBA	2300	1	dBA	3099	-9	dBA	3080	-8	dBA
ML_ExLv07_o	Building Vent 7	658	22	dBA	632	21	dBA	1510	12	dBA	1483	7	dBA	2545	-16	dBA	2523	-17	dBA	2314	7	dBA	2288	1	dBA	3071	-13	dBA	3053	-13	dBA
ML_ExLv08_o	Building Vent 8	795	15	dBA	769	15	dBA	1645	6	dBA	1618	6	dBA	2522	1	dBA	2501	0	dBA	2439	1	dBA	2412	1	dBA	3068	-2	dBA	3050	-3	dBA
ML_ExLv09_o	Building Vent 9	782	15	dBA	756	15	dBA	1627	11	dBA	1600	10	dBA	2501	1	dBA	2480	0	dBA	2416	6	dBA	2389	1	dBA	3045	-2	dBA	3027	-3	dBA
ML_ExLv10_o	Building Vent 0	763	16	dBA	737	16	dBA	1614	11	dBA	1586	6	dBA	2526	-7	dBA	2505	-8	dBA	2409	6	dBA	2383	1	dBA	3068	-2	dBA	3050	-3	dBA
ML_ExLv11_o	Building Vent 1	693	2	dBA	667	2	dBA	1544	6	dBA	1517	5	dBA	2536	1	dBA	2514	0	dBA	2345	1	dBA	2318	-2	dBA	3067	-2	dBA	3049	-3	dBA
ML_ExLv12_o	Building Vent 2	673	14	dBA	648	13	dBA	1523	12	dBA	1495	7	dBA	2529	1	dBA	2507	0	dBA	2322	7	dBA	2296	1	dBA	3057	-2	dBA	3039	-3	dBA
ML_ExLv13_o	Building Vent 3	714	2	dBA	689	4	dBA	1565	7	dBA	1538	7	dBA	2533	1	dBA	2511	0	dBA	2364	6	dBA	2338	1	dBA	3067	-2	dBA	3049	-3	dBA
ML_ExLv14_o	Building Vent 4	748	9	dBA	723	12	dBA	1604	7	dBA	1577	6	dBA	2554	0	dBA	2532	0	dBA	2407	1	dBA	2380	1	dBA	3093	-2	dBA	3075	-3	dBA
Htruck1_o	Haul Truck #1	Varies	24	dBA	Varies	21	dBA	Varies	18	dBA	Varies	17	dBA	Varies	12	dBA	Varies	11	dBA	Varies	10	dBA	Varies	9	dBA	Varies	8	dBA	Varies	8	dBA
Htruck2_o	Haul Truck #2	Varies	24	dBA	Varies	21	dBA	Varies	18	dBA	Varies	17	dBA	Varies	14	dBA	Varies	14	dBA	Varies	12	dBA	Varies	11	dBA	Varies	11	dBA	Varies	10	dBA
Htruck3_o	Haul Truck #3	Varies	32	dBA	Varies	29	dBA	Varies	27	dBA	Varies	25	dBA	Varies	24	dBA	Varies	23	dBA	Varies	20	dBA	Varies	19	dBA	Varies	19	dBA	Varies	19	dBA

**Table 3A: Acoustic Assessment Summary**

Treasury Metals Inc. – Goliath Gold Project, 1401701

## Notes to Table:

- "Table A3" in Appendix A of Basic CCofA Guide.
- 1. "Continuous" noise sources includes sum of steady, quasi-steady impulsive, tonal, cyclical and buzzing noise sources, with appropriate penalties applied, in accordance with documents NPC-104 and NPC-300. Impulsive and emergency noise sources are assessed separately from continuous noise sources.
- 2. Daytime occurs from 0700-1900h. Evening occurs from 1900h-2300h. Nighttime occurs from 2300-0700h.
- 3. Worst-case cumulative sound level from all applicable sources operating.
- 4. Has an acoustic audit (as defined in Publication NPC-233) been conducted with source in place and operating?
- 5. Applicable worst-case NPC-300 sound level limit.
- 6. Performance limit (aka guideline limit) based on following:
  - C = Calculated based on road traffic volumes in compliance with NPC-206 requirements.
  - M = Measured based on monitoring for a minimum 48 hour period, in accordance with NPC-233 requirements.
  - D = Default guideline minima per NPC-300.

**Assessment of Impacts for "Continuous" Noise Sources <sup>[1]</sup>**

Point of Reception ID	Point of Reception Description	Time Period <sup>[2]</sup>	Total Sound Level at PoR <sup>[3]</sup> (dBA)	Verified by Acoustic Audit <sup>[4]</sup> (Yes/No)	Performance Limit <sup>[5]</sup> (dBA)	Performance Limit Source <sup>[6]</sup> (C / M / D)	Compliance with Performance Limit (Yes/No)
NR03	House - owned by Mcleish	Daytime	40	No	45	D	Yes
		Evening	40	No	40		Yes
		Nighttime	40	No	40		Yes
NR03_O	Outdoor receptor- Mcleish	Daytime	39	No	45	D	Yes
		Evening	39	No	40		Yes
		Nighttime	39	No	40		Yes
NR04	House - owned by Nystroms	Daytime	34	No	45	D	Yes
		Evening	34	No	40		Yes
		Nighttime	34	No	40		Yes
NR04_O	Outdoor receptor- Nystroms	Daytime	33	No	45	D	Yes
		Evening	33	No	40		Yes
		Nighttime	33	No	40		Yes
NR30	House - East Thunder Lake Road	Daytime	34	No	45	D	Yes
		Evening	34	No	40		Yes
		Nighttime	34	No	40		Yes
NR30_O	Outdoor receptor - East Thunder Lake Road	Daytime	33	No	45	D	Yes
		Evening	33	No	40		Yes
		Nighttime	33	No	40		Yes
NR44	House - Near Trans-Canada Highway	Daytime	31	No	45	D	Yes
		Evening	31	No	40		Yes
		Nighttime	31	No	40		Yes
NR44_O	Outdoor receptor - Near Trans-Canada Highway	Daytime	30	No	45	D	Yes
		Evening	30	No	40		Yes
		Nighttime	30	No	40		Yes
NR47	House - East Thunder Lake Road	Daytime	31	No	45	D	Yes
		Evening	31	No	40		Yes
		Nighttime	31	No	40		Yes
NR47_O	Outdoor receptor - East Thunder Lake Road	Daytime	30	No	45	D	Yes
		Evening	30	No	40		Yes
		Nighttime	30	No	40		Yes

**Table 3B: Acoustic Assessment Summary**

Treasury Metals Inc. – Goliath Gold Project, 1401701

**Notes to Table:**

- "Table A3" in Appendix A of Basic CCofA Guide.
- 1. "Continuous" noise sources includes sum of steady, quasi-steady impulsive, tonal, cyclical and buzzing noise sources, with appropriate penalties applied, in accordance with documents NPC-104 and NPC-300. Impulsive and emergency noise sources are assessed separately from continuous noise sources.
- 2. Daytime occurs from 0700-1900h. Evening occurs from 1900h-2300h. Nighttime occurs from 2300-0700h.
- 3. Worst-case cumulative sound level from all applicable sources operating.
- 4. Has an acoustic audit (as defined in Publication NPC-233) been conducted with source in place and operating?
- 5. Applicable worst-case NPC-300 sound level limit.
- 6. Performance limit (aka guideline limit) based on following:
  - C = Calculated based on road traffic volumes in compliance with NPC-206 requirements.
  - M = Measured based on monitoring for a minimum 48 hour period, in accordance with NPC-233 requirements.
  - D = Default guideline minima per NPC-300.

**Assessment of Noise Impacts from Emergency Source Testing <sup>[1]</sup>**

<b>Point of Reception ID</b>	<b>Point of Reception Description</b>	<b>Time Period <sup>[2]</sup></b>	<b>Total Sound Level at PoR <sup>[3]</sup> (dBA)</b>	<b>Verified by Acoustic Audit <sup>[4]</sup> (Yes/No)</b>	<b>Performance Limit <sup>[5]</sup> (dBA)</b>	<b>Performance Limit Source <sup>[6]</sup> (C / M/ D)</b>	<b>Compliance with Performance Limit (Yes/No)</b>
NR03	House - owned by Mcleish	Daytime	43	No	50	D	Yes
NR03_O	Outdoor receptor- Mcleish	Daytime	43	No	50	D	Yes
NR04	House - owned by Nystroms	Daytime	36	No	50	D	Yes
NR04_O	Outdoor receptor- Nystroms	Daytime	33	No	50	D	Yes
NR30	House - East Thunder Lake Road	Daytime	28	No	50	D	Yes
NR30_O	Outdoor receptor - East Thunder Lake Road	Daytime	27	No	50	D	Yes
NR44	House - Near Trans-Canada Highway	Daytime	31	No	50	D	Yes
NR44_O	Outdoor receptor - Near Trans-Canada Highway	Daytime	28	No	50	D	Yes
NR47	House - East Thunder Lake Road	Daytime	25	No	50	D	Yes
NR47_O	Outdoor receptor - East Thunder Lake Road	Daytime	25	No	50	D	Yes

**Table 3C: Acoustic Assessment Summary**

Treasury Metals Inc. – Goliath Gold Project, 1401701

**Notes to Table:**

- "Table A3" in Appendix A of Basic CCoFA Guide.
- 1. "Blasting" noise sources includes sum of steady noise sources, with appropriate penalties applied.
- 2. Daytime occurs from 0700-1900h
- 3. Worst-case cumulative sound level from all applicable sources operating.
- 4. Has an acoustic audit (as defined in Publication NPC-233) been conducted with source in place and operating?
- 5. Applicable worst-case NPC-119 sound level limit.
- 6. Performance limit (aka guideline limit) based on NPC-119

**Assessment of Impacts for Blasting Noise Sources <sup>[1]</sup>**

Point of Reception ID	Point of Reception Description	Time Period <sup>[2]</sup>	Total Sound Level at PoR <sup>[3]</sup> (dBA)	Verified by Acoustic Audit <sup>[4]</sup> (Yes/No)	Performance Limit <sup>[5]</sup> (dBA)	Performance Limit Source <sup>[6]</sup>	Compliance with Performance Limit (Yes/No)
NR03	House - owned by Mcleish	Daytime	78	No	120	NPC-119 Cautionary Limit	Yes
NR04	House - owned by Nystroms	Daytime	71	No	120	NPC-119 Cautionary Limit	Yes
NR30	House - East Thunder Lake Road	Daytime	75	No	120	NPC-119 Cautionary Limit	Yes
NR44	House - Near Trans-Canada Highway	Daytime	68	No	120	NPC-119 Cautionary Limit	Yes
NR47	House - East Thunder Lake Road	Daytime	70	No	120	NPC-119 Cautionary Limit	Yes



**Table 3D: Vibration Assessment Summary**

Treasury Metals Inc. – Goliath Gold Project, 1401701


**Notes to Table:**

- "Table A3" in Appendix A of Basic CCoFA Guide.
- 1. Daytime occurs from 0700-1900h
- 2. Worst-case cumulative vibration level from all applicable sources operating.
- 3. Applicable worst-case NPC-119 vibration level limit.
- 4. Performance limit (aka guideline limit) based on NPC-119

**Assessment of Impacts for Blasting Vibration Sources <sup>[1]</sup>**

<b>Point of Reception ID</b>	<b>Point of Reception Description</b>	<b>Time Period <sup>[2]</sup></b>	<b>Total PPV Level at PoR <sup>[3]</sup> (mm/sec)</b>	<b>Performance Limit <sup>[5]</sup> (mm/sec)</b>	<b>Performance Limit Source <sup>[6]</sup></b>	<b>Compliance with Performance Limit (Yes/No)</b>
NR03	House - owned by Mcleish	Daytime	1.23	10	NPC-119 Cautionary Limit	Yes
NR04	House - owned by Nystroms	Daytime	0.57	10	NPC-119 Cautionary Limit	Yes
NR30	House - East Thunder Lake Road	Daytime	0.82	10	NPC-119 Cautionary Limit	Yes
NR44	House - Near Trans-Canada Highway	Daytime	0.41	10	NPC-119 Cautionary Limit	Yes
NR47	House - East Thunder Lake Road	Daytime	0.52	10	NPC-119 Cautionary Limit	Yes

# FIGURES




Source locations



Drawn by: NBN	Figure: 1
Approx. Scale: 1:8,500	
Date Revised: Aug. 20, 2014	







Sensitive Receptor Locations



True North


Drawn by: NBN | Figure: 2

Approx. Scale: 1:25,000

Date Revised: Aug. 20, 2014







Predicted Sound Level Contours for Normal Operations




True North

Drawn by: NBN	Figure: 3
Approx. Scale: 1:20,000	
Date Revised: Aug. 21, 2014	







Predicted Sound Level Contours for Emergency Source Testing  
Daytime



Drawn by: NBN	Figure: 4
Approx. Scale: 1:20,000	
Date Revised: Aug. 20, 2014	



# APPENDIX A



# Acoustic Assessment Report Check-List

Prepared by:

**Ontario Ministry of the Environment**  
Environmental Approval Access and Service Integration Branch

Last Revision Date: February 2013

**Ce formulaire est disponible en français**

For more information:

Ministry of the Environment

Public Information Centre

Telephone: 416-325-4000

Toll free: 1-800-565-4923

Email: [picemail.moe@ontario.ca](mailto:picemail.moe@ontario.ca)

[www.ontario.ca/environment](http://www.ontario.ca/environment)

© Queen's Printer for Ontario, 2013

PIBS 5356e01

Company Name: Treasury Metals Incorporated

Company Address: 130 King Street West

Location of Facility: Toronto, Ontario

The attached Acoustic Assessment Report was prepared in accordance with the guidance in the ministry document "Information to be Submitted for Approval of Stationary Sources of Sound" (NPC 233) dated October 1995 and the minimum required information identified in the check-list on the reverse of this sheet has been submitted.

Company Contact: \_\_\_\_\_

Name: Mark Wheeler, P.Eng.

Title: Senior Mining Engineer

Phone Number: (416) 214-4654

Signature: \_\_\_\_\_

Date: \_\_\_\_\_

Technical Contact: \_\_\_\_\_

Name: Melissa Annett

Representing: RWDI AIR Inc.

Phone Number: (519) 823-1311 ext 2372

Signature: \_\_\_\_\_

Date: \_\_\_\_\_

## ACOUSTIC ASSESSMENT REPORT CHECKLIST

Required Information		Submitted	Explanation/Reference
<b>1.0</b>	<b>Introduction (Project Background and Overview)</b>	<input checked="" type="checkbox"/> Yes	Section 1
<b>2.0</b>	<b>Facility Description</b>		
2.1	Operating hours of facility and significant Noise Sources	<input checked="" type="checkbox"/> Yes	Section 2
2.2	Site Plan identifying all significant Noise Sources	<input checked="" type="checkbox"/> Yes	Figure 1
<b>3.0</b>	<b>Noise Source Summary</b>		
3.1	<b>Noise Source Summary Table</b>	<input checked="" type="checkbox"/> Yes	Table 1
3.2	Source noise emissions specifications	<input checked="" type="checkbox"/> Yes	Appendix B
3.3	Source power/capacity ratings	<input checked="" type="checkbox"/> Yes	Appendix B
3.4	Noise control equipment description and acoustical specifications	<input type="checkbox"/> Yes	N/A
<b>4.0</b>	<b>Point of Reception Noise Impact Calculations</b>		
4.1	<b>Point of Reception Noise Impact Table</b>	<input checked="" type="checkbox"/> Yes	Table 2
4.2	Point(s) of Reception (POR) list and description	<input checked="" type="checkbox"/> Yes	Section 4
4.3	Land-use Zoning Plan	<input checked="" type="checkbox"/> Yes	See details in section 4
4.4	Scaled Area Location Plan	<input checked="" type="checkbox"/> Yes	Figure 2
4.5	Procedure used to assess noise impacts at each POR	<input checked="" type="checkbox"/> Yes	Section 6
4.6	List of parameters/assumptions used in calculations	<input checked="" type="checkbox"/> Yes	Appendix D
<b>5.0</b>	<b>Acoustic Assessment Summary</b>		
5.1	<b>Acoustic Assessment Summary Table</b>	<input checked="" type="checkbox"/> Yes	Table 3
5.2	Rationale for selecting applicable noise guideline limits	<input checked="" type="checkbox"/> Yes	Section 5
5.3	Predictable Worst Case Impacts Operating Scenario	<input checked="" type="checkbox"/> Yes	Section 3
<b>6.0</b>	<b>Conclusions</b>		
6.1	Statement of compliance with the selected noise performance limits	<input checked="" type="checkbox"/> Yes	Section 7
<b>7.0</b>	<b>Appendices (Provide details such as)</b>	<input checked="" type="checkbox"/> Yes	
	Listing of Insignificant Noise Sources	<input checked="" type="checkbox"/> Yes	Section 3.1
	Manufacturer's Noise Specifications	<input checked="" type="checkbox"/> Yes	Appendix B
	Calculations	<input checked="" type="checkbox"/> Yes	Appendix B and D
	Instrumentation	<input checked="" type="checkbox"/> Yes	Appendix C
	Meteorology during Sound Level Measurements	<input checked="" type="checkbox"/> Yes	Appendix C
	Raw Data from Measurements	<input checked="" type="checkbox"/> Yes	Appendix C
	Drawings (Facility / Equipment)	<input checked="" type="checkbox"/> Yes	Figures Section



## NOISE SCREENING PROCESS FOR S.9 APPLICATIONS SUPPLEMENT TO APPLICATION FOR APPROVAL

*In order to obtain an approval under Section 9 of the EPA, applicants are, as a minimum, required to assess and document the impacts of all noise emissions from their facility on any noise sensitive locations defined as a Point of Reception. In order to facilitate this assessment, the ministry has developed a Noise Screening Process.*

*The Noise Screening Process has been developed for mining, utilities and manufacturing operations that are being reviewed by the Air and Noise Unit of the Environmental Assessment and Approvals Branch. Other facilities that require Section 9 approval can not use this Noise Screening Process. Applications for equipment identified as candidates for the Streamline Review Unit (SRU) should not complete this process, rather they should follow specific directions from the SRU. For more information about the types of applications that may be reviewed by the SRU, please refer to the Guide to Applying for Approval (Air & Noise) dated February, 2005.*

### **The Noise Screening Process consists of the following Steps:**

- |         |   |
|---------|---|
| Step 1: | Identify the closest Point of Reception to the facility. (Zoning Plan)  |
| Step 2: | Determine the actual separation distance from the Point of Reception to the facility. (Scaled Area Location Plan)   |
| Step 3: | Calculate the minimum required separation distance by completing the questionnaire on using the facility's North American Industrial Classification System Code and generic assumptions regarding the actual noise sources present at the facility. |
| Step 4: | Compare the actual separation distance determined in Step 2 with the minimum required separation distance calculated in Step 3 and sign the form.   |

The Noise Screening Process is based on the fact that the noise emissions from any noise sources at a facility will not exceed ministry noise guidelines at the closest Point of Reception provided there is a sufficient separation distance between the facility's noise sources and the Point of Reception. Using conservative assumptions regarding the likely noise sources present at a facility, a procedure was developed for calculating the minimum required separation distance to achieve compliance with the ministry noise guidelines. If the actual separation distance from the facility to the closest Point of Reception is greater than the calculated minimum required separation distance, then no further action is required. The signed Noise Screening Process form would provide sufficient supporting information for the noise assessment required by the application process.

If the closest Point of Reception is closer than the minimum required separation distance calculated in Step 3 then further assessment is required. The application may still be approved as proposed and noise control measures may not be necessary; however, a more detailed noise impact assessment using site specific information on the noise sources present at the facility must be completed. The Zoning Plan and Scaled Area Location Plan required by the Noise Screening Process will form part of the required assessment outlined in the ministry publication NPC 233 "Information to be Submitted for Approval of Stationary Sources of Sound." See the Guide to Applying for Approval (Air and Noise) dated February, 2005 for more information on the minimum required supporting information to be included with an application that is unable to pass the Noise Screening Process.



## 1. Applicant Information

Company Name <b>Treasury Metals Incorporated</b>	Site Name <b>Goliath Gold Project</b>	North American Industry Classification System (NAICS) Code <b>21222</b>
Site Address - Street information ( <i>applies to an address that has civic numbering and street information - includes street number, name, type and direction</i> )		Unit Identifier ( <i>identifies type of unit, such as suite &amp; number</i> )
Survey Address ( <i>used for a rural location specified for a subdivided township, an unsubdivided township or unsurveyed territory</i> )		
Non Address Information ( <i>includes any additional information to clarify clients' physical location</i> ) <b>49°45'29.39"N , 92°36'19.65"W</b>		
Municipality/Unorganized Township <b>Wabigoon</b>	County/District <b>Kenora</b>	Postal Code

## 2. Noise Screening Process (*please refer to the attached Noise Screening Process – Information & Instructions*)

Step 1 Identify Closest Point of Reception (POR) (attach Land Use Zoning Designation Plan) POR Description <u>House - owned by Mcleish</u> POR Acoustical Class (as per NPC-205 & NPC-232) <input type="checkbox"/> 1 <input type="checkbox"/> 2 <input checked="" type="checkbox"/> 3		
Step 2 Determine Actual Separation Distance (attach Scaled Area Location Plan) <span style="float: right;"><u>350</u> m</span>		
Step 3 Calculate Minimum Separation Distance (complete attached Noise Screening Process Questionnaire) <span style="float: right;"><u>1000</u> m</span>		
Step 4 By signing this statement you are verifying that: <ul style="list-style-type: none"> <li>• I am the applicant or have been retained by the applicant, for the purposes of completing this Noise Screening Process;</li> <li>• The closest Point of Reception has been identified and the Land Use Zoning Designation Plan provided by the Local Municipality is attached (Step 1);</li> <li>• A Scaled Area Location Plan, prepared by myself, that identifies the facility, the closest Point of Reception and the actual minimum separation distance is attached (Step 2);</li> <li>• I have accurately completed the Noise Screening Process questionnaire and identified all noise sources as required (Step 3);</li> <li>• The actual separation distance from the facility to the closest Point of Reception, as determined in Steps 1 and 2, is greater than the minimum required separation distance determined in Step 3; and</li> <li>• The facility belongs to one of the sectors for which the ministry has indicated the Noise Screening Process is applicable.</li> </ul>		
Name of Signing Authority ( <i>please print</i> )	Title:	Company: ( <i>if different from the Applicant</i> )
Civic Address - Street information ( <i>includes street number, name, type and direction</i> ) <input type="checkbox"/> Same as Site Address		Unit Identifier ( <i>identifies type of unit, such as suite &amp; number</i> )
Municipality	Postal Station	Province/State
		Country
		Postal Code
Telephone Number ( <i>including area code &amp; extension</i> )	Fax Number ( <i>including area code</i> )	E-mail Address
Signature		Date (y/m/d)



# Noise Screening Process Questionnaire

## Question 1

**1 (a) - Is your facility NAICS Code Listed on Table 1.1 below?**

<b>Table 1.1 Industry with significant noise sources</b>		
NAICS Code	Industry	Check all That Apply
21	Mining and Oil and Gas Extraction	<input checked="" type="checkbox"/>
22111	Electrical Power Generation	<input type="checkbox"/>
324	Petroleum and Coal Products Manufacturing	<input type="checkbox"/>
3251	Basic Chemical Manufacturing	<input type="checkbox"/>
32731	Cement Manufacturing	<input type="checkbox"/>
32741	Lime Manufacturing	<input type="checkbox"/>
3311	Iron and Steel Mills and Ferro-Alloy Manufacturing	<input type="checkbox"/>
3313	Alumina and Aluminium Production and Processing	<input type="checkbox"/>

**1 (b) - Is any of the following equipment Listed on Table 1.2 below present at the facility?**

<b>Table 1.2 Equipment with significant noise emissions</b>	
Equipment	Check all That Apply
Flares	<input type="checkbox"/>
Gas Turbines, Cogeneration Facilities or any other continuous or peak shaving electrical power generation equipment	<input type="checkbox"/>
Arc Furnaces	<input type="checkbox"/>
Asphalt Plants	<input type="checkbox"/>
High velocity or pressure atmospheric vents such as Gas Process Blow Down Devices	<input type="checkbox"/>
Rock, Concrete or Aggregate Crushing Operations	<input checked="" type="checkbox"/>
Individual Fans with flow rates in excess of 47 m <sup>3</sup> /s	<input checked="" type="checkbox"/>
Individual Pressure Blowers or Positive Displacement Blowers with static pressures in excess of 1.25 kilopascal	<input checked="" type="checkbox"/>

Did you answer “Yes” to Question 1(a) or 1 (b)?  Yes  No

**If Yes,** the minimum required separation distance is 1,000 m.  
You have completed Step 3 of the Noise Screening Process, proceed to Step 4.

**If No,** proceed to Question 2

**Proceed to Question 2**

## Question 2

2 - Is your facility NAICS Code Listed on Table 2 below?

<b>Table 2 Industries with a 500 m Radius</b>		
NAICS Code	Industry	Check all That Apply
22112	Electrical Power Transmission, Control and Distribution	<input type="checkbox"/>
2213	Water Sewage and Other Systems	<input type="checkbox"/>
321	Wood Product Manufacturing	<input type="checkbox"/>
322	Paper Manufacturing	<input type="checkbox"/>
325	Chemical Manufacturing (except 3251 as noted in Table 1.1 above)	<input type="checkbox"/>
326	Plastics and Rubber Products Manufacturing	<input type="checkbox"/>
327	Non-Metallic Mineral Product Manufacturing (except 32731 and 32741 as noted in Table 1.1 above)	<input type="checkbox"/>
331	Primary Metal Manufacturing (except 3311 as noted in Table 1.1 above)	<input type="checkbox"/>
332	Fabricated Metal Product Manufacturing (except 33271 and 3328)	<input type="checkbox"/>
333	Machinery Manufacturing	<input type="checkbox"/>
335	Electrical Equipment, Appliance and Component Manufacturing	<input type="checkbox"/>
336	Transportation Equipment Manufacturing	<input type="checkbox"/>

Did you answer "Yes" to Question 2?

Yes

No

**If Yes**, the minimum required separation distance is as follows:

	Minimum Separation	Check the One That Applies
For Class 1:		
Daytime Operation Only (between 7:00 am and 7:00 pm)	300 m	<input type="checkbox"/> N/A
Daytime and Afternoon shift only (between 7:00 am and 11:00 pm)	400 m	<input checked="" type="checkbox"/>
Other times (outside the hours of 7:00 am to 11:00 pm)	500 m	<input type="checkbox"/>
For Class 2:		
Daytime Operation Only (between 7:00 am and 7:00 pm)	300 m	<input type="checkbox"/> N/A
Multi shifts (outside the hours of 7:00 am to 7:00 pm)	500 m	<input type="checkbox"/> N/A
For Class 3:		
Any Operation	500 m	<input type="checkbox"/>

You have completed Step 3 of the Noise Screening Process, proceed to Step 4

**If No**, proceed to Question 3

**Proceed to Question 3**

### Question 3

**3 - Provide information on the facility and any noise sources that may be present by answering the following questions to determine a Score for noise sources located at the facility:**

	Check one for each question	Value	Score
<b>(a) What is the area of the enclosed buildings of the facility?</b>			
< 650 m <sup>2</sup>	<input type="checkbox"/>	20	
650 m <sup>2</sup> to < 2,300 m <sup>2</sup>	<input type="checkbox"/>	25	
2,300 m <sup>2</sup> to 9,300 m <sup>2</sup>	<input type="checkbox"/>	30	
> 9,300 m <sup>2</sup>	<input type="checkbox"/>	40	
multi building	<input type="checkbox"/>	40	
<b>(b) Are any cooling towers located at the facility?</b>			
Yes			
- Total of all cooling towers less than 20 horsepower	<input type="checkbox"/>	10	
- Total of all cooling towers from 20 to 100 horsepower	<input type="checkbox"/>	20	
- Total of all cooling towers greater than 100 horsepower	<input type="checkbox"/>	40	
No	<input type="checkbox"/>	0	
<b>(c) Are any outdoor air cooled chillers located at the facility?</b>			
Yes			
- Total of all chillers less than 150 ton	<input type="checkbox"/>	10	
- Total of all chillers from 150 to 1,000 ton	<input type="checkbox"/>	20	
- Total of all chillers greater than 1,000 ton	<input type="checkbox"/>	40	
No	<input type="checkbox"/>	0	
<b>(d) Are any air compressors used to provide process air or for pneumatic conveying systems located at the facility?</b>			
Yes			
- Total of all compressors less than 10 horsepower	<input type="checkbox"/>	10	
- Total of all compressors from 10 to 75 horsepower	<input type="checkbox"/>	20	
- Total of all compressors greater than 75 horsepower	<input type="checkbox"/>	40	
No	<input type="checkbox"/>	0	
<b>(e) Is a boiler located at the facility?</b>			
Yes			
- Total heat input of all boilers less than 10 million BTU/hr	<input type="checkbox"/>	10	
- Total heat input of all boilers from 10 to 67 million BTU/hr	<input type="checkbox"/>	20	
- Total heat input of all boilers greater than 67 million BTU/hr	<input type="checkbox"/>	40	
No	<input type="checkbox"/>	0	
<b>(f) What is the total volumetric flow rate of all process exhaust and general ventilation fans?</b>			
< 5 m <sup>3</sup> /s	<input type="checkbox"/>	0	
5 m <sup>3</sup> /s to < 10 m <sup>3</sup> /s	<input type="checkbox"/>	10	
10 m <sup>3</sup> /s to < 15 m <sup>3</sup> /s	<input type="checkbox"/>	20	
15 m <sup>3</sup> /s to < 20 m <sup>3</sup> /s	<input type="checkbox"/>	30	
> 20 m <sup>3</sup> /s	<input type="checkbox"/>	40	
<b>(g) Are any of the above air compressors, fan or blower motors located outside the building envelope?</b>			
Yes	<input type="checkbox"/>	10	
No	<input type="checkbox"/>	0	
<b>SUBTOTAL - Add Score from (a) to (g)</b>			

### Question 3 (continued)

Adjustments for Hours of Operation		Check one	Value	Score
Class 1	Daytime Operation Only (between 7:00 am and 7:00 pm) *	<input checked="" type="checkbox"/>	-20	
	Daytime and Afternoon shift only (between 7:00 am and 11:00 pm) **	<input type="checkbox"/>	-15	
	Other times (outside the hours of 7:00 am to 11:00 pm)	<input type="checkbox"/>	-10	
Class 2	Daytime Operation Only (between 7:00 am and 7:00 pm)*	<input type="checkbox"/>	-20	
	Multi shifts (outside the hours of 7:00 am to 7:00 pm)	<input type="checkbox"/>	-10	
Class 3	Daytime Operation Only (between 7:00 am and 7:00 pm)	<input type="checkbox"/>	-10	
	Multi shifts (outside the hours of 7:00 am to 7:00 pm)	<input type="checkbox"/>	0	
<b>TOTAL ADJUSTMENT (A)</b>				
Adjustments for Elevated Background Noise at Point of Reception (POR)***		Check one	Value	Score
Class 1	POR within 100 m of a 400 Series Freeway (e.g. 401)	<input checked="" type="checkbox"/>	-10	
	POR within 30 m of a Provincial Highway or Arterial Road (eg HWY 27, Keele St)	<input type="checkbox"/>	-10	
	POR at other locations	<input type="checkbox"/>	0	
Class 2	POR within 100 m of a 400 Series Freeway (e.g. 401)	<input type="checkbox"/>	-10	
	POR within 30 m of a Provincial Highway or Arterial Road (eg HWY 27, Keele St)	<input type="checkbox"/>	-10	
	POR at other locations	<input type="checkbox"/>	0	
Class 3	All locations	<input type="checkbox"/>	0	
<b>TOTAL ADJUSTMENT (B)</b>				
<b>TOTAL SCORE - SUBTOTAL + TOTAL ADJUSTMENT (A) + TOTAL ADJUSTMENT (B)</b>				

- \* Note: the largest minimum separation distance for Daytime Operation only in Class 1 or 2 is 300 m.
- \*\* Note: the largest minimum separation distance for Evening and Daytime Operation only in Class 1 is 400 m
- \*\*\* Note: if Adjustments for Elevated Background Noise are used then the applicant must identify the next closest receptor outside the area of influence of the roadway and show that the actual separation distance to the next closest receptor is greater than the minimum required separation distance without adjustments.

#### Minimum Separation Distances – Based on Total Score (above)

Total Score	Minimum Separation Distance	Check the distance that applies
< 0 points	50 m	<input type="checkbox"/>
< 5 points	75 m	<input type="checkbox"/>
< 10 points	100 m	<input type="checkbox"/>
< 20 points	200 m	<input type="checkbox"/>
< 30 points	300 m	<input type="checkbox"/>
< 40 points	400 m	<input type="checkbox"/>
40 or more points	500 m	<input type="checkbox"/>
<b>Distance:</b>		m

## NOISE SCREENING PROCESS – INFORMATION & INSTRUCTIONS

### STEP 1: IDENTIFY CLOSEST POINT OF RECEPTION

The applicant must identify and locate the closest Point of Reception (POR) affected by any noise emissions that may arise from the operations at the facility. A Point of Reception is defined as “any point on the premises of a person where sound or vibration originating from other than those premises is received”.

The Point of Reception may be located on any of the following existing or zoned for future use premises:

- permanent or seasonal residences;
- hotels/motels;
- nursing/retirement homes;
- rental residences;
- hospitals;
- campgrounds; and
- noise sensitive buildings such as schools and places of worship.

For the Screening Process it is only required to identify the closest Point of Reception to the facility or any outdoor noise sources. For a more detailed assessment additional Point(s) or Reception may be required to be identified in other directions based on site specific conditions.

The closest Point of Reception must be selected using a **Land Use Zoning Designation Plan**. This plan indicates the approved local land use and nature of the neighbourhood for the area surrounding the facility. The plan must be based on up-to-date Zoning information provided by the Local Municipality. Zoning Designation Plans may be obtained from the planning department of the Local Municipality. This information may be in the form of hard copy zoning plans prepared by the municipality or electronic base maps showing local land use and features that may be available from the municipality to be printed by the applicant.

The Zoning information obtained from the Local Municipality must be detailed enough to clearly indicate the approved local land use for the individual properties surrounding the facility in a radius including the closest Point of Reception. The plan must include a scale and legend indicating the land use. The Zoning Information used to identify the closest Point of Reception must be attached to the Screening Process.

The Point of Reception Identification section should also describe the environmental noise climate at the Point of Reception in terms of the acoustical class, according to the following definitions:

- "Class 1 Area" means an area with an acoustical environment typical of a major population centre, where the background noise is dominated by the urban hum.
- "Class 2 Area" means an area with an acoustical environment that has qualities representative of both Class 1 and Class 3 Areas, and in which a low ambient sound level, normally occurring only between 23:00 and 07:00 hours in Class 1 Areas, will typically be realized as early as 19:00 hours.  
Other characteristics which may indicate the presence of a Class 2 Area include:
  - absence of urban hum between 19:00 and 23:00 hours;
  - evening background sound level defined by natural environment and infrequent human activity; and
  - no clearly audible sound from stationary sources other than from those under impact assessment.
- "Class 3 Area" means a rural area with an acoustical environment that is dominated by natural sounds having little or no road traffic, such as the following:
  - a small community with less than 1,000 population;
  - an agricultural area;
  - a rural recreational area such as a cottage or a resort area; or
  - a wilderness area.

## STEP 2: DETERMINE ACTUAL SEPARATION DISTANCE

The location of the closest Point of Reception must be shown on a figure, prepared by the applicant, to determine the actual separation distance from the facility to the Point of Reception. The figure is referred to as a **Scaled Area Location Plan**.

For the Purposes of the Screening Process it may be possible to use the Zoning information provided by the Local Municipality as the Scaled Area Location Plan. However, the information is usually better presented in two separate figures because the scale of zoning plans available from the Local municipality is usually too small to sufficiently show the level of detail required by the Scaled Area Location Plan.

This figure, prepared by the applicant, must clearly indicate the location of the facility, the facility property line, all buildings on the facility and any noise sources at the facility that are located outside of the building envelope, such as dust collectors located beside a building. For the purposes of the Screening Process, it is not required to identify all noise sources, such as roof-mounted exhaust fans, on the Scaled Area Location Plan. The Scaled Area Location Plan must also show and name all local roads and features of the neighbourhood for the area surrounding the facility within a radius that includes the closest Point of Reception identified in Step 1. The figure must include a legend and scale.

The actual separation distance is calculated from the closest facility wall or outside noise source, such as a dust collector located outside the facility, to the Property Line of the selected Point of Reception. For rural receptors in Class 3 Areas, where properties may be larger and may include areas that would not be considered noise-sensitive, Points of Reception are limited to locations within 30 metres of a dwelling or a camping area, where sound or vibration originating from other than those premises is received. The location of the closest Point of Reception must be shown on the figure and the actual separation distance from the facility to the Property line of the closest Point of Reception must also be shown as a line on the figure, measured in metres.

Base maps showing the features of the surrounding neighbourhood may be obtained from the Local Municipality, Ministry of Natural Resources or other mapping companies.

The plan may include the location and features of all buildings surrounding the facility and include the topography of the surrounding area should it have an effect on the transmission of noise to a Point of Reception. However for the Screening Process this is usually not necessary. This information is required for a more detailed noise assessment.

Note: For larger facilities with outdoor noise sources, this process may have to be repeated for each outdoor noise source and different Points of Reception in order to identify the shortest actual separation distance to the closest Point of Reception.

## STEP 3 – CALCULATE MINIMUM REQUIRED SEPARATION DISTANCE

Applicants are required to complete the Noise Screening Process questionnaire to calculate the minimum required separation distance that will result in compliance with the noise guidelines for the facility. Generic separation distances have been supplied that should provide a sufficient separation distance for a facility based on the type of operations conducted at the facility and the size and quantity of common noise sources associated with the type of facility under review. The minimum required distances have been provided from 1,000 m to 50 m. If a facility is closer to a Point of Reception than 50 m, you can not use this process. Conversely, if a facility is well sited, located more than 1,000m from a Point of Reception, then a detailed noise assessment is not required.

Applicants must use the North American Industry Classification System (NAICS) Code required by the application form to describe the facility. The NAICS code is determined in accordance with the Statistics Canada publication “North American Industry Classification System (NAICS) 2002 - Canada”. For more information on determining the NAICS Code for a business please see [www.statcan.ca](http://www.statcan.ca). This screening process only applies to facilities with NAICS Codes starting with 21, 22, 31, 32 or 33. **If the NAICS code for the facility does not fall into one of these sectors then this step of the Screening Process can not be used.**

The following explanations are intended to assist with completing the Questionnaire:

Table 1.2 The presence of any one piece of equipment identified on this table should be indicated in the appropriate check box. The reference to fans and blowers is for individual large fans or blowers only. It is not required to sum the total volumetric flow rate or pressure drops across all fans or blowers at the facility. The applicant

must include any fans or blowers located on delivery trucks that supply or transport raw materials or products from the facility.

Table 1.2 The applicant must identify large atmospheric vents that are associated with process pressure vessels, or piping such as natural gas blow down valves at pipeline compressor stations. This category of equipment is not intended to capture mandatory steam release valves from commercial boilers.

Question 3 For each type of equipment identified on this table the total rating for all similar pieces of equipment should be summed and indicated in the appropriate question.

Question 3(f) The applicant is required to sum the total maximum volumetric flow rate for all process or general ventilation fans or blowers at the facility that are not directly referenced elsewhere in the table. If fans are capable of operating at two speeds the higher volumetric flow rate should be used. It is not necessary to include fans associated with cooling towers or part of packaged HVAC equipment. Fans serving condensers or other cooling units should be included. The applicant must include any fans or blowers located on delivery trucks that supply or transport raw materials or products from the facility.

Question 3(g) The applicant is required to identify if any motors powering any of the fans, blowers or air compressors are located outside the building envelope. For example if a fan serving a dust collector is located outside then the answer is yes. If the fan and dust collector are inside the building envelope the answer is no.

#### **STEP 4: STATEMENT FACILITY MEETS SCREENING REQUIRMENTS**

If an applicant can demonstrate through this screening process that the actual separation distance from the facility to the closest Point of Reception shown on the Scaled Area Location Plan is greater than the minimum required separation distance calculated in Step 3, then the person who conducted the Noise Screening Process must complete and sign off in Step 4.



# APPENDIX B

Notes to Table:

- Wherever possible, the Source ID matches the identifiers used in the ESDM report.
- Sound Power Level of Source, in dBA, not including sound characteristic adjustments per NPC-104.
- Source Location: O = Outside of building, including the roof, I = Inside of building.
- Sound Characteristic, per NPC-104:  
 - S = Steady  
 - Q = Quasi-Steady Impulsive  
 - I = Impulsive  
 - B = Buzzing  
 - T = Tonal  
 - C = Cyclic
- Noise control measures currently in place or specified in construction drawings:  
 - S = Silencer/Muffler  
 - A = Acoustic lining, plenum  
 - B = Barrier  
 - L = Lagging  
 - E = Acoustic enclosure  
 - O = Other  
 - U = Uncontrolled

Where noise control measures are specified in construction drawings or were found on existing equipment, octave band sound power levels include the effects of the noise control measures. Noise control measures recommended in the mitigation section of this report are not included in this table.

- Source type indicates Cadna/A modelling methodology. For Point, Line, and Area sources, PWLs represent the overall level for the entire source. Where source type is Truck Route, the source is modelled as a moving point source, and PWL is calculated from a single-vehicle passby.
- Sound Power Level Data Source:  
 - Man = Manufacturer's Data  
 - Mea = Measured Directly  
 - Pre = Pre-tender Package  
 - EC = Engineering Calc based on specifications  
 - Same ### = same type as source no. ###  
 - File = Measurement on File at RWDI

Source ID <sup>[1]</sup>	Source Description	Sound Power Level <sup>[2]</sup> (dBA)	Source Location <sup>[3]</sup> (I or O)	Sound Characteristics <sup>[4]</sup> (S,Q,I,B,T,C)	Noise Control Measures <sup>[5]</sup> (S,A,B,L,E,O,U)	1/1 Octave Band Sound Power Level Data if available (dB)								Source Type <sup>[6]</sup>	PWL Data Source <sup>[7]</sup>	Height Above Roof (m)	Local Roof Height Ab. Grade (m)	Height Above Grade (m)	Source Co-ordinates for point sources (m)			Operating Times Mintues per Hour	Quieter than average equipment
						31.5	63	125	250	500	1000	2000	4000						8000	X	Y		
Gen150_e	150 kW Emergency Generator	113	O	S	E,S									Point	Man	-	-	394.9	528916	5512129	394.9	60.0	
Gen600_e	600 kW Emergency Generator	114	O	S	E,S									Point	Man	-	-	396.4	528925	5512129	396.4	60.0	
ML_Blwr_o	Blower	91	O	S	U									Point	EC	-	-	394.3	528946	5512126	394.3	60.0	
ML_Crshr_o	Jaw Crusher	99	O	S	U									Point	File	-	-	396.3	528689	5511955	396.3	60.0	✓
ML_FEx_o	Furnance Exhaust	74	O	S	U									Point	File	2.5	8.0	405.0	528966	5512070	405.0	60.0	
ML_KF_o	Kiln Fan	94	O	S	U									Point	Man	2.5	8.0	405.0	528945	5512069	405.0	60.0	
ML_ldr_o	Front End Loader	100	O	S	U									Point	File	-	-	396.4	528655	5511962	396.4	30.0	✓
ML_Rckdrp_o	Rock Drop	119	O	S	U									Point	File	-	-	396.8	528676	5511955	396.8	1.3	
OP_Dpump1_o	Dewatering Pump at 180m Head	101	O	S	U									Point	EC	-	-	392.2	527523	5511828	392.2	60.0	
OP_DRILL1_o	Drill	107	O	S	U									Point	Mea	-	-	399.6	527847	5511952	399.6	30.0	
OP_DRILL2_o	Drill	107	O	S	U									Point	Mea	-	-	395.7	527532	5511893	395.7	30.0	
OP_DZR_lowgrade_o	CAT D8N dozer	100	O	S	U									Point	File	-	-	398.6	528471	5511818	398.6	30.0	✓
OP_DZR_overburden_o	CAT D8N dozer	110	O	S	U									Point	File	-	-	407.5	527551	5511497	407.5	30.0	
OP_DZR_waste_o	CAT D8N dozer	110	O	S	U									Point	File	-	-	397.2	527604	5512244	397.2	60.0	
OP_Excvt1_o	Hydraulic Excavator	101	O	S	U									Point	File	-	-	400.6	527939	5511932	400.6	60.0	✓
OP_Excvt2_o	Hydraulic Excavator	106	O	S	U									Point	File	-	-	394.1	527548	5511822	394.1	60.0	
OP_Rckdrp_lowgrade_o	Rock Drop	112	O	S	U									Point	File	-	-	397.1	528461	5511833	397.1	2.3	
OP_Rckdrp_overburden_o	Rock Drop	112	O	S	U									Point	File	-	-	406.0	527617	5511529	406.0	2.3	
OP_Rckdrp_waste_o	Rock Drop	112	O	S	U									Point	File	-	-	397.1	527658	5512227	397.1	2.3	
UG_ExVentRaise1_o	Exhaust Vent Raise 1	116	O	S	U									Point	Man	-	-	392.6	527629	5511652	392.6	60.0	
UG_ExVentRaise2_o	Exhaust Vent Raise 2	111	O	S	U									Point	Man	-	-	397.9	528835	5512296	397.9	60.0	✓
UG_VentRaise1_o	Fresh Air Intake Vent Raise	116	O	S	U									Point	Man	-	-	397.4	528124	5511885	397.4	60.0	
ML_ExLvr01_o	Building Vent 1	90	O	S	U									Point	EC	-	-	401.5	528976	5512139	401.5	60.0	
ML_ExLvr02_o	Building Vent 2	90	O	S	U									Point	EC	-	-	402.0	528977	5512165	402.0	60.0	
ML_ExLvr03_o	Building Vent 3	90	O	S	U									Point	EC	-	-	400.2	528986	5512072	400.2	60.0	
ML_ExLvr04_o	Building Vent 4	90	O	S	U									Point	EC	-	-	400.7	528976	5512100	400.7	60.0	
ML_ExLvr05_o	Building Vent 5	90	O	S	U									Point	EC	-	-	401.1	528976	5512120	401.1	60.0	
ML_ExLvr06_o	Building Vent 6	90	O	S	U									Point	EC	-	-	399.9	528965	5512058	399.9	60.0	
ML_ExLvr07_o	Building Vent 7	90	O	S	U									Point	EC	-	-	400.0	528937	5512058	400.0	60.0	
ML_ExLvr08_o	Building Vent 8	90	O	S	U									Point	EC	-	-	402.7	528933	5512196	402.7	60.0	
ML_ExLvr09_o	Building Vent 9	90	O	S	U									Point	EC	-	-	402.4	528910	5512180	402.4	60.0	
ML_ExLvr10_o	Building Vent 10	90	O	S	U									Point	EC	-	-	402.1	528933	5512164	402.1	60.0	
ML_ExLvr11_o	Building Vent 11	90	O	S	U									Point	EC	-	-	400.7	528933	5512093	400.7	60.0	
ML_ExLvr12_o	Building Vent 12	90	O	S	U									Point	EC	-	-	400.3	528923	5512073	400.3	60.0	
ML_ExLvr13_o	Building Vent 13	90	O	S	U									Point	EC	-	-	401.1	528934	5512115	401.1	60.0	
ML_ExLvr14_o	Building Vent 14	90	O	S	U									Point	EC	-	-	401.7	528959	5512150	401.7	60.0	
Htruck1_o	Haul Truck #1	107	O	S	U									Truck Route	File	-	-	-	-	-	-	60.0	✓
Htruck2_o	Haul Truck #2	107	O	S	U									Truck Route	File	-	-	-	-	-	-	60.0	✓
Htruck3_o	Haul Truck #3	107	O	S	U									Truck Route	File	-	-	-	-	-	-	60.0	✓

**Table B.2 : SOURCE LEVEL DATA AND SPL TO PWL CONVERSIONS - Version 3.4**  
 Treasury Metals Inc. – Goliath Gold Project - 1401701

**Notes to Table:**  
 1. All measurements conducted on April 22, 2014., using Larson Davis LD-824 SLM's / RTA's.  
 2. All measurements were consistent with ISO 3744:1994(E) and ISO 3746:1995 measurement standards, and the applicable portions of the MOE Publication NPC-103.  
 3. Calc Type of C, A, or S refer to the source geometry, and represent Cylindrical, Area, or Spherical sources, respectively.  
 4. SPL Ref Distance refers to the radial distance from the microphone to the acoustic centre of a spherical source or the symmetrical axis of a cylindrical source.  
 5. Length refers to the length of a cylindrical source or line source. A length of 1.0 m may be used to define a PWL per metre.  
 6. Net surface area refers to surface area corrected for partition coefficient. Partition coefficient applies only to spherical and cylindrical geometries. Sound power level is estimated using an area correction 10 log A.  
 7. Refer to "Spectral Weighting" column for dB or dBA application information.

Measurement Reference	Source ID	Source Description	Calc Type <sup>(3)</sup> (A, C, or S)	SPL Ref Distance <sup>(4)</sup> (S or C) (m)	Length <sup>(5)</sup> (C only) (m)	Area (A only) (m <sup>2</sup> )	Partition Coefficient (S or C) (%)	Net Surface Area <sup>(6)</sup> (m <sup>2</sup> )	Octave Band Sound Pressure Level Data (dB or dBA) <sup>(7)</sup>										Total (dBA)	Octave Band Sound Power Level Data (dB or dBA) <sup>(7)</sup>										Total (dBA)		
									Spectral Weighting (A or Flat)											Sound Power Level Adjustment (dB)		Purpose										
									31.5	63	125	250	500	1000	2000	4000	8000	31.5		Purpose	63	125	250	500	1000	2000	4000	8000				
140422 824 1401873 File_001.slmld	OP_DRILL1_o	Wire-line core diamond drill w/ enclosed diesel	S	14.50			50%	1320.4	Flat	69.5	65.4	72.7	72.1	66.0	63.9	62.4	56.3	50.0	70.0		100.7	Purpose	96.6	104.0	103.3	97.3	95.1	93.6	87.5	81.2	101.2	
140422 824 1401873 File_001.slmld	OP_DRILL2_o	Wire-line core diamond drill w/ enclosed diesel	S	14.50			50%	1320.4	Flat	69.5	65.4	72.7	72.1	66.0	63.9	62.4	56.3	50.0	70.0		100.7	Purpose	96.6	104.0	103.3	97.3	95.1	93.6	87.5	81.2	101.2	

**Table B.3 : Power Level Data**  
Treasury Metals Inc. – Goliath Gold Project - 1401701

Notes to Table:  
1. Refer to "Spectral Weighting" column for spectral weighting information.

Power Level Data Source	Source ID	Source Description	Sound Power Level Adjustment		Spectral Weighting (A or Flat)	Octave Band Sound Power Level Data (dB or dBA) <sup>[1]</sup>										Total dBA	Octave Band Sound Power Level Data (dB or dBA) <sup>[1]</sup>										Total dBA
			(dB)	Purpose		31.5	63	125	250	500	1000	2000	4000	8000	31.5		63	125	250	500	1000	2000	4000	8000			
Measurement on file	OP_Rckdrp_lowgrade_o	Rock Drop at low grade stockpile			Flat	100.2	106.4	116.2	106.7	109.1	103.0	103.5	102.9	102.7	111.6	100.2	106.4	116.2	106.7	109.1	103.0	103.5	102.9	102.7	111.6		
Measurement on file	OP_Rckdrp_overburden_o	Rock Drop at overburden stockpile			Flat	100.2	106.4	116.2	106.7	109.1	103.0	103.5	102.9	102.7	111.6	100.2	106.4	116.2	106.7	109.1	103.0	103.5	102.9	102.7	111.6		
Measurement on file	OP_Rckdrp_waste_o	Rock Drop at waste stockpile			Flat	100.2	106.4	116.2	106.7	109.1	103.0	103.5	102.9	102.7	111.6	100.2	106.4	116.2	106.7	109.1	103.0	103.5	102.9	102.7	111.6		
Measurement on file	ML_Rckdrp_o	Rock Drop at the crusher			Flat	114.1	115.7	120.7	122.4	112.7	113.9	111.2	106.1	100.4	119.3	114.1	115.7	120.7	122.4	112.7	113.9	111.2	106.1	100.4	119.3		
Engineering calculation	UG_ExVentRaise2_o	Exhaust Vent Raise 2			Flat		117.0	117.0	114.0	108.0	105.0	100.0	94.0	87.0	111.0		117.0	117.0	114.0	108.0	105.0	100.0	94.0	87.0	111.0		
Measurement on file	ML_Crshr_o	Crusher			Flat	88.5	86.5	87.5	90.5	93.5	94.5	93.5	89.5	82.5	99.2	88.5	86.5	87.5	90.5	93.5	94.5	93.5	89.5	82.5	99.2		
Measurement on file	ML_ldr_o	Loader			Flat	97.8	97.3	104.6	101.9	97.2	93.9	91.0	87.7	82.0	100.2	97.8	97.3	104.6	101.9	97.2	93.9	91.0	87.7	82.0	100.2		
Measurement on file	OP_Excvt1_o	Hydraulic Excavator			Flat	94.5	117.5	109.5	99.5	96.5	92.5	93.5	89.5	84.5	101.1	94.5	117.5	109.5	99.5	96.5	92.5	93.5	89.5	84.5	101.1		
Measurement on file	OP_Excvt2_o	Hydraulic Excavator			Flat	99.5	122.5	114.5	104.5	101.5	97.5	98.5	94.5	89.5	106.1	99.5	122.5	114.5	104.5	101.5	97.5	98.5	94.5	89.5	106.1		
Measurement on file	Htruck1_o	Haul Truck #1			Flat	99.5	95.5	101.5	103.5	102.5	102.5	101.5	94.5	89.5	107.2	99.5	95.5	101.5	103.5	102.5	102.5	101.5	94.5	89.5	107.2		
Measurement on file	Htruck2_o	Haul Truck #2			Flat	99.5	95.5	101.5	103.5	102.5	102.5	101.5	94.5	89.5	107.2	99.5	95.5	101.5	103.5	102.5	102.5	101.5	94.5	89.5	107.2		
Measurement on file	Htruck3_o	Haul Truck #3			Flat	99.5	95.5	101.5	103.5	102.5	102.5	101.5	94.5	89.5	107.2	99.5	95.5	101.5	103.5	102.5	102.5	101.5	94.5	89.5	107.2		
Measurement on file	OP_DZR_lowgrade_o	Dozer at low grade stockpile			Flat	95.5	96.3	101.1	94.2	95.1	95.3	94.2	88.1	79.3	100.0	95.5	96.3	101.1	94.2	95.1	95.3	94.2	88.1	79.3	100.0		
Measurement on file	OP_DZR_overburden_o	Dozer at overburden stockpile			Flat	105.5	106.3	111.1	104.2	105.1	105.3	104.2	98.1	89.3	110.0	105.5	106.3	111.1	104.2	105.1	105.3	104.2	98.1	89.3	110.0		
Measurement on file	OP_DZR_waste_o	Dozer at waste stockpile			Flat	105.5	106.3	111.1	104.2	105.1	105.3	104.2	98.1	89.3	110.0	105.5	106.3	111.1	104.2	105.1	105.3	104.2	98.1	89.3	110.0		



# Twin City Fan & Blower

A Twin City Fan Company

5959 Trenton Lane · Minneapolis, MN 55442-3238  
Phone (763) 551-7600 · Fax (763) 551-7601 · www.tcf.com



Sources:  
UG\_ExVentRaise1\_o  
UG\_VentRaise1\_o

Customer: W/A  
Job Name:  
Job ID: Goliath

July 16, 2014  
Page: 1

Fan Description	Fan Performance	Motor Data
Tag ..... ExVentRaise	CFM ..... 370,000	Motor not defined. ....
Type ..... BC-SW	Operating SP (in.wg) ..... 10	
Size ..... 982	Standard SP (in.wg) ..... 10	
Width ..... SWSI	RPM ..... 762	
Class ..... V	Tip Speed (fpm) ..... 19,600	
Wheel diameter (in.) ..... 98.25	Oper. BHP ..... 1172.10	
Drive method ... 60 Hz belt drive	Standard BHP ..... 1172.10	
Percentage width ..... 100%	Outlet area (sq. ft) ..... 55.5	
Percentage diameter ..... 100%	Outlet Velocity (fpm) ..... 6,667	
	Temperature (°F) ..... 70	
	Altitude (ft) ..... 0	
	Density (lb/ft <sup>3</sup> ) ..... 0.075	
	Max RPM for Class ..... 775	
	Static Efficiency ..... 49.62	
	Mechanical Efficiency .... 63.37	

## Sound

Sound Power Levels in dB re. 10<sup>-12</sup>Watts:

Octave Bands	1	2	3	4	5	6	7	8	LwA
Level at Inlet	122	122	119	113	110	105	99	92	116

Estimated sound pressure level in dBA (re: 0.0002 microbar) based on a single\* ducted installation:

Distance in ft	10
dBA at Inlet	99

\*To estimate dBA level for ducted inlet and ducted outlet (into and out of the room) type installation, deduct 20 from the LWA value shown.

Using a directivity factor of 2.

Estimated Sound Pressure based on free field, hemispherical (Q = 2) radiation at the stated distance.

Definitions:

LwA The overall (single value) fan sound power level, 'A' weighted.

dBA The environment for each fan installation influences its measured sound value, therefore dBA levels cannot be guaranteed. Consult AMCA Publication 303 for further details.  
A fan's dBA is influenced by nearby reflective surfaces.



# Twin City Fan & Blower

*A Twin City Fan Company*

5959 Trenton Lane · Minneapolis, MN 55442-3238  
Phone (763) 551-7600 · Fax (763) 551-7601 · [www.tcf.com](http://www.tcf.com)



Customer: W/A  
Job Name:  
Job ID: Goliath

July 16, 2014  
Page: 2



1. Twin City Fan and Blower certifies that the model BC-SW is licensed to bear the AMCA Seal. The ratings shown are based on tests and procedures performed in accordance with AMCA Publication 211 and AMCA Publication 311 and comply with the requirements of the AMCA Certified Ratings Program.
2. Performance shown is for Installation Type B & D: Free or ducted inlet, Ducted outlet.
3. Power rating (BHP) does not include belt drive losses.
4. Performance ratings do not include the effects of appurtenances in the airstream.
5. The sound power level ratings shown are in decibels, referred to 10 E-12 watts calculated per AMCA Standard 301.
6. Values shown are for inlet Lwi and LwiA sound power levels for Installation Type B: Free inlet, Ducted outlet.
7. Ratings do not include the effects of duct end correction.
8. The A-weighted sound ratings shown have been calculated per AMCA Standard 301.



# Twin City Fan & Blower

A Twin City Fan Company

5959 Trenton Lane · Minneapolis, MN 55442-3238  
Phone (763) 551-7600 · Fax (763) 551-7601 · www.tcf.com



Source:  
ML\_KF\_o

Customer: W/A  
Job Name:  
Job ID: Goliath

July 17, 2014  
Page: 1

Fan Description	Fan Performance	Motor Data
Tag ..... Kiln Fan	CFM ..... 10,000	Motor not defined. ....
Type ..... BC-SW	Operating SP (in.wg) ..... 4	
Size ..... 245	Standard SP (in.wg) ..... 4	
Width ..... SWSI	RPM ..... 1611	
Class ..... II	Tip Speed (fpm) ..... 10,333	
Wheel diameter (in.) ..... 24.5	Oper. BHP ..... 9.93	
Drive method ... 60 Hz belt drive	Standard BHP ..... 9.93	
Percentage width ..... 100%	Outlet area (sq. ft) ..... 3.45	
Percentage diameter ..... 100%	Outlet Velocity (fpm) ..... 2,899	
	Temperature (°F) ..... 70	
	Altitude (ft) ..... 0	
	Density (lb/ft <sup>3</sup> ) ..... 0.075	
	Max RPM for Class ..... 2033	
	Static Efficiency ..... 63.30	
	Mechanical Efficiency .... 71.59	

## Sound

Sound Power Levels in dB re. 10-12Watts:

Octave Bands	1	2	3	4	5	6	7	8	LwA
Level at Inlet	95	93	93	93	90	85	79	72	95

Estimated sound pressure level in dBA (re: 0.0002 microbar) based on a single\* ducted installation:

Distance in ft	1	3	5
dBA at Inlet	95	85	81

\*To estimate dBA level for ducted inlet and ducted outlet (into and out of the room) type installation, deduct 20 from the LWA value shown.

Using a directivity factor of 1.

Estimated Sound Pressure based on free field, spherical (Q = 1) radiation at the stated distance.

### Definitions:

LwA The overall (single value) fan sound power level, 'A' weighted.

dBA The environment for each fan installation influences its measured sound value, therefore dBA levels cannot be guaranteed. Consult AMCA Publication 303 for further details.  
A fan's dBA is influenced by nearby reflective surfaces.





# Twin City Fan & Blower

*A Twin City Fan Company*

5959 Trenton Lane · Minneapolis, MN 55442-3238  
Phone (763) 551-7600 · Fax (763) 551-7601 · [www.tcf.com](http://www.tcf.com)



Customer: W/A  
Job Name:  
Job ID: Goliath

July 17, 2014  
Page: 2



1. Twin City Fan and Blower certifies that the model BC-SW is licensed to bear the AMCA Seal. The ratings shown are based on tests and procedures performed in accordance with AMCA Publication 211 and AMCA Publication 311 and comply with the requirements of the AMCA Certified Ratings Program.
2. Performance shown is for Installation Type B & D: Free or ducted inlet, Ducted outlet.
3. Power rating (BHP) does not include belt drive losses.
4. Performance ratings do not include the effects of appurtenances in the airstream.
5. The sound power level ratings shown are in decibels, referred to 10 E-12 watts calculated per AMCA Standard 301.
6. Values shown are for inlet Lwi and LwiA sound power levels for Installation Type B: Free inlet, Ducted outlet.
7. Ratings do not include the effects of duct end correction.
8. The A-weighted sound ratings shown have been calculated per AMCA Standard 301.



**Sound Pressure Levels @ 7 meters dB(A)**

Configuration		Position (Note 1)								8 Position Average
		1	2	3	4	5	6	7	8	
Standard - Unhoused (Note 3)	Infinite Exhaust	79.9	85.3	84.3	86.3	80.3	85.1	83.4	85.0	83.7
F182 and F216-Weather (Note 3)	Infinite Exhaust	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
F182 and F216-Weather	Mounted Muffler	87.5	87.7	87.8	86.2	84.7	87.8	88.0	89.4	87.4
F172 - Quiet Site II First Stage	Mounted Muffler	81.8	82.8	76.9	76.1	72.1	70.8	73.6	82.6	77.1
F173 and F217 - Quiet Site II Second Stage	Mounted Muffler	73.1	73.4	74.6	74.2	70.1	68.2	69.3	71.8	71.8

Note:

1. Position 1 faces the engine front at 23 feet (7 m) from the center of the generator set. The positions proceed around the generator set in a counter-clockwise direction in 45° increments.
2. Data based on full rated load with standard radiator-fan package.
3. Sound data for generator set with infinite exhaust do not include exhaust noise.
4. Sound pressure levels per ANSI S1.13-1971 as applicable.
5. Reference sound pressure is 20 µPa.
6. Sound pressure levels are subject to instrumentation, measurement, installation and generator set variability.
7. Sound pressure levels for aluminum enclosures are approximately 2dB(A) higher than listed sound pressure levels for steel enclosures.

**Sound Power Levels dB(A)**

Configuration		Octave Band Center Frequency (Hz)								Sound Power Level
		63	125	250	500	1000	2000	4000	8000	
Standard - Unhoused (Note 3)	Infinite Exhaust	75.6	91.5	97.3	102.2	106.7	106.1	99.6	95.5	110.9
F182 and F216-Weather	Mounted Muffler	101.7	95.3	97.7	108.1	107.3	105.5	102.2	99.7	113.1
F172 - Quiet Site II First Stage	Mounted Muffler	94.2	90.7	91.1	97.6	101.1	101.0	95.6	90.7	106.1
F173 and F217- Quiet Site II Second Stage	Mounted Muffler	92.4	88.9	87.4	87.7	90.9	89.7	87.9	87.9	98.3

Note:

1. Data based on full rated load with standard radiator-fan package.
2. Sound power per ANSI S12.34-1988 and ISO 3744 as applicable.
3. Sound data for generator set with infinite exhaust do not include exhaust noise.
4. Reference sound power is  $1pW=1 \times 10^{-12}$  W.
5. Sound power levels are subject to instrumentation, measurement, installation and generator set variability.
6. Sound power levels for aluminum enclosures are approximately 2dB(A) higher than listed sound power levels for steel enclosures.



Source:  
Gen600\_e

**Sound Pressure Levels @ 7 meters dB(A)**

Configuration		Position (Note 1)								8 Position Average
		1	2	3	4	5	6	7	8	
Standard-Unhoused (Note 3)	Infinite Exhaust	90.6	91.9	88.5	89.8	86.1	90.3	90.9	91	90.2
F200 - Weather	Mounted Muffler	88.1	88.7	78.2	82.9	85.3	80.9	76.8	87.8	85.2
F201 - Quiet Site II First Stage	Mounted Muffler	75	74.1	74	79	83.7	77.6	72.1	72.7	78.1
F202 - Quiet Site II Second Stage	Mounted Muffler	73.9	74.8	74.5	73.3	72.6	72.4	73.1	74.1	73.7
Unhoused - Remote Cooled (Note 3 & 7)	Infinite Exhaust	87.2	90.1	87.5	89.2	85.2	89.6	90.1	89.2	88.8

Note:

1. Position 1 faces the engine front at 23 feet (7 m) from the surface of the generator set. The positions proceed around the generator set in a counter-clockwise direction in 45° increments.
2. Data based on full rated load with standard radiator-fan package.
3. Sound data for generator set with infinite exhaust do not include exhaust noise.
4. Sound pressure levels per ANSI S1.13-1971 as applicable.
5. Reference sound pressure is 10 µPa.
6. Sound pressure levels are subject to instrumentation, measurement, installation and generator set variability.
7. Sound data with remote-cooled sets are based on rated loads without fan noise.

**Sound Power Levels dB(A)**

Configuration		Octave Band Center Frequency (Hz)								Sound Power Level
		63	125	250	500	1000	2000	4000	8000	
Standard-Unhoused (Note 3)	Infinite Exhaust	81.8	98	105.5	111.7	111.8	111.1	108.3	103	117.5
F200 - Weather	Mounted Muffler	83.4	94.9	103.3	108.3	108.5	106.9	103.3	98.8	107.1
F201 - Quiet Site II First Stage	Mounted Muffler	83.4	92.7	99.4	100.8	99.5	99.7	97.1	92.6	107.1
F202 - Quiet Site II Second Stage	Mounted Muffler	83.4	91.4	93.5	92.9	96.1	98.4	97.1	89.9	104.2
Unhoused - Remote Cooled (Note 3 & 6)	Infinite Exhaust	81.2	93.7	103.2	109	109.5	109.9	107.6	102.2	115.7

Note:

1. Sound pressure levels per ANSI S12.34-1988 and SIO 3744 as applicable.
2. Data based on full rated load with standard radiator-fan package.
3. Sound data for generator set with infinite exhaust do not include exhaust noise.
4. Reference sound pressure is 1pW-1x10<sup>-12</sup> W.
5. Sound pressure levels are subject to instrumentation, measurement, installation and generator set variability.
6. Sound data with remote-cooled sets are based on rated loads without fan noise.

**Exhaust Sound Pressure Levels @ 1 meter dB(A)**

Open Exhaust (No Muffler) @ Rated Load	Octave Band Center Frequency (Hz)								Sound Pressure Level
	63	125	250	500	1000	2000	4000	8000	
	78.9	93.6	105.2	100.8	104.7	107.9	106.9	102.4	112.7

Note: Sound pressure level per ISO 6798 Annex A as applicable.

**MOTOR-DRIVEN PUMPS v1.2**

**Sound Level Estimation**


Based on Bies and Hansen, Engineering Noise Control 4th edition  
 Reference: D. A. Bies and C. H. Hansen, 2009. Engineering Noise Control: Theory and Practice, New York, USA.

Project #: 1401701  
 Project Name: Treasury Metals Inc. – Goliath Gold Project

Source:  
OP\_Dpump1\_o



Bies and Hansen Text



**CALCULATION 1: PUMP UNITS**

PROPERTIES									PUMP UNITS															
Tag ID	Description	Qty	Power			Speed		Load %	Formula	SPL@1m dB	Q-factor	PWL dB	Octave Band Sound Level Data (dB)								Overall Level			
			kW	hp	Class	rpm	Class						31.5	63	125	250	500	1000	2000	4000	8000	dB	dBA	dB(C)
1 Dpump	Dewatering Pump at 180m He	1	40	54	A	1800	P3	100	SPL = 75 + 10logkW	91	2	99	86.0	87.0	88.0	90.0	90.0	93.0	90.0	86.0	80.0	98.5	96.6	98.2

**CALCULATION 2a: ELECTRIC MOTORS <300 kW (TYPE M1)**

PROPERTIES											PUMP DRIVERS (ELECTRIC MOTORS) <300 kW															
Tag ID	Description	Qty	Power			Speed rpm	Load %	Motor Type	Fan Type	Adj.	Formula	SPL@1m dB	Q-factor	PWL dB	Octave Band Sound Level Data (dB)								Overall Level			
			kW	hp	Class										31.5	63	125	250	500	1000	2000	4000	8000	dB	dBA	dB(C)
1 Dpump	Dewatering Pump at 180m He	1	40	54	A	1800	100	TEFC	normal	0	SPL = 17 + 17logkW + 15logRPM	93	2	101	87.0	87.0	90.0	92.0	95.0	95.0	94.0	89.0	81.0	101.3	99.7	101.1

**CALCULATION 3: COMBINED PUMPS AND ELECTRIC MOTORS**

PROPERTIES											COMBINED PUMP AND MOTOR SOUND POWER LEVEL														
Tag ID	Description	Qty	Power			Speed rpm	Load %	Pump Driver			Formula	SPL@1m dB	Q-factor	PWL dB	Octave Band Sound Level Data (dB)								Overall Level		
			kW	hp	Class			Type	Fan Type	31.5					63	125	250	500	1000	2000	4000	8000	dB	dBA	dB(C)
1 Dpump	Dewatering Pump at 180m He	1	40	54	M1	1800	100	TEFC	normal					89.6	90.0	92.2	94.2	96.2	97.2	95.5	90.8	83.6	103	101	103

## Fan Sound Power Levels

PWL generation and/or PWL/SPL shaping

### Source Information

From 1991 ASHRAE Handbook of Fundamentals Chapter 42

Type	Fan Type	Description
1	Centrifugal	Airfoil (AF), Backward Curved (BC), Backward Inclined (BI) > 36" dia. (900 mm)
2		AF, BC, BI fans < 36" (900mm)
3		Forward Curved (FC) (All fan sizes) USE FOR CENTRIFUGAL IF EXACT TYPE IS UNKNOWN
4		Radial Bladed Low Pressure, 4 to 10" H2O (1 to 2.5 kPa)
5		Radial Bladed Medium Pressure, 6 to 15" H2O (1.5 to 3.7 kPa)
6		Radial Bladed High Pressure, 15 to 60" H2O (3.7 to 15 kPa)
7	Vaneaxial	Hub Ratio 0.3 to 0.4
8		Hub Ratio 0.4 to 0.6
9		Hub Ratio 0.6 to 0.8 USE FOR VANEAXIAL IF EXACT TYPE IS UNKNOWN
10	Tubeaxial	Wheel dia. > 40" (1000 mm)
11		Wheel dia. < 40" (1000 mm)
12	Propeller	General Ventilation / Cooling Tower

Notes:

Source:  
ML\_FEx\_o

### Unit Conversions

### Calculation

Tag number / Description	Type	Flowrate (cfm)	Static Pressure (in. w.c.)	Fan Power (HP)	Motor Power (HP)	Number of Blades	rpm	Peak Efficiency (%)	given levels (for shaping)			Total Fan Level									
									Value	A-Weighted (y/n)	PWL or SPL	Output Type	Octave Band Frequencies							Overall Level	
													63	125	250	500	1000	2000	4000		8000
Furnace Exhaust	3	1177.16	0.803	0.15				85				PWL	84.8	84.8	74.8	69.8	67.8	62.8	57.8	52.8	88.1 dB

# Calculation of building ventilation

Sources:  
ML\_ExLvr01\_o  
through to  
ML\_ExLvr14\_o

<u>Number of vents</u>	14
<u>Air Changes/hr</u>	6
<u>Radiating Surface Area</u>	
<u>A= Area (m<sup>3</sup>)</u>	9200
<u>Required Louvre Area (m<sup>2</sup>)</u>	31
<u>Louvre Area (m<sup>2</sup>)</u>	1.5
<u>Fan Area (m<sup>2</sup>)</u>	0.8
<u>Reverberant Power Level in the Room (dBA)</u>	85
<u>Sound Power Level per m<sup>2</sup> (dBA)</u>	85

## Exhaust

	31.5	63	125	250	500	1000	2000	4000	8000	PWL(A)
Fan	73.0	74.0	77.0	84.0	82.0	81.0	78.0	72.0	68.0	85.3
Opening (PWL")	78.0	78.0	78.0	78.0	78.0	78.0	78.0	78.0	78.0	85.0
Area correction	-1.0	-1.0	-1.0	-1.0	-1.0	-1.0	-1.0	-1.0	-1.0	
Area corrected PWL	77.0	77.0	77.0	77.0	77.0	77.0	77.0	77.0	77.0	84.0
Total Exhaust	78.5	78.8	80.0	84.8	83.2	82.4	80.5	78.2	77.5	87.7

## Inlet

	31.5	63	125	250	500	1000	2000	4000	8000	PWL(A)
Opening (PWL")	78.0	78.0	78.0	78.0	78.0	78.0	78.0	78.0	78.0	85.0
Area correction	1.8	1.8	1.8	1.8	1.8	1.8	1.8	1.8	1.8	
Area corrected PWL	79.8	79.8	79.8	79.8	79.8	79.8	79.8	79.8	79.8	86.7

## Combined

	82.2	82.3	82.9	86.0	84.8	84.3	83.2	82.1	81.8	90.3
--	------	------	------	------	------	------	------	------	------	------

Blower Calculation (Crocker, 2007)

6.1 Centrifugal Blower Sound Power–Shaft Power Correlation

Realizing that acoustic efficiency ( $\eta$ ) is sound power divided by the mechanical power that drives the source, Beranek et al.<sup>10</sup> developed empirical noise formulations based on shaft horsepower of the fan. The sound power radiation from a wide class of blowers (where  $\eta = 10^{-6}$ ) operating in the ducts of building ventilation systems formed the foundation of this investigation. The authors measured the sound power spectrum from 14 different blowers operating in several different systems. The overall sound power measured in these experiments correlated to

$$L_W = 90 + 10 \log_{10} \text{SHP re } 10^{-12} \text{ W} \quad (10)$$

where SHP is the shaft power of the blower in horsepower. The measured data for the group of fans used in this study yield a spread of about  $\pm 4$  dB about the line computed from Eq. (10). The octave band sound power spectrum was found to slope off with increasing frequency at a rate of 5 dB per octave. The level of the first band, centered at 20 Hz, is 1 dB below the overall level predicted by Eq. (10).

Shaft Horse Power            100.6

	31.5	63	125	250	500	1000	2000	4000	8000	Total dBA
Calculated Sound Power Level	110	110	110	110	110	110	110	110	110	
Spectrum Reduction	1	6	11	16	21	26	31	36	41	
Corrected Sound Power Level	109	104	99	94	89	84	79	74	69	<b>91.4</b>



# Blasting Vibration Calculation

References: ISEE Blaster Handbook

## Ground Vibration

### Equations:

$$PPV = 3330(SD)^{-1.52}$$

$$SD = R/W^{1/2}$$

### Where:

- PPV Peak particle velocity (millimeters per second)
- SD Square root scaled distance
- R Distance (meters) between the blast and point of interest
- W Maximum weight of explosive (kilograms) detonated per delay period

### Project-specific parameters:

- Maximum PPV PPV 10 mm/sec (as specified in NPC-110)
- Maximum charge W 100 kg per delay
- Distance R (unknown) meters

### Calculation:

Receptor	D (m)	W (kg)	SD	PPV (mm/sec)
Location of Maximum PPV	457	100	45.7	9.99
NR03	1813	100	181.253	1.23
NR04	3000	100	300.047	0.57
NR30	2373	100	237.341	0.82
NR44	3734	100	373.418	0.41
NR47	3187	100	318.707	0.52

**Blasting Noise Calculation**

Reference: ISEE Blaster Handbook

Receptor	Distance (m)	Charge - Weight (Kg)	Scaled Distance	Peak Air Pressure (Pa)	Peak Sound Pressure Level (dB)
Cautionary Limit	95	100	20	19.52	120
NR03	1813	100	390	0.16	78
NR04	3000	100	646	0.07	71
NR30	2373	100	511	0.11	75
NR44	3734	100	805	0.05	68
NR47	3187	100	687	0.07	70

**Scaled Distance**

$$\text{Scaled distance (SD}_3\text{)} = R / \sqrt[3]{W}$$

where R = distance (metres) from the blast to a point of interest; and,

W = charge-weight (kilograms) detonated within any 8-millisecond delay period.

**Peak Air Pressure**

$$P = 37.1 \times \text{SD}_3^{-0.97}$$

where P = peak air pressure (Pascals); and,

SD<sub>3</sub> = scaled distance (metres per kilogram [m/kg<sup>1/3</sup>]).

**Peak Sound Pressure Level**

$$\text{dB} = 20 \log(P/P_0)$$

where P<sub>0</sub> is the reference pressure (2 x 10<sup>-5</sup> Pa).

# APPENDIX C

# MEASUREMENT EQUIPMENT

---



## Sound Level Meter 824 Kit 3

<b>Sound Level Meter</b>	
Make and Model	Larson-Davis Model 824 SLM and RTA
Serial No.	824A0988
<b>Pre-amplifier</b>	
Make and Model	Larson-Davis Model PRM902
Serial No.	1462
<b>Microphone</b>	
Make and Model	Larson-Davis Model 2559 precision air-condenser microphone
Serial No.	2800
<b>Calibrator</b>	
Make and Model	Larson-Davis CAL200 precision acoustic calibrator (1000 Hz)
Serial No.	2570



# Weather

[Home](#) > [Weather](#) > [Local Forecasts](#) > [Ontario](#) > [Provincial Summary](#)

## Dryden Airport, Ontario

### Past 24 Hour Conditions

°C | [°F](#) [Table](#) | [Graph](#)

**This table is a summary of hourly weather conditions for the past 24 hours. This summary includes the following parameters: temperature, humidity, dew point, wind speed and direction, air pressure, visibility and/or wind chill and humidex.**

Date / Time (CDT)	Conditions	Temp (°C)	Humidity (%)	Dew Point (°C)	Wind (km/h)	Pressure (kPa)	Vis (km)	<a href="#">Wind Chill</a>
<b>23 April 2014</b>								
5:00	N/A	0	64	-6	SSE 11	102.1	16	*
4:00	Clear	1	63	-6	SSE 9	102.1	16	*
3:00	Clear	1	61	-6	S 4	102.1	16	*
2:00	Clear	2	52	-7	SW 9	102.1	16	*
1:00	Clear	3	50	-7	SW 8	102.1	16	*
00:00	Clear	5	43	-7	SSW 9	102.1	16	*
<b>22 April 2014</b>								
23:00	Clear	5	42	-7	S 11	102.0	16	*
22:00	Clear	4	44	-7	S 11	102.0	16	*
21:00	N/A	N/A	N/A	N/A	N/A	N/A	N/A	*
20:00	Sunny	8	31	-8	N 8	101.9	16	*
19:00	Sunny	9	29	-8	NNW 8	102.0	16	*
18:00	Sunny	10 ↑	30	-7	WNW 5	102.0	16	*
17:00	Sunny	9	32	-7	WNW 5	102.0	16	*
16:00	Sunny	9	31	-8	NNW 11	102.0	16	*
15:00	Sunny	9	33	-7	N 11	102.0	16	*
14:00	Sunny	8	33	-8	N 15	102.0	16	*
13:00	Sunny	7	36	-7	NNW 17 gust 34	102.1	16	*
12:00	Sunny	6	44	-5	NW 15 gust 28	102.1	16	*
11:00	Sunny	5	51	-4	NW 11 gust 30	102.1	16	*

10:00	Partly Cloudy	4	57	-4	NW 15	102.1	16	*
9:00	Sunny	2	73	-3	N 9	102.1	16	*
8:00	Sunny	0	83	-3	WNW 8	102.1	16	-3
7:00	Sunny	-2 ↓	89	-3	WNW 9	102.1	16	-5
6:00	Clear	-2 ↓	87	-4	NW 8	102.1	16	-5
5:00	Clear	-1	82	-4	WNW 8	102.1	16	-4

N/A Not available      ↑ Highest temperature      ↓ Lowest temperature

\* Value not significant.

If you require additional historical weather information, please visit [Climate Data Online](#).

Date modified: 2014-03-25



# APPENDIX D

**Table D.1: Key Parameters Included in the Cadna/A Noise Modelling**

Treasury Metals Inc. – Goliath Gold Project, 1401701

<b>Parameter</b>	<b>Value</b>	<b>Rationale</b>
Ground Absorption	0.8	Accounts for mostly soft (e.g., loose dirt, grass) surfaces between facility and receptors of interest
Temperature	10 °C	Ontario standard conditions
Relative Humidity	70%	Ontario standard conditions
Max. Order of Reflection	0	No significant reflections from buildings on site

## Cadna/A ISO-9613 Calculation Protocol - Definitions

Parameter	Unit	Definition
<b>X</b>	<b>(m)</b>	X-axis Cartesian coordinate
<b>Y</b>	<b>(m)</b>	Y-axis Cartesian coordinate
<b>Z</b>	<b>(m)</b>	Z-axis Cartesian coordinate
<b>Refl.</b>	<b>order</b>	Order of reflection
<b>Freq.</b>	<b>(Hz)</b>	1/1-Octave Frequency Band Centre Frequency
<b>LxT</b>	<b>(dBA)</b>	Daytime Sound Power Level
<b>LxN</b>	<b>(dBA)</b>	Night-time Sound Power Level
<b>K0</b>	<b>(dB)</b>	D_omega in ISO-9613 (correction for radiation into solid angles less than 4 Pi)
<b>Dc</b>	<b>(dB)</b>	Attenuation due to Directivity Effects
<b>Adiv</b>	<b>(dB)</b>	Attenuation Due to Divergence
<b>Aatm</b>	<b>(dB)</b>	Atmospheric Attenuation
<b>Agr</b>	<b>(dB)</b>	Ground Attenuation
<b>Afol</b>	<b>(dB)</b>	Attenuation due to foliage
<b>Ahous</b>	<b>(dB)</b>	Attenuation from houses
<b>Abar</b>	<b>(dB)</b>	Barrier Attenuation
<b>Cmet</b>	<b>(dB)</b>	Meteorological Correction
<b>RL</b>	<b>(dB)</b>	Reflection Loss
<b>LrT</b>	<b>(dBA)</b>	Resulting Daytime Noise Impacts at the receptor - Leq(1hr)
<b>LrN</b>	<b>(dBA)</b>	Resulting Night-time Noise Impacts at the receptor - Leq(1hr)

Configuration	
Parameter	Value
General	
Country	(user defined)
Max. Error (dB)	0.00
Max. Search Radius (m)	5000.00
Min. Dist Src to Rcvr	0.00
Partition	
Raster Factor	0.50
Max. Length of Section (m)	1000.00
Min. Length of Section (m)	1.00
Min. Length of Section (%)	0.00
Proj. Line Sources	On
Proj. Area Sources	On
Ref. Time	
Reference Time Day (min)	60.00
Reference Time Night (min)	60.00
Daytime Penalty (dB)	0.00
Recr. Time Penalty (dB)	0.00
Night-time Penalty (dB)	0.00
DTM	
Standard Height (m)	395.00
Model of Terrain	Triangulation
Reflection	
max. Order of Reflection	0
Search Radius Src	100.00
Search Radius Rcvr	100.00
Max. Distance Source - Rcvr	1000.00 1000.00
Min. Distance Rcvr - Reflector	1.00 1.00
Min. Distance Source - Reflector	0.10
Industrial (ISO 9613)	
Lateral Diffraction	some Obj
Obst. within Area Src do not shield	On
Screening	Excl. Ground Att. over Barrier
	Dz with limit (20/25)
Barrier Coefficients C1,2,3	3.0 20.0 0.0
Temperature (°C)	10
rel. Humidity (%)	70
Ground Absorption G	0.80
Wind Speed for Dir. (m/s)	3.0
Roads (RLS-90)	
Strictly acc. to RLS-90	
Railways (Schall 03)	
Strictly acc. to Schall 03 / Schall-Transrapid	
Aircraft (???)	
Strictly acc. to AzB	

Sample Calculation at facade of NR03

Receiver  
 Name: House - owned by Mcleish  
 ID: NR03  
 X: 528986.29  
 Y: 5511402.53  
 Z: 398.35

Point Source, ISO 9613, Name: "Blower", ID: "ML_Blwr_o"																				
Nr.	X	Y	Z	Refll.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT	LrN	
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)
1	528945.48	5512125.56	394.29	0	32	69.6	69.6	0.0	-1.8	68.2	0.0	-5.3	0.0	0.0	11.9	0.0	0.0	-7.0	-7.0	
2	528945.48	5512125.56	394.29	0	63	77.8	77.8	0.0	-3.7	68.2	0.1	-5.3	0.0	0.0	16.1	0.0	0.0	-4.9	-4.9	
3	528945.48	5512125.56	394.29	0	125	82.9	82.9	0.0	-7.4	68.2	0.3	5.4	0.0	0.0	15.4	0.0	0.0	-13.7	-13.7	
4	528945.48	5512125.56	394.29	0	250	85.4	85.4	0.0	-8.7	68.2	0.8	6.3	0.0	0.0	17.7	0.0	0.0	-16.3	-16.3	
5	528945.48	5512125.56	394.29	0	500	85.8	85.8	0.0	-9.9	68.2	1.4	6.0	0.0	0.0	18.7	0.0	0.0	-18.4	-18.4	
6	528945.48	5512125.56	394.29	0	1000	84.0	84.0	0.0	11.0	68.2	2.6	0.6	0.0	0.0	24.0	0.0	0.0	-22.4	-22.4	
7	528945.48	5512125.56	394.29	0	2000	80.2	80.2	0.0	11.0	68.2	7.0	-1.1	0.0	0.0	24.7	0.0	0.0	-29.7	-29.7	
8	528945.48	5512125.56	394.29	0	4000	75.0	75.0	0.0	11.0	68.2	23.7	-1.1	0.0	0.0	24.9	0.0	0.0	-51.7	-51.7	
9	528945.48	5512125.56	394.29	0	8000	67.9	67.9	0.0	11.0	68.2	84.6	-1.1	0.0	0.0	24.9	0.0	0.0	-119.8	-119.8	

Point Source, ISO 9613, Name: "Jaw Crusher", ID: "ML_Crshr_o"																				
Nr.	X	Y	Z	Refll.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT	LrN	
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)
1	528688.49	5511954.76	396.30	0	32	49.1	49.1	0.0	0.0	67.0	0.0	-5.0	0.0	0.0	0.0	0.0	0.0	-12.9	-12.9	
2	528688.49	5511954.76	396.30	0	63	60.3	60.3	0.0	0.0	67.0	0.1	-5.0	0.0	0.0	0.0	0.0	0.0	-1.7	-1.7	
3	528688.49	5511954.76	396.30	0	125	71.4	71.4	0.0	0.0	67.0	0.3	4.7	0.0	0.0	0.0	0.0	0.0	-0.5	-0.5	
4	528688.49	5511954.76	396.30	0	250	81.9	81.9	0.0	0.0	67.0	0.7	4.0	0.0	0.0	0.0	0.0	0.0	-10.3	10.3	
5	528688.49	5511954.76	396.30	0	500	90.3	90.3	0.0	0.0	67.0	1.2	-0.4	0.0	0.0	0.0	0.0	0.0	-22.5	22.5	
6	528688.49	5511954.76	396.30	0	1000	94.5	94.5	0.0	0.0	67.0	2.3	-1.0	0.0	0.0	0.0	0.0	0.0	-26.2	26.2	
7	528688.49	5511954.76	396.30	0	2000	94.7	94.7	0.0	0.0	67.0	6.1	-1.0	0.0	0.0	0.0	0.0	0.0	-22.7	22.7	
8	528688.49	5511954.76	396.30	0	4000	90.5	90.5	0.0	0.0	67.0	20.6	-1.0	0.0	0.0	0.0	0.0	0.0	-4.0	4.0	
9	528688.49	5511954.76	396.30	0	8000	81.4	81.4	0.0	0.0	67.0	73.3	-1.0	0.0	0.0	0.0	0.0	0.0	-57.9	-57.9	

Point Source, ISO 9613, Name: "Furnace Exhaust", ID: "ML_FEx_o"																				
Nr.	X	Y	Z	Refll.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT	LrN	
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)
1	528965.95	5512069.71	405.04	0	32	-39.4	-39.4	0.0	0.0	67.5	0.0	-3.6	0.0	0.0	0.0	0.0	0.0	-103.3	103.3	
2	528965.95	5512069.71	405.04	0	63	58.6	58.6	0.0	0.0	67.5	0.1	-3.6	0.0	0.0	0.0	0.0	0.0	-5.3	-5.3	
3	528965.95	5512069.71	405.04	0	125	68.7	68.7	0.0	0.0	67.5	0.3	2.1	0.0	0.0	0.0	0.0	0.0	-1.2	-1.2	
4	528965.95	5512069.71	405.04	0	250	66.2	66.2	0.0	0.0	67.5	0.7	0.4	0.0	0.0	0.0	0.0	0.0	-2.4	-2.4	
5	528965.95	5512069.71	405.04	0	500	66.6	66.6	0.0	0.0	67.5	1.3	-0.7	0.0	0.0	0.0	0.0	0.0	-1.5	-1.5	
6	528965.95	5512069.71	405.04	0	1000	67.8	67.8	0.0	0.0	67.5	2.4	-0.7	0.0	0.0	0.0	0.0	0.0	-1.4	-1.4	
7	528965.95	5512069.71	405.04	0	2000	64.0	64.0	0.0	0.0	67.5	6.5	-0.7	0.0	0.0	0.0	0.0	0.0	-9.2	-9.2	
8	528965.95	5512069.71	405.04	0	4000	58.8	58.8	0.0	0.0	67.5	21.9	-0.7	0.0	0.0	0.0	0.0	0.0	-29.8	-29.8	
9	528965.95	5512069.71	405.04	0	8000	51.7	51.7	0.0	0.0	67.5	78.0	-0.7	0.0	0.0	0.0	0.0	0.0	-93.1	-93.1	

Point Source, ISO 9613, Name: "Kiln Fan", ID: "ML_KF_o"																				
Nr.	X	Y	Z	Refll.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT	LrN	
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)
1	528944.46	5512068.63	405.04	0	63	68.8	68.8	0.0	0.0	67.5	0.1	-3.7	0.0	0.0	0.0	0.0	0.0	4.9	4.9	
2	528944.46	5512068.63	405.04	0	125	76.9	76.9	0.0	0.0	67.5	0.3	2.1	0.0	0.0	0.0	0.0	0.0	7.0	7.0	
3	528944.46	5512068.63	405.04	0	250	84.4	84.4	0.0	0.0	67.5	0.7	0.4	0.0	0.0	0.0	0.0	0.0	15.8	15.8	
4	528944.46	5512068.63	405.04	0	500	89.8	89.8	0.0	0.0	67.5	1.3	-0.7	0.0	0.0	0.0	0.0	0.0	21.8	21.8	
5	528944.46	5512068.63	405.04	0	1000	90.0	90.0	0.0	0.0	67.5	2.4	-0.7	0.0	0.0	0.0	0.0	0.0	20.8	20.8	
6	528944.46	5512068.63	405.04	0	2000	86.2	86.2	0.0	0.0	67.5	6.5	-0.7	0.0	0.0	0.0	0.0	0.0	13.0	13.0	
7	528944.46	5512068.63	405.04	0	4000	80.0	80.0	0.0	0.0	67.5	21.9	-0.7	0.0	0.0	0.0	0.0	0.0	-8.6	-8.6	
8	528944.46	5512068.63	405.04	0	8000	70.9	70.9	0.0	0.0	67.5	78.0	-0.7	0.0	0.0	0.0	0.0	0.0	-73.9	-73.9	

Point Source, ISO 9613, Name: "Front End Loader", ID: "ML_Ldr_o"																				
Nr.	X	Y	Z	Refll.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT	LrN	
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)
1	528654.89	5511961.82	396.35	0	32	55.4	55.4	0.0	0.0	67.3	0.0	-5.0	0.0	0.0	0.0	0.0	0.0	-6.9	-6.9	
2	528654.89	5511961.82	396.35	0	63	68.1	68.1	0.0	0.0	67.3	0.1	-5.0	0.0	0.0	0.0	0.0	0.0	5.8	5.8	

Sample Calculation at facade of NR03



Point Source, ISO 9613, Name: "Rock Drop", ID: "OP_Rckdrp_lowgrade_o"																			
Nr.	X (m)	Y (m)	Z (m)	Refl.	Freq. (Hz)	LxT dB(A)	LxN dB(A)	K0 (dB)	Dc (dB)	Adiv (dB)	Aatm (dB)	Agr (dB)	Afol (dB)	Ahous (dB)	Abar (dB)	Cmet (dB)	RL (dB)	LrT dB(A)	LrN dB(A)
1	528461.24	5511832.86	397.10	0	32	46.7	46.7	0.0	0.0	67.6	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-15.7	-15.7
2	528461.24	5511832.86	397.10	0	63	66.1	66.1	0.0	0.0	67.6	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	3.6	3.6
3	528461.24	5511832.86	397.10	0	125	86.0	86.0	0.0	0.0	67.6	0.3	5.2	0.0	0.0	0.0	0.0	-0.0	12.9	12.9
4	528461.24	5511832.86	397.10	0	250	84.0	84.0	0.0	0.0	67.6	0.7	6.3	0.0	0.0	0.0	0.0	-0.0	9.3	9.3
5	528461.24	5511832.86	397.10	0	500	91.8	91.8	0.0	0.0	67.6	1.3	6.0	0.0	0.0	0.0	0.0	-0.0	16.8	16.8
6	528461.24	5511832.86	397.10	0	1000	88.9	88.9	0.0	0.0	67.6	2.5	0.6	0.0	0.0	0.0	0.0	-0.0	18.2	18.2
7	528461.24	5511832.86	397.10	0	2000	90.6	90.6	0.0	0.0	67.6	6.6	-1.1	0.0	0.0	0.0	0.0	-0.0	17.4	17.4
8	528461.24	5511832.86	397.10	0	4000	89.8	89.8	0.0	0.0	67.6	22.3	-1.1	0.0	0.0	0.0	0.0	-0.0	1.0	1.0
9	528461.24	5511832.86	397.10	0	8000	87.5	87.5	0.0	0.0	67.6	79.3	-1.1	0.0	0.0	0.0	0.0	-0.0	-58.4	-58.4

Point Source, ISO 9613, Name: "Rock Drop", ID: "OP_Rckdrp_overburden_o"																			
Nr.	X (m)	Y (m)	Z (m)	Refl.	Freq. (Hz)	LxT dB(A)	LxN dB(A)	K0 (dB)	Dc (dB)	Adiv (dB)	Aatm (dB)	Agr (dB)	Afol (dB)	Ahous (dB)	Abar (dB)	Cmet (dB)	RL (dB)	LrT dB(A)	LrN dB(A)
1	527617.17	5511528.50	406.00	0	32	46.7	46.7	0.0	0.0	73.8	0.0	-5.6	0.0	0.0	4.8	0.0	-0.0	-26.3	-26.3
2	527617.17	5511528.50	406.00	0	63	66.1	66.1	0.0	0.0	73.8	0.2	-5.6	0.0	0.0	4.8	0.0	-0.0	-7.0	-7.0
3	527617.17	5511528.50	406.00	0	125	86.0	86.0	0.0	0.0	73.8	0.6	6.4	0.0	0.0	0.0	0.0	-0.0	5.2	5.2
4	527617.17	5511528.50	406.00	0	250	84.0	84.0	0.0	0.0	73.8	1.4	6.3	0.0	0.0	0.0	0.0	-0.0	2.5	2.5
5	527617.17	5511528.50	406.00	0	500	91.8	91.8	0.0	0.0	73.8	2.6	5.9	0.0	0.0	0.0	0.0	-0.0	9.4	9.4
6	527617.17	5511528.50	406.00	0	1000	88.9	88.9	0.0	0.0	73.8	5.0	0.5	0.0	0.0	4.3	0.0	-0.0	5.3	5.3
7	527617.17	5511528.50	406.00	0	2000	90.6	90.6	0.0	0.0	73.8	13.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-0.1	-0.1
8	527617.17	5511528.50	406.00	0	4000	89.8	89.8	0.0	0.0	73.8	45.1	-1.1	0.0	0.0	4.8	0.0	-0.0	-32.7	-32.7
9	527617.17	5511528.50	406.00	0	8000	87.5	87.5	0.0	0.0	73.8	160.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-150.6	-150.6

Point Source, ISO 9613, Name: "Rock Drop", ID: "OP_Rckdrp_waste_o"																			
Nr.	X (m)	Y (m)	Z (m)	Refl.	Freq. (Hz)	LxT dB(A)	LxN dB(A)	K0 (dB)	Dc (dB)	Adiv (dB)	Aatm (dB)	Agr (dB)	Afol (dB)	Ahous (dB)	Abar (dB)	Cmet (dB)	RL (dB)	LrT dB(A)	LrN dB(A)
1	527658.43	5512226.93	397.05	0	32	46.7	46.7	0.0	0.0	74.9	0.1	-5.7	0.0	0.0	4.8	0.0	-0.0	-27.3	-27.3
2	527658.43	5512226.93	397.05	0	63	66.1	66.1	0.0	0.0	74.9	0.2	-5.7	0.0	0.0	4.8	0.0	-0.0	-8.1	-8.1
3	527658.43	5512226.93	397.05	0	125	86.0	86.0	0.0	0.0	74.9	0.6	6.4	0.0	0.0	0.0	0.0	-0.0	4.0	4.0
4	527658.43	5512226.93	397.05	0	250	84.0	84.0	0.0	0.0	74.9	1.6	6.3	0.0	0.0	0.0	0.0	-0.0	1.2	1.2
5	527658.43	5512226.93	397.05	0	500	91.8	91.8	0.0	0.0	74.9	3.0	5.9	0.0	0.0	0.0	0.0	-0.0	8.0	8.0
6	527658.43	5512226.93	397.05	0	1000	88.9	88.9	0.0	0.0	74.9	5.7	0.5	0.0	0.0	4.3	0.0	-0.0	3.5	3.5
7	527658.43	5512226.93	397.05	0	2000	90.6	90.6	0.0	0.0	74.9	15.1	-1.1	0.0	0.0	4.8	0.0	-0.0	-3.0	-3.0
8	527658.43	5512226.93	397.05	0	4000	89.8	89.8	0.0	0.0	74.9	51.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-39.9	-39.9
9	527658.43	5512226.93	397.05	0	8000	87.5	87.5	0.0	0.0	74.9	182.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-173.7	-173.7

Point Source, ISO 9613, Name: "Exhaust Vent Raise 1", ID: "UG_ExVentRaise1_o"																			
Nr.	X (m)	Y (m)	Z (m)	Refl.	Freq. (Hz)	LxT dB(A)	LxN dB(A)	K0 (dB)	Dc (dB)	Adiv (dB)	Aatm (dB)	Agr (dB)	Afol (dB)	Ahous (dB)	Abar (dB)	Cmet (dB)	RL (dB)	LrT dB(A)	LrN dB(A)
1	527628.71	5511652.18	392.61	0	63	95.8	95.8	0.0	-3.7	73.8	0.2	-5.6	0.0	0.0	4.8	0.0	-0.0	19.0	19.0
2	527628.71	5511652.18	392.61	0	125	105.9	105.9	0.0	-7.4	73.8	0.6	6.4	0.0	0.0	0.0	0.0	-0.0	17.7	17.7
3	527628.71	5511652.18	392.61	0	250	110.4	110.4	0.0	-8.7	73.8	1.4	6.3	0.0	0.0	0.0	0.0	-0.0	20.2	20.2
4	527628.71	5511652.18	392.61	0	500	109.8	109.8	0.0	-9.9	73.8	2.7	5.9	0.0	0.0	0.0	0.0	-0.0	17.5	17.5
5	527628.71	5511652.18	392.61	0	1000	110.0	110.0	0.0	-11.0	73.8	5.0	0.5	0.0	0.0	4.3	0.0	-0.0	15.3	15.3
6	527628.71	5511652.18	392.61	0	2000	106.2	106.2	0.0	-11.0	73.8	13.3	-1.1	0.0	0.0	4.9	0.0	-0.0	4.3	4.3
7	527628.71	5511652.18	392.61	0	4000	100.0	100.0	0.0	-11.0	73.8	45.2	-1.1	0.0	0.0	4.9	0.0	-0.0	-33.8	-33.8
8	527628.71	5511652.18	392.61	0	8000	90.9	90.9	0.0	-11.0	73.8	161.3	-1.1	0.0	0.0	5.1	0.0	-0.0	-159.2	-159.2

Point Source, ISO 9613, Name: "Exhaust Vent Raise 2", ID: "UG_ExVentRaise2_o"																			
Nr.	X (m)	Y (m)	Z (m)	Refl.	Freq. (Hz)	LxT dB(A)	LxN dB(A)	K0 (dB)	Dc (dB)	Adiv (dB)	Aatm (dB)	Agr (dB)	Afol (dB)	Ahous (dB)	Abar (dB)	Cmet (dB)	RL (dB)	LrT dB(A)	LrN dB(A)
1	528834.74	5512295.63	397.88	0	63	90.8	90.8	0.0	-3.7	70.1	0.1	-5.5	0.0	0.0	0.0	0.0	-0.0	22.3	22.3
2	528834.74	5512295.63	397.88	0	125	100.9	100.9	0.0	-7.4	70.1	0.4	6.0	0.0	0.0	0.0	0.0	-0.0	17.0	17.0
3	528834.74	5512295.63	397.88	0	250	105.4	105.4	0.0	-8.7	70.1	1.0	6.3	0.0	0.0	0.0	0.0	-0.0	19.3	19.3
4	528834.74	5512295.63	397.88	0	500	104.8	104.8	0.0	-9.9	70.1	1.8	6.0	0.0	0.0	0.0	0.0	-0.0	17.0	17.0
5	528834.74	5512295.63	397.88	0	1000	105.0	105.0	0.0	-11.0	70.1	3.3	0.5	0.0	0.0	0.0	0.0	-0.0	20.0	20.0
6	528834.74	5512295.63	397.88	0	2000	101.2	101.2	0.0	-11.0	70.1	8.8	-1.1	0.0	0.0	0.0	0.0	-0.0	12.4	12.4
7	528834.74	5512295.63	397.88	0	4000	95.0	95.0	0.0	-11.0	70.1	29.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-14.7	-14.7
8	528834.74	5512295.63	397.88	0	8000	85.9	85.9	0.0	-11.0	70.1	105.9	-1.1	0.0	0.0	0.0	0.0	-0.0	-100.0	-100.0

Point Source, ISO 9613, Name: "Fresh Air Intake Vent Raise", ID: "UG_VentRaise1_o"																			
Nr.	X (m)	Y (m)	Z (m)	Refl.	Freq. (Hz)	LxT dB(A)	LxN dB(A)	K0 (dB)	Dc (dB)	Adiv (dB)	Aatm (dB)	Agr (dB)	Afol (dB)	Ahous (dB)	Abar (dB)	Cmet (dB)	RL (dB)	LrT dB(A)	LrN dB(A)
1	528123.67	5511884.74	397.40	0	63	95.8	95.8	0.0	-3.7	70.9	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	21.8	21.8
2	528123.67	5511884.74	397.40	0	125	105.9	105.9	0.0	-7.4	70.9	0.4	6.2	0.0	0.0	0.0	0.0	-0.0	21.0	21.0
3	528123.67	5511884.74	397.40	0	250	110.4	110.4	0.0	-8.7	70.9	1.0	6.3	0.0	0.0	0.0	0.0	-0.0	23.5	23.5
4	528123.67	5511884.74	397.40	0	500	109.8	109.8	0.0	-9.9	70.9	1.9	6.0	0.0	0.0	0.0	0.0	-0.0	21.1	21.1
5	528123.67	5511884.74	397.40	0	1000	110.0	110.0	0.0	-11.0	70.9	3.6	0.5	0.0	0.0	4.3	0.0	-0.0	19.7	19.7
6	528123.67	5511884.74	397.40	0	2000	106.2	106.2	0.0	-11.0	70.9	9.6	-1.1	0.0	0.0	4.8	0.0	-0.0	11.1	11.1
7	528123.67	5511884.74	397.40	0	4000	100.0	100.0	0.0	-11.0	70.9	32.4	-1.1	0.0	0.0	4.8	0.0	-0.0	-18.0	-18.0
8	528123.67	5511884.74	397.40	0	8000	90.9	90.9	0.0	-11.0	70.9	115.5	-1.1	0.0	0.0	4.8	0.0	-0.0	-110.3	-110.3



Point Source, ISO 9613, Name: "Building Vent 5", ID: "ML\_ExLvr05\_o"

Nr.	X (m)	Y (m)	Z (m)	Refll	Freq. (Hz)	LxT dB(A)	LxN dB(A)	K0 dB	Dc dB	Adiv dB	Aatm dB	Agr dB	Afol dB	Ahous dB	Abar dB	Cmet dB	RL dB	LrT dB(A)	LrN dB(A)
1	528976.38	5512120.21	401.12	0	32	42.8	42.8	3.0	0.0	68.1	0.0	-4.4	0.0	0.0	2.8	0.0	-0.0	-20.8	-20.8
2	528976.38	5512120.21	401.12	0	63	56.1	56.1	3.0	0.0	68.1	0.1	-4.4	0.0	0.0	3.3	0.0	-0.0	-8.0	-8.0
3	528976.38	5512120.21	401.12	0	125	66.8	66.8	3.0	0.0	68.1	0.3	2.8	0.0	0.0	1.4	0.0	-0.0	-2.9	-2.9
4	528976.38	5512120.21	401.12	0	250	77.4	77.4	3.0	0.0	68.1	0.8	0.3	0.0	0.0	4.0	0.0	-0.0	7.3	7.3
5	528976.38	5512120.21	401.12	0	500	81.6	81.6	3.0	0.0	68.1	1.4	-0.9	0.0	0.0	4.5	0.0	-0.0	11.5	11.5
6	528976.38	5512120.21	401.12	0	1000	84.3	84.3	3.0	0.0	68.1	2.6	-0.9	0.0	0.0	4.6	0.0	-0.0	12.8	12.8
7	528976.38	5512120.21	401.12	0	2000	84.4	84.4	3.0	0.0	68.1	6.9	-0.9	0.0	0.0	4.7	0.0	-0.0	8.5	8.5
8	528976.38	5512120.21	401.12	0	4000	83.1	83.1	3.0	0.0	68.1	23.5	-0.9	0.0	0.0	4.8	0.0	-0.0	-9.4	-9.4
9	528976.38	5512120.21	401.12	0	8000	80.7	80.7	3.0	0.0	68.1	83.9	-0.9	0.0	0.0	4.8	0.0	-0.0	-72.2	-72.2

Point Source, ISO 9613, Name: "Building Vent 6", ID: "ML\_ExLvr06\_o"

Nr.	X (m)	Y (m)	Z (m)	Refll	Freq. (Hz)	LxT dB(A)	LxN dB(A)	K0 dB	Dc dB	Adiv dB	Aatm dB	Agr dB	Afol dB	Ahous dB	Abar dB	Cmet dB	RL dB	LrT dB(A)	LrN dB(A)
1	528964.52	5512058.28	399.91	0	32	42.8	42.8	3.0	0.0	67.3	0.0	-4.3	0.0	0.0	0.0	0.0	-0.0	-17.3	-17.3
2	528964.52	5512058.28	399.91	0	63	56.1	56.1	3.0	0.0	67.3	0.1	-4.3	0.0	0.0	0.0	0.0	-0.0	-4.0	-4.0
3	528964.52	5512058.28	399.91	0	125	66.8	66.8	3.0	0.0	67.3	0.3	2.8	0.0	0.0	0.0	0.0	-0.0	-0.6	-0.6
4	528964.52	5512058.28	399.91	0	250	77.4	77.4	3.0	0.0	67.3	0.7	0.3	0.0	0.0	0.0	0.0	-0.0	12.1	12.1
5	528964.52	5512058.28	399.91	0	500	81.6	81.6	3.0	0.0	67.3	1.3	-0.9	0.0	0.0	0.0	0.0	-0.0	16.9	16.9
6	528964.52	5512058.28	399.91	0	1000	84.3	84.3	3.0	0.0	67.3	2.4	-0.9	0.0	0.0	0.0	0.0	-0.0	18.4	18.4
7	528964.52	5512058.28	399.91	0	2000	84.4	84.4	3.0	0.0	67.3	6.3	-0.9	0.0	0.0	0.0	0.0	-0.0	14.6	14.6
8	528964.52	5512058.28	399.91	0	4000	83.1	83.1	3.0	0.0	67.3	21.5	-0.9	0.0	0.0	0.0	0.0	-0.0	-1.9	-1.9
9	528964.52	5512058.28	399.91	0	8000	80.7	80.7	3.0	0.0	67.3	76.7	-0.9	0.0	0.0	0.0	0.0	-0.0	-59.5	-59.5

Point Source, ISO 9613, Name: "Building Vent 7", ID: "ML\_ExLvr07\_o"

Nr.	X (m)	Y (m)	Z (m)	Refll	Freq. (Hz)	LxT dB(A)	LxN dB(A)	K0 dB	Dc dB	Adiv dB	Aatm dB	Agr dB	Afol dB	Ahous dB	Abar dB	Cmet dB	RL dB	LrT dB(A)	LrN dB(A)
1	528937.18	5512058.27	399.96	0	32	42.8	42.8	3.0	0.0	67.4	0.0	-4.3	0.0	0.0	0.0	0.0	-0.0	-17.3	-17.3
2	528937.18	5512058.27	399.96	0	63	56.1	56.1	3.0	0.0	67.4	0.1	-4.3	0.0	0.0	0.0	0.0	-0.0	-4.0	-4.0
3	528937.18	5512058.27	399.96	0	125	66.8	66.8	3.0	0.0	67.4	0.3	2.8	0.0	0.0	0.0	0.0	-0.0	-0.7	-0.7
4	528937.18	5512058.27	399.96	0	250	77.4	77.4	3.0	0.0	67.4	0.7	0.3	0.0	0.0	0.0	0.0	-0.0	12.0	12.0
5	528937.18	5512058.27	399.96	0	500	81.6	81.6	3.0	0.0	67.4	1.3	-0.9	0.0	0.0	0.0	0.0	-0.0	16.8	16.8
6	528937.18	5512058.27	399.96	0	1000	84.3	84.3	3.0	0.0	67.4	2.4	-0.9	0.0	0.0	0.0	0.0	-0.0	18.4	18.4
7	528937.18	5512058.27	399.96	0	2000	84.4	84.4	3.0	0.0	67.4	6.3	-0.9	0.0	0.0	0.0	0.0	-0.0	14.5	14.5
8	528937.18	5512058.27	399.96	0	4000	83.1	83.1	3.0	0.0	67.4	21.6	-0.9	0.0	0.0	0.0	0.0	-0.0	-2.0	-2.0
9	528937.18	5512058.27	399.96	0	8000	80.7	80.7	3.0	0.0	67.4	76.9	-0.9	0.0	0.0	0.0	0.0	-0.0	-59.7	-59.7

Point Source, ISO 9613, Name: "Building Vent 8", ID: "ML\_ExLvr08\_o"

Nr.	X (m)	Y (m)	Z (m)	Refll	Freq. (Hz)	LxT dB(A)	LxN dB(A)	K0 dB	Dc dB	Adiv dB	Aatm dB	Agr dB	Afol dB	Ahous dB	Abar dB	Cmet dB	RL dB	LrT dB(A)	LrN dB(A)
1	528932.72	5512195.55	402.70	0	32	42.8	42.8	3.0	0.0	69.0	0.0	-4.6	0.0	0.0	4.8	0.0	-0.0	-23.4	-23.4
2	528932.72	5512195.55	402.70	0	63	56.1	56.1	3.0	0.0	69.0	0.1	-4.6	0.0	0.0	4.8	0.0	-0.0	-10.2	-10.2
3	528932.72	5512195.55	402.70	0	125	66.8	66.8	3.0	0.0	69.0	0.3	2.8	0.0	0.0	1.9	0.0	-0.0	-4.3	-4.3
4	528932.72	5512195.55	402.70	0	250	77.4	77.4	3.0	0.0	69.0	0.8	0.2	0.0	0.0	4.5	0.0	-0.0	5.8	5.8
5	528932.72	5512195.55	402.70	0	500	81.6	81.6	3.0	0.0	69.0	1.5	-0.9	0.0	0.0	4.8	0.0	-0.0	10.2	10.2
6	528932.72	5512195.55	402.70	0	1000	84.3	84.3	3.0	0.0	69.0	2.9	-0.9	0.0	0.0	4.8	0.0	-0.0	11.5	11.5
7	528932.72	5512195.55	402.70	0	2000	84.4	84.4	3.0	0.0	69.0	7.7	-0.9	0.0	0.0	4.8	0.0	-0.0	6.8	6.8
8	528932.72	5512195.55	402.70	0	4000	83.1	83.1	3.0	0.0	69.0	26.1	-0.9	0.0	0.0	4.8	0.0	-0.0	-12.8	-12.8
9	528932.72	5512195.55	402.70	0	8000	80.7	80.7	3.0	0.0	69.0	92.9	-0.9	0.0	0.0	4.8	0.0	-0.0	-82.1	-82.1

Point Source, ISO 9613, Name: "Building Vent 9", ID: "ML\_ExLvr09\_o"

Nr.	X (m)	Y (m)	Z (m)	Refll	Freq. (Hz)	LxT dB(A)	LxN dB(A)	K0 dB	Dc dB	Adiv dB	Aatm dB	Agr dB	Afol dB	Ahous dB	Abar dB	Cmet dB	RL dB	LrT dB(A)	LrN dB(A)
1	528909.69	5512180.32	402.44	0	32	42.8	42.8	3.0	0.0	68.9	0.0	-4.6	0.0	0.0	4.8	0.0	-0.0	-23.3	-23.3
2	528909.69	5512180.32	402.44	0	63	56.1	56.1	3.0	0.0	68.9	0.1	-4.6	0.0	0.0	4.8	0.0	-0.0	-10.1	-10.1
3	528909.69	5512180.32	402.44	0	125	66.8	66.8	3.0	0.0	68.9	0.3	2.8	0.0	0.0	2.0	0.0	-0.0	-4.2	-4.2
4	528909.69	5512180.32	402.44	0	250	77.4	77.4	3.0	0.0	68.9	0.8	0.2	0.0	0.0	4.6	0.0	-0.0	5.8	5.8
5	528909.69	5512180.32	402.44	0	500	81.6	81.6	3.0	0.0	68.9	1.5	-0.9	0.0	0.0	4.9	0.0	-0.0	10.2	10.2
6	528909.69	5512180.32	402.44	0	1000	84.3	84.3	3.0	0.0	68.9	2.9	-0.9	0.0	0.0	5.1	0.0	-0.0	11.4	11.4
7	528909.69	5512180.32	402.44	0	2000	84.4	84.4	3.0	0.0	68.9	7.5	-0.9	0.0	0.0	5.4	0.0	-0.0	6.5	6.5
8	528909.69	5512180.32	402.44	0	4000	83.1	83.1	3.0	0.0	68.9	25.6	-0.9	0.0	0.0	5.9	0.0	-0.0	-13.4	-13.4
9	528909.69	5512180.32	402.44	0	8000	80.7	80.7	3.0	0.0	68.9	91.3	-0.9	0.0	0.0	6.8	0.0	-0.0	-82.4	-82.4

Point Source, ISO 9613, Name: "Building Vent 10", ID: "ML\_ExLvr10\_o"

Nr.	X (m)	Y (m)	Z (m)	Refll	Freq. (Hz)	LxT dB(A)	LxN dB(A)	K0 dB	Dc dB	Adiv dB	Aatm dB	Agr dB	Afol dB	Ahous dB	Abar dB	Cmet dB	RL dB	LrT dB(A)	LrN dB(A)
1	528932.95	5512163.56	402.06	0	32	42.8	42.8	3.0	0.0	68.6	0.0	-4.5	0.0	0.0	4.8	0.0	-0.0	-23.2	-23.2
2	528932.95	5512163.56	402.06	0	63	56.1	56.1	3.0	0.0	68.6	0.1	-4.5	0.0	0.0	4.8	0.0	-0.0	-9.9	-9.9
3	528932.95	5512163.56	402.06	0	125	66.8	66.8	3.0	0.0	68.6	0.3	2.8	0.0	0.0	1.9	0.0	-0.0	-3.9	-3.9
4	528932.95	5512163.56	402.06	0	250	77.4	77.4	3.0	0.0	68.6	0.8	0.2	0.0	0.0	4.5	0.0	-0.0	6.1	6.1
5	528932.95	5512163.56	402.06	0	500	81.6	81.6	3.0	0.0	68.6	1.5	-0.9	0.0	0.0	4.8	0.0	-0.0	10.6	10.6
6	528932.95	5512163.56	402.06	0	1000	84.3	84.3	3.0	0.0	68.6	2.8	-0.9	0.0	0.0	4.8	0.0	-0.0	12.0	12.0
7	528932.95	5512163.56	402.06	0	2000	84.4	84.4	3.0	0.0	68.6	7.4	-0.9	0.0	0.0	4.8	0.0	-0.0	7.5	7.5
8	528932.95	5512163.56	402.06	0	4000	83.1	83.1	3.0	0.0	68.6	25.0	-0.9	0.0	0.0	4.8	0.0	-0.0	-11.5	-11.5
9	528932.95	5512163.56	402.06	0	8000	80.7	80.7	3.0	0.0	68.6	89.2	-0.9	0.0	0.0	4.8	0.0	-0.0	-78.0	-78.0

Point Source, ISO 9613, Name: "Building Vent 11", ID: "ML\_ExLvr11\_o"

Nr.	X (m)	Y (m)	Z (m)	Refll	Freq. (Hz)	LxT dB(A)	LxN dB(A)	K0 dB	Dc dB	Adiv dB	Aatm dB	Agr dB	Afol dB	Ahous dB	Abar dB	Cmet dB	RL dB	LrT dB(A)	LrN dB(A)
1	528933.44	5512093.28	400.67	0	32	42.8	42.8	3.0	0.0	67.8	0.0	-4.4	0.0	0.0	6.0	0.0	-0.0	-23.7	-23.7
2	528933.44	5512093.28	400.67	0	63	56.1	56.1	3.0	0.0	67.8	0.1	-4.4	0.0	0.0	8.7	0.0	-0.0	-13.2	-13.2
3	528933.44	5512093.28	400.67	0	125	66.8	66.8	3.0	0.0	67.8	0.3	2.8	0.0	0.0	9.9	0.0	-0.0	-1.0	-1.0

Line Source, ISO 9613, Name: "Haul Truck #1", ID: "Htruck1_o"																			
Nr.	X	Y	Z	Refl.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afof	Ahous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB(A)	(dB(A)
1	528616.76	5511972.53	397.40	0	32	37.6	37.6	0.0	0.0	67.6	0.0	-4.9	0.0	0.0	0.0	0.0	-25.1	-25.1	
2	528616.76	5511972.53	397.40	0	63	46.8	46.8	0.0	0.0	67.6	0.1	-4.9	0.0	0.0	0.0	0.0	-16.0	-16.0	
3	528616.76	5511972.53	397.40	0	125	62.9	62.9	0.0	0.0	67.6	0.3	4.8	0.0	0.0	0.0	0.0	-9.8	-9.8	
4	528616.76	5511972.53	397.40	0	250	72.4	72.4	0.0	0.0	67.6	0.7	2.4	0.0	0.0	0.0	0.0	-1.7	1.7	
5	528616.76	5511972.53	397.40	0	500	76.8	76.8	0.0	0.0	67.6	1.3	-1.0	0.0	0.0	0.0	0.0	8.8	8.8	
6	528616.76	5511972.53	397.40	0	1000	80.0	80.0	0.0	0.0	67.6	2.5	-1.0	0.0	0.0	0.0	0.0	-10.9	10.9	
7	528616.76	5511972.53	397.40	0	2000	80.2	80.2	0.0	0.0	67.6	6.6	-1.0	0.0	0.0	0.0	0.0	-7.0	7.0	
8	528616.76	5511972.53	397.40	0	4000	73.0	73.0	0.0	0.0	67.6	22.3	-1.0	0.0	0.0	0.0	0.0	-15.9	-15.9	
9	528616.76	5511972.53	397.40	0	8000	65.9	65.9	0.0	0.0	67.6	79.4	-1.0	0.0	0.0	0.0	0.0	-80.1	-80.1	
10	528541.47	5512000.24	397.51	0	32	38.1	38.1	0.0	0.0	68.4	0.0	-5.0	0.0	0.0	0.0	0.0	-25.3	-25.3	
11	528541.47	5512000.24	397.51	0	63	47.3	47.3	0.0	0.0	68.4	0.1	-5.0	0.0	0.0	0.0	0.0	-16.2	-16.2	
12	528541.47	5512000.24	397.51	0	125	63.4	63.4	0.0	0.0	68.4	0.3	4.9	0.0	0.0	0.0	0.0	-10.3	-10.3	
13	528541.47	5512000.24	397.51	0	250	72.9	72.9	0.0	0.0	68.4	0.8	2.4	0.0	0.0	0.0	0.0	-1.3	1.3	
14	528541.47	5512000.24	397.51	0	500	77.3	77.3	0.0	0.0	68.4	1.4	-1.0	0.0	0.0	0.0	0.0	-8.4	8.4	
15	528541.47	5512000.24	397.51	0	1000	80.5	80.5	0.0	0.0	68.4	2.7	-1.0	0.0	0.0	0.0	0.0	-10.4	10.4	
16	528541.47	5512000.24	397.51	0	2000	80.7	80.7	0.0	0.0	68.4	7.2	-1.0	0.0	0.0	0.0	0.0	-6.1	6.1	
17	528541.47	5512000.24	397.51	0	4000	73.5	73.5	0.0	0.0	68.4	24.4	-1.0	0.0	0.0	0.0	0.0	-18.3	-18.3	
18	528541.47	5512000.24	397.51	0	8000	66.4	66.4	0.0	0.0	68.4	87.1	-1.0	0.0	0.0	0.0	0.0	-88.1	-88.1	
19	528580.73	5511987.31	397.47	0	32	36.9	36.9	0.0	0.0	68.0	0.0	-5.0	0.0	0.0	0.0	0.0	-26.2	-26.2	
20	528580.73	5511987.31	397.47	0	63	46.1	46.1	0.0	0.0	68.0	0.1	-5.0	0.0	0.0	0.0	0.0	-17.1	-17.1	
21	528580.73	5511987.31	397.47	0	125	62.2	62.2	0.0	0.0	68.0	0.3	4.9	0.0	0.0	0.0	0.0	-11.1	-11.1	
22	528580.73	5511987.31	397.47	0	250	71.7	71.7	0.0	0.0	68.0	0.7	2.4	0.0	0.0	0.0	0.0	-0.5	0.5	
23	528580.73	5511987.31	397.47	0	500	76.1	76.1	0.0	0.0	68.0	1.4	-1.0	0.0	0.0	0.0	0.0	-7.6	7.6	
24	528580.73	5511987.31	397.47	0	1000	79.3	79.3	0.0	0.0	68.0	2.6	-1.0	0.0	0.0	0.0	0.0	-9.6	9.6	
25	528580.73	5511987.31	397.47	0	2000	79.5	79.5	0.0	0.0	68.0	6.9	-1.0	0.0	0.0	0.0	0.0	-5.5	5.5	
26	528580.73	5511987.31	397.47	0	4000	72.3	72.3	0.0	0.0	68.0	23.3	-1.0	0.0	0.0	0.0	0.0	-18.1	-18.1	
27	528580.73	5511987.31	397.47	0	8000	65.2	65.2	0.0	0.0	68.0	83.2	-1.0	0.0	0.0	0.0	0.0	-85.1	-85.1	
28	528498.52	5512009.94	397.72	0	32	37.4	37.4	0.0	0.0	68.8	0.0	-5.1	0.0	0.0	0.0	0.0	-26.4	-26.4	
29	528498.52	5512009.94	397.72	0	63	46.6	46.6	0.0	0.0	68.8	0.1	-5.1	0.0	0.0	0.0	0.0	-17.2	-17.2	
30	528498.52	5512009.94	397.72	0	125	62.7	62.7	0.0	0.0	68.8	0.3	5.0	0.0	0.0	0.0	0.0	-11.4	-11.4	
31	528498.52	5512009.94	397.72	0	250	72.2	72.2	0.0	0.0	68.8	0.8	2.4	0.0	0.0	0.0	0.0	-0.2	0.2	
32	528498.52	5512009.94	397.72	0	500	76.6	76.6	0.0	0.0	68.8	1.5	-1.0	0.0	0.0	0.0	0.0	-7.3	7.3	
33	528498.52	5512009.94	397.72	0	1000	79.8	79.8	0.0	0.0	68.8	2.8	-1.0	0.0	0.0	0.0	0.0	-9.2	9.2	
34	528498.52	5512009.94	397.72	0	2000	80.0	80.0	0.0	0.0	68.8	7.5	-1.0	0.0	0.0	0.0	0.0	-4.7	4.7	
35	528498.52	5512009.94	397.72	0	4000	72.8	72.8	0.0	0.0	68.8	25.5	-1.0	0.0	0.0	0.0	0.0	-20.5	-20.5	
36	528498.52	5512009.94	397.72	0	8000	65.7	65.7	0.0	0.0	68.8	91.0	-1.0	0.0	0.0	0.0	0.0	-93.1	-93.1	
37	528328.22	5512018.73	399.38	0	32	37.6	37.6	0.0	0.0	70.1	0.0	-5.2	0.0	0.0	0.0	0.0	-27.4	-27.4	
38	528328.22	5512018.73	399.38	0	63	46.8	46.8	0.0	0.0	70.1	0.1	-5.2	0.0	0.0	0.0	0.0	-18.2	-18.2	
39	528328.22	5512018.73	399.38	0	125	62.9	62.9	0.0	0.0	70.1	0.4	5.1	0.0	0.0	0.0	0.0	-12.7	-12.7	
40	528328.22	5512018.73	399.38	0	250	72.4	72.4	0.0	0.0	70.1	0.9	2.4	0.0	0.0	0.0	0.0	-1.0	-1.0	
41	528328.22	5512018.73	399.38	0	500	76.8	76.8	0.0	0.0	70.1	1.7	-1.0	0.0	0.0	0.0	0.0	-5.9	5.9	
42	528328.22	5512018.73	399.38	0	1000	80.0	80.0	0.0	0.0	70.1	3.3	-1.0	0.0	0.0	0.0	0.0	-7.6	7.6	
43	528328.22	5512018.73	399.38	0	2000	80.2	80.2	0.0	0.0	70.1	8.7	-1.0	0.0	0.0	0.0	0.0	-2.4	2.4	
44	528328.22	5512018.73	399.38	0	4000	73.0	73.0	0.0	0.0	70.1	29.5	-1.0	0.0	0.0	0.0	0.0	-25.6	-25.6	
45	528328.22	5512018.73	399.38	0	8000	65.9	65.9	0.0	0.0	70.1	105.4	-1.0	0.0	0.0	0.0	0.0	-108.6	-108.6	
46	528357.86	5512072.50	399.40	0	32	37.5	37.5	0.0	0.0	70.3	0.0	-5.2	0.0	0.0	0.0	0.0	-27.5	-27.5	
47	528357.86	5512072.50	399.40	0	63	46.7	46.7	0.0	0.0	70.3	0.1	-5.2	0.0	0.0	0.0	0.0	-18.4	-18.4	
48	528357.86	5512072.50	399.40	0	125	62.8	62.8	0.0	0.0	70.3	0.4	5.2	0.0	0.0	0.0	0.0	-13.0	-13.0	
49	528357.86	5512072.50	399.40	0	250	72.3	72.3	0.0	0.0	70.3	1.0	2.3	0.0	0.0	0.0	0.0	-1.2	-1.2	
50	528357.86	5512072.50	399.40	0	500	76.7	76.7	0.0	0.0	70.3	1.8	-1.0	0.0	0.0	0.0	0.0	-5.7	5.7	
51	528357.86	5512072.50	399.40	0	1000	79.9	79.9	0.0	0.0	70.3	3.4	-1.0	0.0	0.0	0.0	0.0	-7.4	7.4	
52	528357.86	5512072.50	399.40	0	2000	80.1	80.1	0.0	0.0	70.3	8.9	-1.0	0.0	0.0	0.0	0.0	-2.0	2.0	
53	528357.86	5512072.50	399.40	0	4000	72.9	72.9	0.0	0.0	70.3	30.1	-1.0	0.0	0.0	0.0	0.0	-26.4	-26.4	
54	528357.86	5512072.50	399.40	0	8000	65.8	65.8	0.0	0.0	70.3	107.4	-1.0	0.0	0.0	0.0	0.0	-110.7	-110.7	
55	528221.97	5511950.91	399.45	0	32	37.7	37.7	0.0	0.0	70.5	0.0	-5.2	0.0	0.0	0.0	0.0	-27.6	-27.6	
56	528221.97	5511950.91	399.45	0	63	46.9	46.9	0.0	0.0	70.5	0.1	-5.2	0.0	0.0	0.0	0.0	-18.4	-18.4	
57	528221.97	5511950.91	399.45	0	125	63.0	63.0	0.0	0.0	70.5	0.4	5.2	0.0	0.0	0.0	0.0	-13.0	-13.0	
58	528221.97	5511950.91	399.45	0	250	72.5	72.5	0.0	0.0	70.5	1.0	2.3	0.0	0.0	0.0	0.0	-1.3	-1.3	
59	528221.97	5511950.91	399.45	0	500	76.9	76.9	0.0	0.0	70.5	1.8	-1.0	0.0	0.0	0.0	0.0	-5.6	5.6	
60	528221.97	5511950.91	399.45	0	1000	80.1	80.1	0.0	0.0	70.5	3.4	-1.1	0.0	0.0	0.0	0.0	-7.2	7.2	
61	528221.97	5511950.91	399.45	0	2000	80.3	80.3	0.0	0.0	70.5	9.1	-1.1	0.0	0.0	0.0	0.0	-1.8	1.8	
62	528221.97	5511950.91	399.45	0	4000	73.1	73.1	0.0	0.0	70.5	30.8	-1.1	0.0	0.0	0.0	0.0	-27.1	-27.1	
63	528221.97	5511950.91	399.45	0	8000	66.0	66.0	0.0	0.0	70.5	110.0	-1.1	0.0	0.0	0.0	0.0	-113.4	-113.4	

Sample Calculation at facade of NR03

Line Source, ISO 9613, Name: "Haul Truck #1", ID: "Htruck1_o"																			
Nr.	X	Y	Z	Refl.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afof	Ahous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB(A)	(dB(A)
64	527966.92	5511862.79	402.55	0	32	38.4	38.4	0.0	0.0	72.0	0.0	-5.4	0.0	0.0	0.0	0.0	-0.0	-28.2	-28.2</

Line Source, ISO 9613, Name: "Haul Truck #1", ID: "Htruck1_o"																			
Nr.	X	Y	Z	Refl.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afof	Ahous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	dB(A)	dB(A)
127	528276.36	5511970.68	399.34	0	32	35.8	35.8	0.0	70.2	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-29.2	-29.2	
128	528276.36	5511970.68	399.34	0	63	45.0	45.0	0.0	70.2	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-20.0	-20.0	
129	528276.36	5511970.68	399.34	0	125	61.1	61.1	0.0	70.2	0.4	5.1	0.0	0.0	0.0	0.0	-0.0	-14.6	-14.6	
130	528276.36	5511970.68	399.34	0	250	70.6	70.6	0.0	70.2	1.0	2.3	0.0	0.0	0.0	0.0	-0.0	-2.8	-2.8	
131	528276.36	5511970.68	399.34	0	500	75.0	75.0	0.0	70.2	1.8	-1.0	0.0	0.0	0.0	0.0	-0.0	4.1	4.1	
132	528276.36	5511970.68	399.34	0	1000	78.2	78.2	0.0	70.2	3.3	-1.0	0.0	0.0	0.0	0.0	-0.0	5.8	5.8	
133	528276.36	5511970.68	399.34	0	2000	78.4	78.4	0.0	70.2	8.8	-1.0	0.0	0.0	0.0	0.0	-0.0	0.5	0.5	
134	528276.36	5511970.68	399.34	0	4000	71.2	71.2	0.0	70.2	29.8	-1.0	0.0	0.0	0.0	0.0	-0.0	-27.7	-27.7	
135	528276.36	5511970.68	399.34	0	8000	64.1	64.1	0.0	70.2	106.3	-1.0	0.0	0.0	0.0	0.0	-0.0	-111.3	-111.3	
136	528413.07	5512073.21	398.89	0	32	35.5	35.5	0.0	69.9	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-29.3	-29.3	
137	528413.07	5512073.21	398.89	0	63	44.7	44.7	0.0	69.9	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-20.2	-20.2	
138	528413.07	5512073.21	398.89	0	125	60.8	60.8	0.0	69.9	0.4	5.1	0.0	0.0	0.0	0.0	-0.0	-14.6	-14.6	
139	528413.07	5512073.21	398.89	0	250	70.3	70.3	0.0	69.9	0.9	2.4	0.0	0.0	0.0	0.0	-0.0	-2.9	-2.9	
140	528413.07	5512073.21	398.89	0	500	74.7	74.7	0.0	69.9	1.7	-1.0	0.0	0.0	0.0	0.0	-0.0	4.1	4.1	
141	528413.07	5512073.21	398.89	0	1000	77.9	77.9	0.0	69.9	3.2	-1.0	0.0	0.0	0.0	0.0	-0.0	5.8	5.8	
142	528413.07	5512073.21	398.89	0	2000	78.1	78.1	0.0	69.9	8.5	-1.0	0.0	0.0	0.0	0.0	-0.0	0.7	0.7	
143	528413.07	5512073.21	398.89	0	4000	70.9	70.9	0.0	69.9	28.9	-1.0	0.0	0.0	0.0	0.0	-0.0	-26.9	-26.9	
144	528413.07	5512073.21	398.89	0	8000	63.8	63.8	0.0	69.9	103.1	-1.0	0.0	0.0	0.0	0.0	-0.0	-108.2	-108.2	
145	528422.77	5512051.97	398.72	0	32	35.2	35.2	0.0	69.7	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-29.4	-29.4	
146	528422.77	5512051.97	398.72	0	63	44.4	44.4	0.0	69.7	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-20.3	-20.3	
147	528422.77	5512051.97	398.72	0	125	60.5	60.5	0.0	69.7	0.4	5.1	0.0	0.0	0.0	0.0	-0.0	-14.7	-14.7	
148	528422.77	5512051.97	398.72	0	250	70.0	70.0	0.0	69.7	0.9	2.4	0.0	0.0	0.0	0.0	-0.0	-3.0	-3.0	
149	528422.77	5512051.97	398.72	0	500	74.4	74.4	0.0	69.7	1.7	-1.0	0.0	0.0	0.0	0.0	-0.0	4.0	4.0	
150	528422.77	5512051.97	398.72	0	1000	77.6	77.6	0.0	69.7	3.1	-1.0	0.0	0.0	0.0	0.0	-0.0	5.8	5.8	
151	528422.77	5512051.97	398.72	0	2000	77.8	77.8	0.0	69.7	8.3	-1.0	0.0	0.0	0.0	0.0	-0.0	0.8	0.8	
152	528422.77	5512051.97	398.72	0	4000	70.6	70.6	0.0	69.7	28.2	-1.0	0.0	0.0	0.0	0.0	-0.0	-26.3	-26.3	
153	528422.77	5512051.97	398.72	0	8000	63.5	63.5	0.0	69.7	100.5	-1.0	0.0	0.0	0.0	0.0	-0.0	-105.7	-105.7	
154	528471.73	5512020.10	398.03	0	32	34.0	34.0	0.0	69.1	0.0	-5.1	0.0	0.0	0.0	0.0	-0.0	-30.0	-30.0	
155	528471.73	5512020.10	398.03	0	63	43.2	43.2	0.0	69.1	0.1	-5.1	0.0	0.0	0.0	0.0	-0.0	-20.9	-20.9	
156	528471.73	5512020.10	398.03	0	125	59.3	59.3	0.0	69.1	0.3	5.0	0.0	0.0	0.0	0.0	-0.0	-15.2	-15.2	
157	528471.73	5512020.10	398.03	0	250	68.8	68.8	0.0	69.1	0.8	2.4	0.0	0.0	0.0	0.0	-0.0	-3.5	-3.5	
158	528471.73	5512020.10	398.03	0	500	73.2	73.2	0.0	69.1	1.6	-1.0	0.0	0.0	0.0	0.0	-0.0	3.5	3.5	
159	528471.73	5512020.10	398.03	0	1000	76.4	76.4	0.0	69.1	2.9	-1.0	0.0	0.0	0.0	0.0	-0.0	5.4	5.4	
160	528471.73	5512020.10	398.03	0	2000	76.6	76.6	0.0	69.1	7.8	-1.0	0.0	0.0	0.0	0.0	-0.0	0.7	0.7	
161	528471.73	5512020.10	398.03	0	4000	69.4	69.4	0.0	69.1	26.3	-1.0	0.0	0.0	0.0	0.0	-0.0	-25.0	-25.0	
162	528471.73	5512020.10	398.03	0	8000	62.3	62.3	0.0	69.1	94.0	-1.0	0.0	0.0	0.0	0.0	-0.0	-99.8	-99.8	
163	528036.65	5511924.49	398.38	0	32	36.6	36.6	0.0	71.7	0.0	-5.3	0.0	0.0	4.8	0.0	-0.0	-34.6	-34.6	
164	528036.65	5511924.49	398.38	0	63	45.8	45.8	0.0	71.7	0.1	-5.3	0.0	0.0	4.8	0.0	-0.0	-25.5	-25.5	
165	528036.65	5511924.49	398.38	0	125	61.9	61.9	0.0	71.7	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-15.5	-15.5	
166	528036.65	5511924.49	398.38	0	250	71.4	71.4	0.0	71.7	1.1	2.3	0.0	0.0	2.4	0.0	-0.0	-6.2	-6.2	
167	528036.65	5511924.49	398.38	0	500	75.8	75.8	0.0	71.7	2.1	-1.0	0.0	0.0	4.8	0.0	-0.0	-1.7	-1.7	
168	528036.65	5511924.49	398.38	0	1000	79.0	79.0	0.0	71.7	4.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-0.4	-0.4	
169	528036.65	5511924.49	398.38	0	2000	79.2	79.2	0.0	71.7	10.5	-1.1	0.0	0.0	4.8	0.0	-0.0	-6.7	-6.7	
170	528036.65	5511924.49	398.38	0	4000	72.0	72.0	0.0	71.7	35.5	-1.1	0.0	0.0	4.8	0.0	-0.0	-38.9	-38.9	
171	528036.65	5511924.49	398.38	0	8000	64.9	64.9	0.0	71.7	126.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-137.2	-137.2	
172	528298.07	5511983.61	399.37	0	32	35.0	35.0	0.0	70.1	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-30.0	-30.0	
173	528298.07	5511983.61	399.37	0	63	44.2	44.2	0.0	70.1	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-20.8	-20.8	
174	528298.07	5511983.61	399.37	0	125	60.3	60.3	0.0	70.1	0.4	5.1	0.0	0.0	0.0	0.0	-0.0	-15.4	-15.4	
175	528298.07	5511983.61	399.37	0	250	69.8	69.8	0.0	70.1	0.9	2.4	0.0	0.0	0.0	0.0	-0.0	-3.6	-3.6	
176	528298.07	5511983.61	399.37	0	500	74.2	74.2	0.0	70.1	1.7	-1.0	0.0	0.0	0.0	0.0	-0.0	3.3	3.3	
177	528298.07	5511983.61	399.37	0	1000	77.4	77.4	0.0	70.1	3.3	-1.0	0.0	0.0	0.0	0.0	-0.0	5.0	5.0	
178	528298.07	5511983.61	399.37	0	2000	77.6	77.6	0.0	70.1	8.7	-1.0	0.0	0.0	0.0	0.0	-0.0	-0.2	-0.2	
179	528298.07	5511983.61	399.37	0	4000	70.4	70.4	0.0	70.1	29.5	-1.0	0.0	0.0	0.0	0.0	-0.0	-28.2	-28.2	
180	528298.07	5511983.61	399.37	0	8000	63.3	63.3	0.0	70.1	105.3	-1.0	0.0	0.0	0.0	0.0	-0.0	-111.1	-111.1	
181	528061.13	5511943.43	397.96	0	32	36.2	36.2	0.0	71.6	0.0	-5.3	0.0	0.0	4.8	0.0	-0.0	-34.9	-34.9	
182	528061.13	5511943.43	397.96	0	63	45.4	45.4	0.0	71.6	0.1	-5.3	0.0	0.0	4.8	0.0	-0.0	-25.8	-25.8	
183	528061.13	5511943.43	397.96	0	125	61.5	61.5	0.0	71.6	0.4	5.3	0.0	0.0	0.0	0.0	-0.0	-15.9	-15.9	
184	528061.13	5511943.43	397.96	0	250	71.0	71.0	0.0	71.6	1.1	2.3	0.0	0.0	2.4	0.0	-0.0	-6.5	-6.5	
185	528061.13	5511943.43	397.96	0	500	75.4	75.4	0.0	71.6	2.1	-1.0	0.0	0.0	4.8	0.0	-0.0	-2.1	-2.1	
186	528061.13	5511943.43	397.96	0	1000	78.6	78.6	0.0	71.6	3.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-0.7	-0.7	
187	528061.13	5511943.43	397.96	0	2000	78.8	78.8	0.0	71.6	10.4	-1.1	0.0	0.0	4.8	0.0	-0.0	-6.9	-6.9	
188	528061.13	5511943.43	397.96	0	4000	71.6	71.6	0.0	71.6	35.1	-1.1	0.0	0.0	4.8	0.0	-0.0	-38.9	-38.9	
189	528061.13	5511943.43	397.96	0	8000	64.5	64.5	0.0	71.6	125.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-136.1	-136.1	

Sample Calculation at facade of NR03

Line Source, ISO 9613, Name: "Haul Truck #1", ID: "Htruck1_o"																			
Nr.	X	Y	Z	Refl.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afof	Ahous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	dB(A)	dB(A)
190	528252.92	5511961.53	399.33	0	32	34.8	34.8	0.0	70.3</										

Line Source, ISO 9613, Name: "Haul Truck #1", ID: "Htruck1_o"																			
Nr.	X	Y	Z	RefI.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afof	Ahous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)
253	528092.66	5511948.86	398.66	0	32	33.8	33.8	0.0	0.0	71.4	1.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-32.3	-32.3
254	528092.66	5511948.86	398.66	0	63	43.0	43.0	0.0	0.0	71.4	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-23.2	-23.2
255	528092.66	5511948.86	398.66	0	125	59.1	59.1	0.0	0.0	71.4	0.4	5.3	0.0	0.0	0.0	0.0	-0.0	-17.9	-17.9
256	528092.66	5511948.86	398.66	0	250	68.6	68.6	0.0	0.0	71.4	1.1	2.3	0.0	0.0	0.0	0.0	-0.0	-6.2	-6.2
257	528092.66	5511948.86	398.66	0	500	73.0	73.0	0.0	0.0	71.4	2.0	-1.0	0.0	0.0	0.0	0.0	-0.0	0.7	0.7
258	528092.66	5511948.86	398.66	0	1000	76.2	76.2	0.0	0.0	71.4	3.8	-1.1	0.0	0.0	0.0	0.0	-0.0	2.1	2.1
259	528092.66	5511948.86	398.66	0	2000	76.4	76.4	0.0	0.0	71.4	10.1	-1.1	0.0	0.0	0.0	0.0	-0.0	-4.0	-4.0
260	528092.66	5511948.86	398.66	0	4000	69.2	69.2	0.0	0.0	71.4	34.3	-1.1	0.0	0.0	0.0	0.0	-0.0	-35.4	-35.4
261	528092.66	5511948.86	398.66	0	8000	62.1	62.1	0.0	0.0	71.4	122.4	-1.1	0.0	0.0	0.0	0.0	-0.0	-130.6	-130.6
262	528344.98	5512039.84	399.39	0	32	32.1	32.1	0.0	0.0	70.1	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-32.8	-32.8
263	528344.98	5512039.84	399.39	0	63	41.3	41.3	0.0	0.0	70.1	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-23.7	-23.7
264	528344.98	5512039.84	399.39	0	125	57.4	57.4	0.0	0.0	70.1	0.4	5.1	0.0	0.0	0.0	0.0	-0.0	-18.2	-18.2
265	528344.98	5512039.84	399.39	0	250	66.9	66.9	0.0	0.0	70.1	0.9	2.4	0.0	0.0	0.0	0.0	-0.0	-6.5	-6.5
266	528344.98	5512039.84	399.39	0	500	71.3	71.3	0.0	0.0	70.1	1.7	-1.0	0.0	0.0	0.0	0.0	-0.0	0.5	0.5
267	528344.98	5512039.84	399.39	0	1000	74.5	74.5	0.0	0.0	70.1	3.3	-1.0	0.0	0.0	0.0	0.0	-0.0	2.1	2.1
268	528344.98	5512039.84	399.39	0	2000	74.7	74.7	0.0	0.0	70.1	8.7	-1.0	0.0	0.0	0.0	0.0	-0.0	-3.1	-3.1
269	528344.98	5512039.84	399.39	0	4000	67.5	67.5	0.0	0.0	70.1	29.6	-1.0	0.0	0.0	0.0	0.0	-0.0	-31.2	-31.2
270	528344.98	5512039.84	399.39	0	8000	60.4	60.4	0.0	0.0	70.1	105.7	-1.0	0.0	0.0	0.0	0.0	-0.0	-114.3	-114.3
271	528129.22	5511940.46	399.01	0	32	32.8	32.8	0.0	0.0	71.1	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-33.0	-33.0
272	528129.22	5511940.46	399.01	0	63	42.0	42.0	0.0	0.0	71.1	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-23.9	-23.9
273	528129.22	5511940.46	399.01	0	125	58.1	58.1	0.0	0.0	71.1	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-18.6	-18.6
274	528129.22	5511940.46	399.01	0	250	67.6	67.6	0.0	0.0	71.1	1.1	2.3	0.0	0.0	0.0	0.0	-0.0	-6.8	-6.8
275	528129.22	5511940.46	399.01	0	500	72.0	72.0	0.0	0.0	71.1	2.0	-1.0	0.0	0.0	0.0	0.0	-0.0	0.0	0.0
276	528129.22	5511940.46	399.01	0	1000	75.2	75.2	0.0	0.0	71.1	3.7	-1.1	0.0	0.0	0.0	0.0	-0.0	1.5	1.5
277	528129.22	5511940.46	399.01	0	2000	75.4	75.4	0.0	0.0	71.1	9.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-4.4	-4.4
278	528129.22	5511940.46	399.01	0	4000	68.2	68.2	0.0	0.0	71.1	33.2	-1.1	0.0	0.0	0.0	0.0	-0.0	-35.0	-35.0
279	528129.22	5511940.46	399.01	0	8000	61.1	61.1	0.0	0.0	71.1	118.3	-1.1	0.0	0.0	0.0	0.0	-0.0	-127.2	-127.2
280	528116.36	5511944.50	398.89	0	32	32.4	32.4	0.0	0.0	71.2	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-33.5	-33.5
281	528116.36	5511944.50	398.89	0	63	41.6	41.6	0.0	0.0	71.2	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-24.4	-24.4
282	528116.36	5511944.50	398.89	0	125	57.7	57.7	0.0	0.0	71.2	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-19.1	-19.1
283	528116.36	5511944.50	398.89	0	250	67.2	67.2	0.0	0.0	71.2	1.1	2.3	0.0	0.0	0.0	0.0	-0.0	-7.4	-7.4
284	528116.36	5511944.50	398.89	0	500	71.6	71.6	0.0	0.0	71.2	2.0	-1.0	0.0	0.0	0.0	0.0	-0.0	-0.5	-0.5
285	528116.36	5511944.50	398.89	0	1000	74.8	74.8	0.0	0.0	71.2	3.8	-1.1	0.0	0.0	0.0	0.0	-0.0	0.9	0.9
286	528116.36	5511944.50	398.89	0	2000	75.0	75.0	0.0	0.0	71.2	9.9	-1.1	0.0	0.0	0.0	0.0	-0.0	-5.0	-5.0
287	528116.36	5511944.50	398.89	0	4000	67.8	67.8	0.0	0.0	71.2	33.6	-1.1	0.0	0.0	0.0	0.0	-0.0	-35.9	-35.9
288	528116.36	5511944.50	398.89	0	8000	60.7	60.7	0.0	0.0	71.2	119.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-129.2	-129.2
289	528352.25	5512048.07	399.35	0	32	31.3	31.3	0.0	0.0	70.1	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-33.6	-33.6
290	528352.25	5512048.07	399.35	0	63	40.5	40.5	0.0	0.0	70.1	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-24.5	-24.5
291	528352.25	5512048.07	399.35	0	125	56.6	56.6	0.0	0.0	70.1	0.4	5.1	0.0	0.0	0.0	0.0	-0.0	-19.0	-19.0
292	528352.25	5512048.07	399.35	0	250	66.1	66.1	0.0	0.0	70.1	0.9	2.4	0.0	0.0	0.0	0.0	-0.0	-7.3	-7.3
293	528352.25	5512048.07	399.35	0	500	70.5	70.5	0.0	0.0	70.1	1.7	-1.0	0.0	0.0	0.0	0.0	-0.0	-0.3	-0.3
294	528352.25	5512048.07	399.35	0	1000	73.7	73.7	0.0	0.0	70.1	3.3	-1.0	0.0	0.0	0.0	0.0	-0.0	1.3	1.3
295	528352.25	5512048.07	399.35	0	2000	73.9	73.9	0.0	0.0	70.1	8.7	-1.0	0.0	0.0	0.0	0.0	-0.0	-3.9	-3.9
296	528352.25	5512048.07	399.35	0	4000	66.7	66.7	0.0	0.0	70.1	29.7	-1.0	0.0	0.0	0.0	0.0	-0.0	-32.0	-32.0
297	528352.25	5512048.07	399.35	0	8000	59.6	59.6	0.0	0.0	70.1	105.8	-1.0	0.0	0.0	0.0	0.0	-0.0	-115.2	-115.2
298	527937.06	5511855.74	403.18	0	32	32.1	32.1	0.0	0.0	72.2	0.0	-5.4	0.0	0.0	0.0	0.0	-0.0	-34.7	-34.7
299	527937.06	5511855.74	403.18	0	63	41.3	41.3	0.0	0.0	72.2	0.1	-5.4	0.0	0.0	0.0	0.0	-0.0	-25.6	-25.6
300	527937.06	5511855.74	403.18	0	125	57.4	57.4	0.0	0.0	72.2	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-20.5	-20.5
301	527937.06	5511855.74	403.18	0	250	66.9	66.9	0.0	0.0	72.2	1.2	2.3	0.0	0.0	0.0	0.0	-0.0	-8.7	-8.7
302	527937.06	5511855.74	403.18	0	500	71.3	71.3	0.0	0.0	72.2	2.2	-1.0	0.0	0.0	0.0	0.0	-0.0	-2.0	-2.0
303	527937.06	5511855.74	403.18	0	1000	74.5	74.5	0.0	0.0	72.2	4.2	-1.1	0.0	0.0	0.0	0.0	-0.0	-0.7	-0.7
304	527937.06	5511855.74	403.18	0	2000	74.7	74.7	0.0	0.0	72.2	11.1	-1.1	0.0	0.0	0.0	0.0	-0.0	-7.4	-7.4
305	527937.06	5511855.74	403.18	0	4000	67.5	67.5	0.0	0.0	72.2	37.4	-1.1	0.0	0.0	0.0	0.0	-0.0	-41.0	-41.0
306	527937.06	5511855.74	403.18	0	8000	60.4	60.4	0.0	0.0	72.2	133.6	-1.1	0.0	0.0	0.0	0.0	-0.0	-144.2	-144.2
307	528363.40	5512094.97	399.49	0	32	30.0	30.0	0.0	0.0	70.4	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-35.2	-35.2
308	528363.40	5512094.97	399.49	0	63	39.2	39.2	0.0	0.0	70.4	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-26.0	-26.0
309	528363.40	5512094.97	399.49	0	125	55.3	55.3	0.0	0.0	70.4	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-20.6	-20.6
310	528363.40	5512094.97	399.49	0	250	64.8	64.8	0.0	0.0	70.4	1.0	2.3	0.0	0.0	0.0	0.0	-0.0	-8.9	-8.9
311	528363.40	5512094.97	399.49	0	500	69.2	69.2	0.0	0.0	70.4	1.8	-1.0	0.0	0.0	0.0	0.0	-0.0	-2.0	-2.0
312	528363.40	5512094.97	399.49	0	1000	72.4	72.4	0.0	0.0	70.4	3.4	-1.1	0.0	0.0	0.0	0.0	-0.0	-0.3	-0.3
313	528363.40	5512094.97	399.49	0	2000	72.6	72.6	0.0	0.0	70.4	9.0	-1.1	0.0	0.0	0.0	0.0	-0.0	-5.7	-5.7
314	528363.40	5512094.97	399.49	0	4000	65.4	65.4	0.0	0.0	70.4	30.5	-1.1	0.0	0.0	0.0	0.0	-0.0	-34.4	-34.4
315	528363.40	5512094.97	399.49	0	8000	58.3	58.3	0.0	0.0	70.4	108.9	-1.1	0.0	0.0	0.0	0.0	-0.0	-119.9	-119.9

Line Source, ISO 9613, Name: "Haul Truck #1", ID: "Htruck1_o"																			
Nr.	X	Y	Z	RefI.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afof	Ahous	Abar	Cmet	RL	LrT	LrN

Line Source, ISO 9613, Name: "Haul Truck #1", ID: "Htruck1_o"																			
Nr.	X	Y	Z	Refl.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	dB	dB	dB	dB	dB	dB	dB	dB	dB	dB	dB(A)	dB(A)
379	528081.50	5511949.22	398.55	0	32	27.9	27.9	0.0	0.0	71.5	0.1	-5.3	0.0	0.0	4.8	0.0	-0.0	-43.0	-43.0
380	528081.50	5511949.22	398.55	0	63	37.1	37.1	0.0	0.0	71.5	0.1	-5.3	0.0	0.0	4.8	0.0	-0.0	-33.9	-33.9
381	528081.50	5511949.22	398.55	0	125	53.2	53.2	0.0	0.0	71.5	0.4	5.3	0.0	0.0	0.0	0.0	-0.0	-23.9	-23.9
382	528081.50	5511949.22	398.55	0	250	62.7	62.7	0.0	0.0	71.5	1.1	2.3	0.0	0.0	2.4	0.0	-0.0	-14.6	-14.6
383	528081.50	5511949.22	398.55	0	500	67.1	67.1	0.0	0.0	71.5	2.0	-1.0	0.0	0.0	4.8	0.0	-0.0	-10.1	-10.1
384	528081.50	5511949.22	398.55	0	1000	70.3	70.3	0.0	0.0	71.5	3.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-8.7	-8.7
385	528081.50	5511949.22	398.55	0	2000	70.5	70.5	0.0	0.0	71.5	10.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-14.9	-14.9
386	528081.50	5511949.22	398.55	0	4000	63.3	63.3	0.0	0.0	71.5	34.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-46.5	-46.5
387	528081.50	5511949.22	398.55	0	8000	56.2	56.2	0.0	0.0	71.5	123.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-142.5	-142.5
388	528077.11	5511949.37	398.44	0	32	27.6	27.6	0.0	0.0	71.5	0.0	-5.3	0.0	0.0	4.8	0.0	-0.0	-43.4	-43.4
389	528077.11	5511949.37	398.44	0	63	36.8	36.8	0.0	0.0	71.5	0.1	-5.3	0.0	0.0	4.8	0.0	-0.0	-34.3	-34.3
390	528077.11	5511949.37	398.44	0	125	52.9	52.9	0.0	0.0	71.5	0.4	5.3	0.0	0.0	0.0	0.0	-0.0	-24.3	-24.3
391	528077.11	5511949.37	398.44	0	250	62.4	62.4	0.0	0.0	71.5	1.1	2.3	0.0	0.0	2.4	0.0	-0.0	-15.0	-15.0
392	528077.11	5511949.37	398.44	0	500	66.8	66.8	0.0	0.0	71.5	2.0	-1.0	0.0	0.0	4.8	0.0	-0.0	-10.5	-10.5
393	528077.11	5511949.37	398.44	0	1000	70.0	70.0	0.0	0.0	71.5	3.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-9.1	-9.1
394	528077.11	5511949.37	398.44	0	2000	70.2	70.2	0.0	0.0	71.5	10.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-15.2	-15.2
395	528077.11	5511949.37	398.44	0	4000	63.0	63.0	0.0	0.0	71.5	34.8	-1.1	0.0	0.0	4.8	0.0	-0.0	-46.9	-46.9
396	528077.11	5511949.37	398.44	0	8000	55.9	55.9	0.0	0.0	71.5	124.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-143.3	-143.3
397	527993.02	5511872.03	401.47	0	32	27.8	27.8	0.0	0.0	71.8	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-38.7	-38.7
398	527993.02	5511872.03	401.47	0	63	37.0	37.0	0.0	0.0	71.8	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-29.6	-29.6
399	527993.02	5511872.03	401.47	0	125	53.1	53.1	0.0	0.0	71.8	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-24.4	-24.4
400	527993.02	5511872.03	401.47	0	250	62.6	62.6	0.0	0.0	71.8	1.2	2.3	0.0	0.0	0.0	0.0	-0.0	-12.7	-12.7
401	527993.02	5511872.03	401.47	0	500	67.0	67.0	0.0	0.0	71.8	2.1	-1.0	0.0	0.0	0.0	0.0	-0.0	-5.9	-5.9
402	527993.02	5511872.03	401.47	0	1000	70.2	70.2	0.0	0.0	71.8	4.0	-1.1	0.0	0.0	0.0	0.0	-0.0	-4.6	-4.6
403	527993.02	5511872.03	401.47	0	2000	70.4	70.4	0.0	0.0	71.8	10.6	-1.1	0.0	0.0	0.0	0.0	-0.0	-11.0	-11.0
404	527993.02	5511872.03	401.47	0	4000	63.2	63.2	0.0	0.0	71.8	36.0	-1.1	0.0	0.0	0.0	0.0	-0.0	-43.6	-43.6
405	527993.02	5511872.03	401.47	0	8000	56.1	56.1	0.0	0.0	71.8	128.4	-1.1	0.0	0.0	0.0	0.0	-0.0	-143.1	-143.1
406	528389.49	5512104.65	400.41	0	32	26.2	26.2	0.0	0.0	70.3	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-38.9	-38.9
407	528389.49	5512104.65	400.41	0	63	35.4	35.4	0.0	0.0	70.3	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-29.8	-29.8
408	528389.49	5512104.65	400.41	0	125	51.5	51.5	0.0	0.0	70.3	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-24.3	-24.3
409	528389.49	5512104.65	400.41	0	250	61.0	61.0	0.0	0.0	70.3	1.0	2.3	0.0	0.0	0.0	0.0	-0.0	-12.6	-12.6
410	528389.49	5512104.65	400.41	0	500	65.4	65.4	0.0	0.0	70.3	1.8	-1.0	0.0	0.0	0.0	0.0	-0.0	-5.6	-5.6
411	528389.49	5512104.65	400.41	0	1000	68.6	68.6	0.0	0.0	70.3	3.4	-1.0	0.0	0.0	0.0	0.0	-0.0	-4.0	-4.0
412	528389.49	5512104.65	400.41	0	2000	68.8	68.8	0.0	0.0	70.3	8.9	-1.0	0.0	0.0	0.0	0.0	-0.0	-9.3	-9.3
413	528389.49	5512104.65	400.41	0	4000	61.6	61.6	0.0	0.0	70.3	30.2	-1.0	0.0	0.0	0.0	0.0	-0.0	-37.8	-37.8
414	528389.49	5512104.65	400.41	0	8000	54.5	54.5	0.0	0.0	70.3	107.7	-1.0	0.0	0.0	0.0	0.0	-0.0	-122.4	-122.4
415	527926.98	5511858.27	402.67	0	32	26.1	26.1	0.0	0.0	72.2	0.0	-5.4	0.0	0.0	0.0	0.0	-0.0	-40.8	-40.8
416	527926.98	5511858.27	402.67	0	63	35.3	35.3	0.0	0.0	72.2	0.1	-5.4	0.0	0.0	0.0	0.0	-0.0	-31.7	-31.7
417	527926.98	5511858.27	402.67	0	125	51.4	51.4	0.0	0.0	72.2	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-26.6	-26.6
418	527926.98	5511858.27	402.67	0	250	60.9	60.9	0.0	0.0	72.2	1.2	2.3	0.0	0.0	0.0	0.0	-0.0	-14.8	-14.8
419	527926.98	5511858.27	402.67	0	500	65.3	65.3	0.0	0.0	72.2	2.2	-1.0	0.0	0.0	0.0	0.0	-0.0	-8.1	-8.1
420	527926.98	5511858.27	402.67	0	1000	68.5	68.5	0.0	0.0	72.2	4.2	-1.1	0.0	0.0	0.0	0.0	-0.0	-6.8	-6.8
421	527926.98	5511858.27	402.67	0	2000	68.7	68.7	0.0	0.0	72.2	11.1	-1.1	0.0	0.0	0.0	0.0	-0.0	-13.6	-13.6
422	527926.98	5511858.27	402.67	0	4000	61.5	61.5	0.0	0.0	72.2	37.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-47.4	-47.4
423	527926.98	5511858.27	402.67	0	8000	54.4	54.4	0.0	0.0	72.2	134.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-151.5	-151.5
424	527929.84	5511857.55	402.75	0	32	26.0	26.0	0.0	0.0	72.2	0.0	-5.4	0.0	0.0	0.0	0.0	-0.0	-40.9	-40.9
425	527929.84	5511857.55	402.75	0	63	35.2	35.2	0.0	0.0	72.2	0.1	-5.4	0.0	0.0	0.0	0.0	-0.0	-31.8	-31.8
426	527929.84	5511857.55	402.75	0	125	51.3	51.3	0.0	0.0	72.2	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-26.7	-26.7
427	527929.84	5511857.55	402.75	0	250	60.8	60.8	0.0	0.0	72.2	1.2	2.3	0.0	0.0	0.0	0.0	-0.0	-15.0	-15.0
428	527929.84	5511857.55	402.75	0	500	65.2	65.2	0.0	0.0	72.2	2.2	-1.0	0.0	0.0	0.0	0.0	-0.0	-8.2	-8.2
429	527929.84	5511857.55	402.75	0	1000	68.4	68.4	0.0	0.0	72.2	4.2	-1.1	0.0	0.0	0.0	0.0	-0.0	-7.0	-7.0
430	527929.84	5511857.55	402.75	0	2000	68.6	68.6	0.0	0.0	72.2	11.1	-1.1	0.0	0.0	0.0	0.0	-0.0	-13.7	-13.7
431	527929.84	5511857.55	402.75	0	4000	61.4	61.4	0.0	0.0	72.2	37.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-47.5	-47.5
432	527929.84	5511857.55	402.75	0	8000	54.3	54.3	0.0	0.0	72.2	134.5	-1.1	0.0	0.0	0.0	0.0	-0.0	-153.3	-153.3
433	528102.58	5511948.54	398.76	0	32	24.5	24.5	0.0	0.0	71.3	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-41.5	-41.5
434	528102.58	5511948.54	398.76	0	63	33.7	33.7	0.0	0.0	71.3	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-32.4	-32.4
435	528102.58	5511948.54	398.76	0	125	49.8	49.8	0.0	0.0	71.3	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-27.2	-27.2
436	528102.58	5511948.54	398.76	0	250	59.3	59.3	0.0	0.0	71.3	1.1	2.3	0.0	0.0	0.0	0.0	-0.0	-15.4	-15.4
437	528102.58	5511948.54	398.76	0	500	63.7	63.7	0.0	0.0	71.3	2.0	-1.0	0.0	0.0	0.0	0.0	-0.0	-8.6	-8.6
438	528102.58	5511948.54	398.76	0	1000	66.9	66.9	0.0	0.0	71.3	3.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-7.1	-7.1
439	528102.58	5511948.54	398.76	0	2000	67.1	67.1	0.0	0.0	71.3	10.0	-1.1	0.0	0.0	0.0	0.0	-0.0	-13.2	-13.2
440	528102.58	5511948.54	398.76	0	4000	59.9	59.9	0.0	0.0	71.3	34.0	-1.1	0.0	0.0	0.0	0.0	-0.0	-44.4	-44.4
441	528102.58	5511948.54	398.76	0	8000	52.8	52.8	0.0	0.0	71.3	121.4	-1.1	0.0	0.0	0.0	0.0	-0.0	-138.9	-138.9

Sample Calculation at facade of NR03

Line Source, ISO 9613, Name: "Haul Truck #2", ID: "Htruck2_o"																	
Nr.	X	Y	Z	Refl.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar</		

Line Source, ISO 9613, Name: "Haul Truck #2", ID: "Htruck2_o"																			
Nr.	X	Y	Z	RefI.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	AfoI	Afous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)
64	528431.88	5511834.17	399.60	0	32	33.8	33.8	0.0	0.0	67.9	0.0	-5.0	0.0	0.0	0.0	0.0	-2.1	-2.1	-2.1
65	528431.88	5511834.17	399.60	0	63	43.0	43.0	0.0	0.0	67.9	0.1	-5.0	0.0	0.0	0.0	0.0	-2.0	-2.0	-2.0
66	528431.88	5511834.17	399.60	0	125	59.1	59.1	0.0	0.0	67.9	0.3	4.8	0.0	0.0	0.0	0.0	-13.9	-13.9	-13.9
67	528431.88	5511834.17	399.60	0	250	68.6	68.6	0.0	0.0	67.9	0.7	2.4	0.0	0.0	0.0	0.0	-2.4	-2.4	-2.4
68	528431.88	5511834.17	399.60	0	500	73.0	73.0	0.0	0.0	67.9	1.4	-1.0	0.0	0.0	0.0	0.0	4.7	4.7	4.7
69	528431.88	5511834.17	399.60	0	1000	76.2	76.2	0.0	0.0	67.9	2.6	-1.0	0.0	0.0	0.0	0.0	6.7	6.7	6.7
70	528431.88	5511834.17	399.60	0	2000	76.4	76.4	0.0	0.0	67.9	6.8	-1.0	0.0	0.0	0.0	0.0	2.7	2.7	2.7
71	528431.88	5511834.17	399.60	0	4000	69.2	69.2	0.0	0.0	67.9	23.0	-1.0	0.0	0.0	0.0	0.0	-20.7	-20.7	-20.7
72	528431.88	5511834.17	399.60	0	8000	62.1	62.1	0.0	0.0	67.9	82.1	-1.0	0.0	0.0	0.0	0.0	-86.9	-86.9	-86.9
73	527952.82	5511860.26	402.60	0	32	37.8	37.8	0.0	0.0	72.1	0.0	-5.4	0.0	0.0	0.0	0.0	-28.9	-28.9	-28.9
74	527952.82	5511860.26	402.60	0	63	47.0	47.0	0.0	0.0	72.1	0.1	-5.4	0.0	0.0	0.0	0.0	-19.8	-19.8	-19.8
75	527952.82	5511860.26	402.60	0	125	63.1	63.1	0.0	0.0	72.1	0.5	5.3	0.0	0.0	0.0	0.0	-14.7	-14.7	-14.7
76	527952.82	5511860.26	402.60	0	250	72.6	72.6	0.0	0.0	72.1	1.2	2.3	0.0	0.0	0.0	0.0	-2.9	-2.9	-2.9
77	527952.82	5511860.26	402.60	0	500	77.0	77.0	0.0	0.0	72.1	2.2	-1.0	0.0	0.0	0.0	0.0	3.8	3.8	3.8
78	527952.82	5511860.26	402.60	0	1000	80.2	80.2	0.0	0.0	72.1	4.1	-1.1	0.0	0.0	0.0	0.0	5.1	5.1	5.1
79	527952.82	5511860.26	402.60	0	2000	80.4	80.4	0.0	0.0	72.1	10.9	-1.1	0.0	0.0	0.0	0.0	-1.5	-1.5	-1.5
80	527952.82	5511860.26	402.60	0	4000	73.2	73.2	0.0	0.0	72.1	37.0	-1.1	0.0	0.0	0.0	0.0	-34.8	-34.8	-34.8
81	527952.82	5511860.26	402.60	0	8000	66.1	66.1	0.0	0.0	72.1	132.1	-1.1	0.0	0.0	0.0	0.0	-137.0	-137.0	-137.0
82	528328.50	5512009.55	399.35	0	32	35.9	35.9	0.0	0.0	70.0	0.0	-5.2	0.0	0.0	0.0	0.0	-28.9	-28.9	-28.9
83	528328.50	5512009.55	399.35	0	63	45.1	45.1	0.0	0.0	70.0	0.1	-5.2	0.0	0.0	0.0	0.0	-19.8	-19.8	-19.8
84	528328.50	5512009.55	399.35	0	125	61.2	61.2	0.0	0.0	70.0	0.4	5.1	0.0	0.0	0.0	0.0	-14.3	-14.3	-14.3
85	528328.50	5512009.55	399.35	0	250	70.7	70.7	0.0	0.0	70.0	0.9	2.4	0.0	0.0	0.0	0.0	-2.6	-2.6	-2.6
86	528328.50	5512009.55	399.35	0	500	75.1	75.1	0.0	0.0	70.0	1.7	-1.0	0.0	0.0	0.0	0.0	4.4	4.4	4.4
87	528328.50	5512009.55	399.35	0	1000	78.3	78.3	0.0	0.0	70.0	3.3	-1.0	0.0	0.0	0.0	0.0	6.1	6.1	6.1
88	528328.50	5512009.55	399.35	0	2000	78.5	78.5	0.0	0.0	70.0	8.7	-1.0	0.0	0.0	0.0	0.0	0.9	0.9	0.9
89	528328.50	5512009.55	399.35	0	4000	71.3	71.3	0.0	0.0	70.0	29.3	-1.0	0.0	0.0	0.0	0.0	-27.0	-27.0	-27.0
90	528328.50	5512009.55	399.35	0	8000	64.2	64.2	0.0	0.0	70.0	104.6	-1.0	0.0	0.0	0.0	0.0	-109.4	-109.4	-109.4
91	528214.84	5511950.50	399.48	0	32	36.3	36.3	0.0	0.0	70.5	0.0	-5.2	0.0	0.0	0.0	0.0	-29.0	-29.0	-29.0
92	528214.84	5511950.50	399.48	0	63	45.5	45.5	0.0	0.0	70.5	0.1	-5.2	0.0	0.0	0.0	0.0	-19.9	-19.9	-19.9
93	528214.84	5511950.50	399.48	0	125	61.6	61.6	0.0	0.0	70.5	0.4	5.2	0.0	0.0	0.0	0.0	-14.5	-14.5	-14.5
94	528214.84	5511950.50	399.48	0	250	71.1	71.1	0.0	0.0	70.5	1.0	2.3	0.0	0.0	0.0	0.0	-2.8	-2.8	-2.8
95	528214.84	5511950.50	399.48	0	500	75.5	75.5	0.0	0.0	70.5	1.8	-1.0	0.0	0.0	0.0	0.0	4.1	4.1	4.1
96	528214.84	5511950.50	399.48	0	1000	78.7	78.7	0.0	0.0	70.5	3.5	-1.1	0.0	0.0	0.0	0.0	5.8	5.8	5.8
97	528214.84	5511950.50	399.48	0	2000	78.9	78.9	0.0	0.0	70.5	9.1	-1.1	0.0	0.0	0.0	0.0	0.3	0.3	0.3
98	528214.84	5511950.50	399.48	0	4000	71.7	71.7	0.0	0.0	70.5	31.0	-1.1	0.0	0.0	0.0	0.0	-28.8	-28.8	-28.8
99	528214.84	5511950.50	399.48	0	8000	64.6	64.6	0.0	0.0	70.5	110.6	-1.1	0.0	0.0	0.0	0.0	-115.5	-115.5	-115.5
100	528379.77	5512086.35	399.50	0	32	35.7	35.7	0.0	0.0	70.2	0.0	-5.2	0.0	0.0	0.0	0.0	-29.4	-29.4	-29.4
101	528379.77	5512086.35	399.50	0	63	44.9	44.9	0.0	0.0	70.2	0.1	-5.2	0.0	0.0	0.0	0.0	-20.3	-20.3	-20.3
102	528379.77	5512086.35	399.50	0	125	61.0	61.0	0.0	0.0	70.2	0.4	5.1	0.0	0.0	0.0	0.0	-14.8	-14.8	-14.8
103	528379.77	5512086.35	399.50	0	250	70.5	70.5	0.0	0.0	70.2	1.0	2.3	0.0	0.0	0.0	0.0	-3.1	-3.1	-3.1
104	528379.77	5512086.35	399.50	0	500	74.9	74.9	0.0	0.0	70.2	1.8	-1.0	0.0	0.0	0.0	0.0	3.9	3.9	3.9
105	528379.77	5512086.35	399.50	0	1000	78.1	78.1	0.0	0.0	70.2	3.3	-1.0	0.0	0.0	0.0	0.0	5.5	5.5	5.5
106	528379.77	5512086.35	399.50	0	2000	78.3	78.3	0.0	0.0	70.2	8.8	-1.0	0.0	0.0	0.0	0.0	0.3	0.3	0.3
107	528379.77	5512086.35	399.50	0	4000	71.1	71.1	0.0	0.0	70.2	29.9	-1.0	0.0	0.0	0.0	0.0	-28.1	-28.1	-28.1
108	528379.77	5512086.35	399.50	0	8000	64.0	64.0	0.0	0.0	70.2	106.8	-1.0	0.0	0.0	0.0	0.0	-112.1	-112.1	-112.1
109	528397.40	5512069.15	399.22	0	32	35.4	35.4	0.0	0.0	70.0	0.0	-5.2	0.0	0.0	0.0	0.0	-29.4	-29.4	-29.4
110	528397.40	5512069.15	399.22	0	63	44.6	44.6	0.0	0.0	70.0	0.1	-5.2	0.0	0.0	0.0	0.0	-20.3	-20.3	-20.3
111	528397.40	5512069.15	399.22	0	125	60.7	60.7	0.0	0.0	70.0	0.4	5.1	0.0	0.0	0.0	0.0	-14.8	-14.8	-14.8
112	528397.40	5512069.15	399.22	0	250	70.2	70.2	0.0	0.0	70.0	0.9	2.4	0.0	0.0	0.0	0.0	-3.1	-3.1	-3.1
113	528397.40	5512069.15	399.22	0	500	74.6	74.6	0.0	0.0	70.0	1.7	-1.0	0.0	0.0	0.0	0.0	3.9	3.9	3.9
114	528397.40	5512069.15	399.22	0	1000	77.8	77.8	0.0	0.0	70.0	3.3	-1.0	0.0	0.0	0.0	0.0	5.6	5.6	5.6
115	528397.40	5512069.15	399.22	0	2000	78.0	78.0	0.0	0.0	70.0	8.6	-1.0	0.0	0.0	0.0	0.0	0.5	0.5	0.5
116	528397.40	5512069.15	399.22	0	4000	70.8	70.8	0.0	0.0	70.0	29.2	-1.0	0.0	0.0	0.0	0.0	-27.3	-27.3	-27.3
117	528397.40	5512069.15	399.22	0	8000	63.7	63.7	0.0	0.0	70.0	104.0	-1.0	0.0	0.0	0.0	0.0	-109.2	-109.2	-109.2
118	528360.42	5512053.46	399.28	0	32	35.5	35.5	0.0	0.0	70.1	0.0	-5.2	0.0	0.0	0.0	0.0	-29.5	-29.5	-29.5
119	528360.42	5512053.46	399.28	0	63	44.7	44.7	0.0	0.0	70.1	0.1	-5.2	0.0	0.0	0.0	0.0	-20.4	-20.4	-20.4
120	528360.42	5512053.46	399.28	0	125	60.8	60.8	0.0	0.0	70.1	0.4	5.1	0.0	0.0	0.0	0.0	-14.9	-14.9	-14.9
121	528360.42	5512053.46	399.28	0	250	70.3	70.3	0.0	0.0	70.1	0.9	2.4	0.0	0.0	0.0	0.0	-3.1	-3.1	-3.1
122	528360.42	5512053.46	399.28	0	500	74.7	74.7	0.0	0.0	70.1	1.7	-1.0	0.0	0.0	0.0	0.0	3.8	3.8	3.8
123	528360.42	5512053.46	399.28	0	1000	77.9	77.9	0.0	0.0	70.1	3.3	-1.0	0.0	0.0	0.0	0.0	5.5	5.5	5.5
124	528360.42	5512053.46	399.28	0	2000	78.1	78.1	0.0	0.0	70.1	8.7	-1.0	0.0	0.0	0.0	0.0	0.3	0.3	0.3
125	528360.42	5512053.46	399.28	0	4000	70.9	70.9	0.0	0.0	70.1	29.6	-1.0	0.0	0.0	0.0	0.0	-27.8	-27.8	-27.8
126	528360.42	5512053.46	399.28	0	8000	63.8	63.8	0.0	0.0	70.1	105.6	-1.0	0.0	0.0	0.0	0.0	-110.9	-110.9	-110.9

Sample Calculation at facade of NR03

Line Source, ISO 9613, Name: "Haul Truck #2", ID: "Htruck2_o"																			
Nr.	X	Y	Z	RefI.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	AfoI	Afous	Abar	Cmet	RL	LrT	LrN

Line Source, ISO 9613, Name: "Haul Truck #2", ID: "Htruck2_o"																			
Nr.	X	Y	Z	Refl.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	dB(A)	dB(A)
190	528188.51	5511945.88	399.52	0	32	34.8	34.8	0.0	0.0	70.7	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-30.6	-30.6
191	528188.51	5511945.88	399.52	0	63	44.0	44.0	0.0	0.0	70.7	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-21.5	-21.5
192	528188.51	5511945.88	399.52	0	125	60.1	60.1	0.0	0.0	70.7	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-16.1	-16.1
193	528188.51	5511945.88	399.52	0	250	69.6	69.6	0.0	0.0	70.7	1.0	2.3	0.0	0.0	0.0	0.0	-0.0	-4.4	-4.4
194	528188.51	5511945.88	399.52	0	500	74.0	74.0	0.0	0.0	70.7	1.9	-1.0	0.0	0.0	0.0	0.0	-0.0	2.5	2.5
195	528188.51	5511945.88	399.52	0	1000	77.2	77.2	0.0	0.0	70.7	3.5	-1.1	0.0	0.0	0.0	0.0	-0.0	4.1	4.1
196	528188.51	5511945.88	399.52	0	2000	77.4	77.4	0.0	0.0	70.7	9.3	-1.1	0.0	0.0	0.0	0.0	-0.0	-1.5	-1.5
197	528188.51	5511945.88	399.52	0	4000	70.2	70.2	0.0	0.0	70.7	31.6	-1.1	0.0	0.0	0.0	0.0	-0.0	-31.0	-31.0
198	528188.51	5511945.88	399.52	0	8000	63.1	63.1	0.0	0.0	70.7	112.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-119.3	-119.3
199	527682.76	5511832.72	394.27	0	32	37.8	37.8	0.0	0.0	73.8	0.0	-5.5	0.0	0.0	4.8	0.0	-0.0	-35.3	-35.3
200	527682.76	5511832.72	394.27	0	63	47.0	47.0	0.0	0.0	73.8	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-26.2	-26.2
201	527682.76	5511832.72	394.27	0	125	63.1	63.1	0.0	0.0	73.8	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-16.5	-16.5
202	527682.76	5511832.72	394.27	0	250	72.6	72.6	0.0	0.0	73.8	1.4	2.3	0.0	0.0	2.5	0.0	-0.0	-7.4	-7.4
203	527682.76	5511832.72	394.27	0	500	77.0	77.0	0.0	0.0	73.8	2.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-3.1	-3.1
204	527682.76	5511832.72	394.27	0	1000	80.2	80.2	0.0	0.0	73.8	5.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-2.3	-2.3
205	527682.76	5511832.72	394.27	0	2000	80.4	80.4	0.0	0.0	73.8	13.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-10.3	-10.3
206	527682.76	5511832.72	394.27	0	4000	73.2	73.2	0.0	0.0	73.8	45.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-49.2	-49.2
207	527682.76	5511832.72	394.27	0	8000	66.1	66.1	0.0	0.0	73.8	160.4	-1.1	0.0	0.0	4.8	0.0	-0.0	-171.8	-171.8
208	528306.29	5511985.21	399.35	0	32	33.8	33.8	0.0	0.0	70.0	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-31.1	-31.1
209	528306.29	5511985.21	399.35	0	63	43.0	43.0	0.0	0.0	70.0	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-22.0	-22.0
210	528306.29	5511985.21	399.35	0	125	59.1	59.1	0.0	0.0	70.0	0.4	5.1	0.0	0.0	0.0	0.0	-0.0	-16.4	-16.4
211	528306.29	5511985.21	399.35	0	250	68.6	68.6	0.0	0.0	70.0	0.9	2.4	0.0	0.0	0.0	0.0	-0.0	-4.7	-4.7
212	528306.29	5511985.21	399.35	0	500	73.0	73.0	0.0	0.0	70.0	1.7	-1.0	0.0	0.0	0.0	0.0	-0.0	2.2	2.2
213	528306.29	5511985.21	399.35	0	1000	76.2	76.2	0.0	0.0	70.0	3.3	-1.0	0.0	0.0	0.0	0.0	-0.0	3.9	3.9
214	528306.29	5511985.21	399.35	0	2000	76.4	76.4	0.0	0.0	70.0	8.7	-1.0	0.0	0.0	0.0	0.0	-0.0	-1.3	-1.3
215	528306.29	5511985.21	399.35	0	4000	69.2	69.2	0.0	0.0	70.0	29.4	-1.0	0.0	0.0	0.0	0.0	-0.0	-29.2	-29.2
216	528306.29	5511985.21	399.35	0	8000	62.1	62.1	0.0	0.0	70.0	104.7	-1.0	0.0	0.0	0.0	0.0	-0.0	-111.6	-111.6
217	527534.04	5511753.63	395.79	0	32	37.8	37.8	0.0	0.0	74.5	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-36.0	-36.0
218	527534.04	5511753.63	395.79	0	63	47.0	47.0	0.0	0.0	74.5	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-27.0	-27.0
219	527534.04	5511753.63	395.79	0	125	63.1	63.1	0.0	0.0	74.5	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-17.4	-17.4
220	527534.04	5511753.63	395.79	0	250	72.6	72.6	0.0	0.0	74.5	1.6	2.3	0.0	0.0	2.5	0.0	-0.0	-8.3	-8.3
221	527534.04	5511753.63	395.79	0	500	77.0	77.0	0.0	0.0	74.5	2.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-4.1	-4.1
222	527534.04	5511753.63	395.79	0	1000	80.2	80.2	0.0	0.0	74.5	5.5	-1.1	0.0	0.0	4.8	0.0	-0.0	-3.5	-3.5
223	527534.04	5511753.63	395.79	0	2000	80.4	80.4	0.0	0.0	74.5	14.4	-1.1	0.0	0.0	4.8	0.0	-0.0	-12.2	-12.2
224	527534.04	5511753.63	395.79	0	4000	73.2	73.2	0.0	0.0	74.5	49.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-54.0	-54.0
225	527534.04	5511753.63	395.79	0	8000	66.1	66.1	0.0	0.0	74.5	174.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-186.7	-186.7
226	528131.87	5511945.36	399.04	0	32	34.2	34.2	0.0	0.0	71.1	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-31.7	-31.7
227	528131.87	5511945.36	399.04	0	63	43.4	43.4	0.0	0.0	71.1	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-22.6	-22.6
228	528131.87	5511945.36	399.04	0	125	59.5	59.5	0.0	0.0	71.1	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-17.3	-17.3
229	528131.87	5511945.36	399.04	0	250	69.0	69.0	0.0	0.0	71.1	1.1	2.3	0.0	0.0	0.0	0.0	-0.0	-5.5	-5.5
230	528131.87	5511945.36	399.04	0	500	73.4	73.4	0.0	0.0	71.1	2.0	-1.0	0.0	0.0	0.0	0.0	-0.0	1.3	1.3
231	528131.87	5511945.36	399.04	0	1000	76.6	76.6	0.0	0.0	71.1	3.7	-1.1	0.0	0.0	0.0	0.0	-0.0	2.8	2.8
232	528131.87	5511945.36	399.04	0	2000	76.8	76.8	0.0	0.0	71.1	9.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-3.1	-3.1
233	528131.87	5511945.36	399.04	0	4000	69.6	69.6	0.0	0.0	71.1	33.2	-1.1	0.0	0.0	0.0	0.0	-0.0	-33.6	-33.6
234	528131.87	5511945.36	399.04	0	8000	62.5	62.5	0.0	0.0	71.1	118.3	-1.1	0.0	0.0	0.0	0.0	-0.0	-125.9	-125.9
235	528002.84	5511884.45	400.78	0	32	34.6	34.6	0.0	0.0	71.8	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-31.9	-31.9
236	528002.84	5511884.45	400.78	0	63	43.8	43.8	0.0	0.0	71.8	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-22.8	-22.8
237	528002.84	5511884.45	400.78	0	125	59.9	59.9	0.0	0.0	71.8	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-17.7	-17.7
238	528002.84	5511884.45	400.78	0	250	69.4	69.4	0.0	0.0	71.8	1.1	2.3	0.0	0.0	0.0	0.0	-0.0	-5.9	-5.9
239	528002.84	5511884.45	400.78	0	500	73.8	73.8	0.0	0.0	71.8	2.1	-1.0	0.0	0.0	0.0	0.0	-0.0	0.9	0.9
240	528002.84	5511884.45	400.78	0	1000	77.0	77.0	0.0	0.0	71.8	4.0	-1.1	0.0	0.0	0.0	0.0	-0.0	2.2	2.2
241	528002.84	5511884.45	400.78	0	2000	77.2	77.2	0.0	0.0	71.8	10.6	-1.1	0.0	0.0	0.0	0.0	-0.0	-4.1	-4.1
242	528002.84	5511884.45	400.78	0	4000	70.0	70.0	0.0	0.0	71.8	35.9	-1.1	0.0	0.0	0.0	0.0	-0.0	-36.6	-36.6
243	528002.84	5511884.45	400.78	0	8000	62.9	62.9	0.0	0.0	71.8	128.0	-1.1	0.0	0.0	0.0	0.0	-0.0	-135.9	-135.9
244	527982.67	5511869.54	401.92	0	32	34.0	34.0	0.0	0.0	71.9	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-32.4	-32.4
245	527982.67	5511869.54	401.92	0	63	43.2	43.2	0.0	0.0	71.9	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-23.5	-23.5
246	527982.67	5511869.54	401.92	0	125	59.3	59.3	0.0	0.0	71.9	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-18.3	-18.3
247	527982.67	5511869.54	401.92	0	250	68.8	68.8	0.0	0.0	71.9	1.2	2.3	0.0	0.0	0.0	0.0	-0.0	-6.5	-6.5
248	527982.67	5511869.54	401.92	0	500	73.2	73.2	0.0	0.0	71.9	2.1	-1.0	0.0	0.0	0.0	0.0	-0.0	0.3	0.3
249	527982.67	5511869.54	401.92	0	1000	76.4	76.4	0.0	0.0	71.9	4.0	-1.1	0.0	0.0	0.0	0.0	-0.0	1.6	1.6
250	527982.67	5511869.54	401.92	0	2000	76.6	76.6	0.0	0.0	71.9	10.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-4.9	-4.9
251	527982.67	5511869.54	401.92	0	4000	69.4	69.4	0.0	0.0	71.9	36.3	-1.1	0.0	0.0	0.0	0.0	-0.0	-37.6	-37.6
252	527982.67	5511869.54	401.92	0	8000	62.3	62.3	0.0	0.0	71.9	129.4	-1.1	0.0	0.0	0.0	0.0	-0.0	-137.9	-137.9

Sample Calculation at facade of NR03

Line Source, ISO 9613, Name: "Haul Truck #2", ID: "Htruck2_o"																			
Nr.	X	Y	Z	Refl.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT	Lr



Line Source, ISO 9613, Name: "Haul Truck #2", ID: "Htruck2_o"																			
Nr.	X	Y	Z	RefL	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	dB	dB	dB	dB	dB	dB	dB	dB	dB	dB	dB(A)	dB(A)
316	528057.34	5511944.50	397.47	0	32	32.5	32.5	0.0	0.0	71.6	0.0	-5.3	0.0	0.0	4.8	0.0	-0.0	-38.6	-38.6
317	528057.34	5511944.50	397.47	0	63	41.7	41.7	0.0	0.0	71.6	0.1	-5.3	0.0	0.0	4.8	0.0	-0.0	-29.5	-29.5
318	528057.34	5511944.50	397.47	0	125	57.8	57.8	0.0	0.0	71.6	0.4	5.3	0.0	0.0	0.0	0.0	-0.0	-19.5	-19.5
319	528057.34	5511944.50	397.47	0	250	67.3	67.3	0.0	0.0	71.6	1.1	2.3	0.0	0.0	2.4	0.0	-0.0	-10.2	-10.2
320	528057.34	5511944.50	397.47	0	500	71.7	71.7	0.0	0.0	71.6	2.1	-1.0	0.0	0.0	4.8	0.0	-0.0	-5.7	-5.7
321	528057.34	5511944.50	397.47	0	1000	74.9	74.9	0.0	0.0	71.6	3.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-4.4	-4.4
322	528057.34	5511944.50	397.47	0	2000	75.1	75.1	0.0	0.0	71.6	10.4	-1.1	0.0	0.0	4.8	0.0	-0.0	-10.6	-10.6
323	528057.34	5511944.50	397.47	0	4000	67.9	67.9	0.0	0.0	71.6	35.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-42.7	-42.7
324	528057.34	5511944.50	397.47	0	8000	60.8	60.8	0.0	0.0	71.6	125.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-140.2	-140.2
325	527636.81	5511789.59	394.26	0	32	34.7	34.7	0.0	0.0	74.0	0.0	-5.5	0.0	0.0	4.8	0.0	-0.0	-38.6	-38.6
326	527636.81	5511789.59	394.26	0	63	43.9	43.9	0.0	0.0	74.0	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-29.5	-29.5
327	527636.81	5511789.59	394.26	0	125	60.0	60.0	0.0	0.0	74.0	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-19.8	-19.8
328	527636.81	5511789.59	394.26	0	250	69.5	69.5	0.0	0.0	74.0	1.5	2.3	0.0	0.0	2.5	0.0	-0.0	-10.7	-10.7
329	527636.81	5511789.59	394.26	0	500	73.9	73.9	0.0	0.0	74.0	2.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-6.5	-6.5
330	527636.81	5511789.59	394.26	0	1000	77.1	77.1	0.0	0.0	74.0	5.1	-1.1	0.0	0.0	4.8	0.0	-0.0	-5.6	-5.6
331	527636.81	5511789.59	394.26	0	2000	77.3	77.3	0.0	0.0	74.0	13.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-13.9	-13.9
332	527636.81	5511789.59	394.26	0	4000	70.1	70.1	0.0	0.0	74.0	46.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-53.5	-53.5
333	527636.81	5511789.59	394.26	0	8000	63.0	63.0	0.0	0.0	74.0	164.1	-1.1	0.0	0.0	4.8	0.0	-0.0	-178.7	-178.7
334	527708.09	5511852.14	394.19	0	32	34.3	34.3	0.0	0.0	73.6	0.0	-5.5	0.0	0.0	4.8	0.0	-0.0	-38.6	-38.6
335	527708.09	5511852.14	394.19	0	63	43.5	43.5	0.0	0.0	73.6	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-29.6	-29.6
336	527708.09	5511852.14	394.19	0	125	59.6	59.6	0.0	0.0	73.6	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-19.9	-19.9
337	527708.09	5511852.14	394.19	0	250	69.1	69.1	0.0	0.0	73.6	1.4	2.3	0.0	0.0	2.5	0.0	-0.0	-10.7	-10.7
338	527708.09	5511852.14	394.19	0	500	73.5	73.5	0.0	0.0	73.6	2.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-6.4	-6.4
339	527708.09	5511852.14	394.19	0	1000	76.7	76.7	0.0	0.0	73.6	5.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-5.5	-5.5
340	527708.09	5511852.14	394.19	0	2000	76.9	76.9	0.0	0.0	73.6	13.1	-1.1	0.0	0.0	4.8	0.0	-0.0	-13.5	-13.5
341	527708.09	5511852.14	394.19	0	4000	69.7	69.7	0.0	0.0	73.6	44.4	-1.1	0.0	0.0	4.8	0.0	-0.0	-52.0	-52.0
342	527708.09	5511852.14	394.19	0	8000	62.6	62.6	0.0	0.0	73.6	158.4	-1.1	0.0	0.0	4.8	0.0	-0.0	-173.1	-173.1
343	528116.46	5511948.65	398.89	0	32	31.5	31.5	0.0	0.0	71.2	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-34.5	-34.5
344	528116.46	5511948.65	398.89	0	63	40.7	40.7	0.0	0.0	71.2	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-25.4	-25.4
345	528116.46	5511948.65	398.89	0	125	56.8	56.8	0.0	0.0	71.2	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-20.1	-20.1
346	528116.46	5511948.65	398.89	0	250	66.3	66.3	0.0	0.0	71.2	1.1	2.3	0.0	0.0	0.0	0.0	-0.0	-8.4	-8.4
347	528116.46	5511948.65	398.89	0	500	70.7	70.7	0.0	0.0	71.2	2.0	-1.0	0.0	0.0	0.0	0.0	-0.0	-1.5	-1.5
348	528116.46	5511948.65	398.89	0	1000	73.9	73.9	0.0	0.0	71.2	3.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-0.0	-0.0
349	528116.46	5511948.65	398.89	0	2000	74.1	74.1	0.0	0.0	71.2	9.9	-1.1	0.0	0.0	0.0	0.0	-0.0	-6.0	-6.0
350	528116.46	5511948.65	398.89	0	4000	66.9	66.9	0.0	0.0	71.2	33.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-36.9	-36.9
351	528116.46	5511948.65	398.89	0	8000	59.8	59.8	0.0	0.0	71.2	120.0	-1.1	0.0	0.0	0.0	0.0	-0.0	-130.4	-130.4
352	527591.34	5511763.66	395.15	0	32	34.4	34.4	0.0	0.0	74.2	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-39.1	-39.1
353	527591.34	5511763.66	395.15	0	63	43.6	43.6	0.0	0.0	74.2	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-30.0	-30.0
354	527591.34	5511763.66	395.15	0	125	59.7	59.7	0.0	0.0	74.2	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-20.4	-20.4
355	527591.34	5511763.66	395.15	0	250	69.2	69.2	0.0	0.0	74.2	1.5	2.3	0.0	0.0	2.5	0.0	-0.0	-11.3	-11.3
356	527591.34	5511763.66	395.15	0	500	73.6	73.6	0.0	0.0	74.2	2.8	-1.1	0.0	0.0	4.8	0.0	-0.0	-7.1	-7.1
357	527591.34	5511763.66	395.15	0	1000	76.8	76.8	0.0	0.0	74.2	5.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-6.3	-6.3
358	527591.34	5511763.66	395.15	0	2000	77.0	77.0	0.0	0.0	74.2	13.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-14.8	-14.8
359	527591.34	5511763.66	395.15	0	4000	69.8	69.8	0.0	0.0	74.2	47.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-55.3	-55.3
360	527591.34	5511763.66	395.15	0	8000	62.7	62.7	0.0	0.0	74.2	168.4	-1.1	0.0	0.0	4.8	0.0	-0.0	-183.6	-183.6
361	527565.49	5511754.61	395.44	0	32	34.5	34.5	0.0	0.0	74.3	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-39.1	-39.1
362	527565.49	5511754.61	395.44	0	63	43.7	43.7	0.0	0.0	74.3	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-30.1	-30.1
363	527565.49	5511754.61	395.44	0	125	59.8	59.8	0.0	0.0	74.3	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-20.4	-20.4
364	527565.49	5511754.61	395.44	0	250	69.3	69.3	0.0	0.0	74.3	1.5	2.3	0.0	0.0	2.5	0.0	-0.0	-11.3	-11.3
365	527565.49	5511754.61	395.44	0	500	73.7	73.7	0.0	0.0	74.3	2.8	-1.1	0.0	0.0	4.8	0.0	-0.0	-7.1	-7.1
366	527565.49	5511754.61	395.44	0	1000	76.9	76.9	0.0	0.0	74.3	5.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-6.4	-6.4
367	527565.49	5511754.61	395.44	0	2000	77.1	77.1	0.0	0.0	74.3	14.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-15.0	-15.0
368	527565.49	5511754.61	395.44	0	4000	69.9	69.9	0.0	0.0	74.3	48.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-56.0	-56.0
369	527565.49	5511754.61	395.44	0	8000	62.8	62.8	0.0	0.0	74.3	171.1	-1.1	0.0	0.0	4.8	0.0	-0.0	-186.3	-186.3
370	527505.86	5511763.90	396.28	0	32	34.4	34.4	0.0	0.0	74.7	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-39.5	-39.5
371	527505.86	5511763.90	396.28	0	63	43.6	43.6	0.0	0.0	74.7	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-30.4	-30.4
372	527505.86	5511763.90	396.28	0	125	59.7	59.7	0.0	0.0	74.7	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-20.9	-20.9
373	527505.86	5511763.90	396.28	0	250	69.2	69.2	0.0	0.0	74.7	1.6	2.3	0.0	0.0	2.5	0.0	-0.0	-11.8	-11.8
374	527505.86	5511763.90	396.28	0	500	73.6	73.6	0.0	0.0	74.7	2.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-7.7	-7.7
375	527505.86	5511763.90	396.28	0	1000	76.8	76.8	0.0	0.0	74.7	5.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-7.1	-7.1
376	527505.86	5511763.90	396.28	0	2000	77.0	77.0	0.0	0.0	74.7	14.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-16.0	-16.0
377	527505.86	5511763.90	396.28	0	4000	69.8	69.8	0.0	0.0	74.7	49.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-58.4	-58.4
378	527505.86	5511763.90	396.28	0	8000	62.7	62.7	0.0	0.0	74.7	178.1	-1.1	0.0	0.0	4.8	0.0	-0.0	-193.7	-193.7

Sample Calculation at facade of NR03

Line Source, ISO 9613, Name: "Haul Truck #2", ID: "Htruck2_o"																	
Nr.	X	Y	Z	RefL	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar	Cmet	

Line Source, ISO 9613, Name: "Haul Truck #2", ID: "Htruck2_o"																			
Nr.	X	Y	Z	RefI.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agf	Afof	Afous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	dB	dB	dB	dB	dB	dB	dB	dB	dB	dB	dB(A)	dB(A)
442	527743.34	5511872.87	397.06	0	32	31.6	31.6	0.0	0.0	73.5	0.0	-5.5	0.0	0.0	4.8	0.0	-0.0	-41.2	-41.2
443	527743.34	5511872.87	397.06	0	63	40.8	40.8	0.0	0.0	73.5	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-32.1	-32.1
444	527743.34	5511872.87	397.06	0	125	56.9	56.9	0.0	0.0	73.5	0.6	5.3	0.0	0.0	4.8	0.0	-0.0	-22.4	-22.4
445	527743.34	5511872.87	397.06	0	250	66.4	66.4	0.0	0.0	73.5	1.4	2.3	0.0	0.0	2.5	0.0	-0.0	-13.2	-13.2
446	527743.34	5511872.87	397.06	0	500	70.8	70.8	0.0	0.0	73.5	2.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-8.9	-8.9
447	527743.34	5511872.87	397.06	0	1000	74.0	74.0	0.0	0.0	73.5	4.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-8.0	-8.0
448	527743.34	5511872.87	397.06	0	2000	74.2	74.2	0.0	0.0	73.5	12.8	-1.1	0.0	0.0	4.8	0.0	-0.0	-15.8	-15.8
449	527743.34	5511872.87	397.06	0	4000	67.0	67.0	0.0	0.0	73.5	43.5	-1.1	0.0	0.0	4.8	0.0	-0.0	-53.7	-53.7
450	527743.34	5511872.87	397.06	0	8000	59.9	59.9	0.0	0.0	73.5	155.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-172.6	-172.6
451	527498.79	5511810.11	395.82	0	32	32.5	32.5	0.0	0.0	74.8	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-41.6	-41.6
452	527498.79	5511810.11	395.82	0	63	41.7	41.7	0.0	0.0	74.8	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-32.5	-32.5
453	527498.79	5511810.11	395.82	0	125	57.8	57.8	0.0	0.0	74.8	0.6	5.3	0.0	0.0	4.8	0.0	-0.0	-22.9	-22.9
454	527498.79	5511810.11	395.82	0	250	67.3	67.3	0.0	0.0	74.8	1.6	2.3	0.0	0.0	2.5	0.0	-0.0	-13.9	-13.9
455	527498.79	5511810.11	395.82	0	500	71.7	71.7	0.0	0.0	74.8	3.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-9.8	-9.8
456	527498.79	5511810.11	395.82	0	1000	74.9	74.9	0.0	0.0	74.8	5.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-9.2	-9.2
457	527498.79	5511810.11	395.82	0	2000	75.1	75.1	0.0	0.0	74.8	14.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-18.3	-18.3
458	527498.79	5511810.11	395.82	0	4000	67.9	67.9	0.0	0.0	74.8	50.5	-1.1	0.0	0.0	4.8	0.0	-0.0	-61.1	-61.1
459	527498.79	5511810.11	395.82	0	8000	60.8	60.8	0.0	0.0	74.8	180.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-197.9	-197.9
460	528418.24	5511959.09	398.14	0	32	26.4	26.4	0.0	0.0	69.0	0.0	-5.1	0.0	0.0	0.0	0.0	-0.0	-37.6	-37.6
461	528418.24	5511959.09	398.14	0	63	35.6	35.6	0.0	0.0	69.0	0.1	-5.1	0.0	0.0	0.0	0.0	-0.0	-28.4	-28.4
462	528418.24	5511959.09	398.14	0	125	51.7	51.7	0.0	0.0	69.0	0.3	5.0	0.0	0.0	0.0	0.0	-0.0	-22.7	-22.7
463	528418.24	5511959.09	398.14	0	250	61.2	61.2	0.0	0.0	69.0	0.8	2.4	0.0	0.0	0.0	0.0	-0.0	-11.1	-11.1
464	528418.24	5511959.09	398.14	0	500	65.6	65.6	0.0	0.0	69.0	1.5	-1.0	0.0	0.0	0.0	0.0	-0.0	-4.0	-4.0
465	528418.24	5511959.09	398.14	0	1000	68.8	68.8	0.0	0.0	69.0	2.9	-1.0	0.0	0.0	0.0	0.0	-0.0	-2.1	-2.1
466	528418.24	5511959.09	398.14	0	2000	69.0	69.0	0.0	0.0	69.0	7.7	-1.0	0.0	0.0	0.0	0.0	-0.0	-6.7	-6.7
467	528418.24	5511959.09	398.14	0	4000	61.8	61.8	0.0	0.0	69.0	26.1	-1.0	0.0	0.0	0.0	0.0	-0.0	-32.3	-32.3
468	528418.24	5511959.09	398.14	0	8000	54.7	54.7	0.0	0.0	69.0	93.0	-1.0	0.0	0.0	0.0	0.0	-0.0	-106.3	-106.3
469	527993.06	5511875.66	401.38	0	32	28.8	28.8	0.0	0.0	71.8	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-37.7	-37.7
470	527993.06	5511875.66	401.38	0	63	38.0	38.0	0.0	0.0	71.8	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-28.6	-28.6
471	527993.06	5511875.66	401.38	0	125	54.1	54.1	0.0	0.0	71.8	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-23.5	-23.5
472	527993.06	5511875.66	401.38	0	250	63.6	63.6	0.0	0.0	71.8	1.2	2.3	0.0	0.0	0.0	0.0	-0.0	-11.7	-11.7
473	527993.06	5511875.66	401.38	0	500	68.0	68.0	0.0	0.0	71.8	2.1	-1.0	0.0	0.0	0.0	0.0	-0.0	-4.9	-4.9
474	527993.06	5511875.66	401.38	0	1000	71.2	71.2	0.0	0.0	71.8	4.0	-1.1	0.0	0.0	0.0	0.0	-0.0	-3.6	-3.6
475	527993.06	5511875.66	401.38	0	2000	71.4	71.4	0.0	0.0	71.8	10.6	-1.1	0.0	0.0	0.0	0.0	-0.0	-10.0	-10.0
476	527993.06	5511875.66	401.38	0	4000	64.2	64.2	0.0	0.0	71.8	36.0	-1.1	0.0	0.0	0.0	0.0	-0.0	-42.6	-42.6
477	527993.06	5511875.66	401.38	0	8000	57.1	57.1	0.0	0.0	71.8	128.6	-1.1	0.0	0.0	0.0	0.0	-0.0	-142.3	-142.3
478	528354.08	5512040.44	399.23	0	32	26.5	26.5	0.0	0.0	70.1	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-38.4	-38.4
479	528354.08	5512040.44	399.23	0	63	35.7	35.7	0.0	0.0	70.1	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-29.3	-29.3
480	528354.08	5512040.44	399.23	0	125	51.8	51.8	0.0	0.0	70.1	0.4	5.1	0.0	0.0	0.0	0.0	-0.0	-23.8	-23.8
481	528354.08	5512040.44	399.23	0	250	61.3	61.3	0.0	0.0	70.1	0.9	2.4	0.0	0.0	0.0	0.0	-0.0	-12.1	-12.1
482	528354.08	5512040.44	399.23	0	500	65.7	65.7	0.0	0.0	70.1	1.7	-1.0	0.0	0.0	0.0	0.0	-0.0	-5.1	-5.1
483	528354.08	5512040.44	399.23	0	1000	68.9	68.9	0.0	0.0	70.1	3.3	-1.0	0.0	0.0	0.0	0.0	-0.0	-3.4	-3.4
484	528354.08	5512040.44	399.23	0	2000	69.1	69.1	0.0	0.0	70.1	8.7	-1.0	0.0	0.0	0.0	0.0	-0.0	-8.7	-8.7
485	528354.08	5512040.44	399.23	0	4000	61.9	61.9	0.0	0.0	70.1	29.4	-1.0	0.0	0.0	0.0	0.0	-0.0	-36.6	-36.6
486	528354.08	5512040.44	399.23	0	8000	54.8	54.8	0.0	0.0	70.1	105.0	-1.0	0.0	0.0	0.0	0.0	-0.0	-119.2	-119.2
487	528081.15	5511949.75	398.55	0	32	27.3	27.3	0.0	0.0	71.5	0.0	-5.3	0.0	0.0	4.8	0.0	-0.0	-43.7	-43.7
488	528081.15	5511949.75	398.55	0	63	36.5	36.5	0.0	0.0	71.5	0.1	-5.3	0.0	0.0	4.8	0.0	-0.0	-34.6	-34.6
489	528081.15	5511949.75	398.55	0	125	52.6	52.6	0.0	0.0	71.5	0.4	5.3	0.0	0.0	0.0	0.0	-0.0	-24.6	-24.6
490	528081.15	5511949.75	398.55	0	250	62.1	62.1	0.0	0.0	71.5	1.1	2.3	0.0	0.0	2.4	0.0	-0.0	-15.3	-15.3
491	528081.15	5511949.75	398.55	0	500	66.5	66.5	0.0	0.0	71.5	2.0	-1.0	0.0	0.0	4.8	0.0	-0.0	-10.8	-10.8
492	528081.15	5511949.75	398.55	0	1000	69.7	69.7	0.0	0.0	71.5	3.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-9.4	-9.4
493	528081.15	5511949.75	398.55	0	2000	69.9	69.9	0.0	0.0	71.5	10.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-15.5	-15.5
494	528081.15	5511949.75	398.55	0	4000	62.7	62.7	0.0	0.0	71.5	34.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-47.2	-47.2
495	528081.15	5511949.75	398.55	0	8000	55.6	55.6	0.0	0.0	71.5	123.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-143.2	-143.2
496	527646.15	5511800.21	394.32	0	32	29.6	29.6	0.0	0.0	73.9	0.0	-5.5	0.0	0.0	4.8	0.0	-0.0	-43.7	-43.7
497	527646.15	5511800.21	394.32	0	63	38.8	38.8	0.0	0.0	73.9	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-34.6	-34.6
498	527646.15	5511800.21	394.32	0	125	54.9	54.9	0.0	0.0	73.9	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-24.9	-24.9
499	527646.15	5511800.21	394.32	0	250	64.4	64.4	0.0	0.0	73.9	1.5	2.3	0.0	0.0	2.5	0.0	-0.0	-15.8	-15.8
500	527646.15	5511800.21	394.32	0	500	68.8	68.8	0.0	0.0	73.9	2.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-11.5	-11.5
501	527646.15	5511800.21	394.32	0	1000	72.0	72.0	0.0	0.0	73.9	5.1	-1.1	0.0	0.0	4.8	0.0	-0.0	-10.7	-10.7
502	527646.15	5511800.21	394.32	0	2000	72.2	72.2	0.0	0.0	73.9	13.5	-1.1	0.0	0.0	4.8	0.0	-0.0	-18.9	-18.9
503	527646.15	5511800.21	394.32	0	4000	65.0	65.0	0.0	0.0	73.9	45.8	-1.1	0.0	0.0	4.8	0.0	-0.0	-58.4	-58.4
504	527646.15	5511800.21	394.32	0	8000	57.9	57.9	0.0	0.0	73.9	163.4	-1.1	0.0	0.0	4.8	0.0	-0.0	-183.1	-183.1

Sample Calculation at facade of NR03

Line Source, ISO 9613, Name: "Haul Truck #2", ID: "Htruck2_o"																			
Nr.	X	Y	Z	RefI.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agf	Afof	Afous	A				

Line Source, ISO 9613, Name: "Haul Truck #2", ID: "Htruck2_o"																			
Nr.	X	Y	Z	Refl.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)
568	527627.29	5511778.16	394.21	0	32	26.1	26.1	0.0	74.0	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-47.2	-47.2	-47.2
569	527627.29	5511778.16	394.21	0	63	35.3	35.3	0.0	74.0	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-38.1	-38.1	-38.1
570	527627.29	5511778.16	394.21	0	125	51.4	51.4	0.0	74.0	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-28.4	-28.4	-28.4
571	527627.29	5511778.16	394.21	0	250	60.9	60.9	0.0	74.0	1.5	2.3	0.0	0.0	2.5	0.0	-0.0	-19.3	-19.3	-19.3
572	527627.29	5511778.16	394.21	0	500	65.3	65.3	0.0	74.0	2.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-15.1	-15.1	-15.1
573	527627.29	5511778.16	394.21	0	1000	68.5	68.5	0.0	74.0	5.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-14.3	-14.3	-14.3
574	527627.29	5511778.16	394.21	0	2000	68.7	68.7	0.0	74.0	13.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-22.6	-22.6	-22.6
575	527627.29	5511778.16	394.21	0	4000	61.5	61.5	0.0	74.0	46.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-62.3	-62.3	-62.3
576	527627.29	5511778.16	394.21	0	8000	54.4	54.4	0.0	74.0	164.8	-1.1	0.0	0.0	4.8	0.0	-0.0	-188.0	-188.0	-188.0
577	527503.87	5511816.58	395.67	0	32	26.8	26.8	0.0	74.8	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-47.3	-47.3	-47.3
578	527503.87	5511816.58	395.67	0	63	36.0	36.0	0.0	74.8	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-38.2	-38.2	-38.2
579	527503.87	5511816.58	395.67	0	125	52.1	52.1	0.0	74.8	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-28.6	-28.6	-28.6
580	527503.87	5511816.58	395.67	0	250	61.6	61.6	0.0	74.8	1.6	2.3	0.0	0.0	2.5	0.0	-0.0	-19.6	-19.6	-19.6
581	527503.87	5511816.58	395.67	0	500	66.0	66.0	0.0	74.8	3.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-15.5	-15.5	-15.5
582	527503.87	5511816.58	395.67	0	1000	69.2	69.2	0.0	74.8	5.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-14.9	-14.9	-14.9
583	527503.87	5511816.58	395.67	0	2000	69.4	69.4	0.0	74.8	14.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-23.9	-23.9	-23.9
584	527503.87	5511816.58	395.67	0	4000	62.2	62.2	0.0	74.8	50.4	-1.1	0.0	0.0	4.8	0.0	-0.0	-66.7	-66.7	-66.7
585	527503.87	5511816.58	395.67	0	8000	55.1	55.1	0.0	74.8	179.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-203.3	-203.3	-203.3
586	527629.06	5511780.29	394.22	0	32	25.4	25.4	0.0	74.0	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-47.9	-47.9	-47.9
587	527629.06	5511780.29	394.22	0	63	34.6	34.6	0.0	74.0	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-38.8	-38.8	-38.8
588	527629.06	5511780.29	394.22	0	125	50.7	50.7	0.0	74.0	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-29.2	-29.2	-29.2
589	527629.06	5511780.29	394.22	0	250	60.2	60.2	0.0	74.0	1.5	2.3	0.0	0.0	2.5	0.0	-0.0	-20.0	-20.0	-20.0
590	527629.06	5511780.29	394.22	0	500	64.6	64.6	0.0	74.0	2.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-15.8	-15.8	-15.8
591	527629.06	5511780.29	394.22	0	1000	67.8	67.8	0.0	74.0	5.1	-1.1	0.0	0.0	4.8	0.0	-0.0	-15.0	-15.0	-15.0
592	527629.06	5511780.29	394.22	0	2000	68.0	68.0	0.0	74.0	13.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-23.3	-23.3	-23.3
593	527629.06	5511780.29	394.22	0	4000	60.8	60.8	0.0	74.0	46.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-63.0	-63.0	-63.0
594	527629.06	5511780.29	394.22	0	8000	53.7	53.7	0.0	74.0	164.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-188.6	-188.6	-188.6
595	527926.30	5511855.09	402.72	0	32	23.5	23.5	0.0	72.2	0.0	-5.4	0.0	0.0	0.0	0.0	-0.0	-43.4	-43.4	-43.4
596	527926.30	5511855.09	402.72	0	63	32.7	32.7	0.0	72.2	0.1	-5.4	0.0	0.0	0.0	0.0	-0.0	-34.3	-34.3	-34.3
597	527926.30	5511855.09	402.72	0	125	48.8	48.8	0.0	72.2	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-29.2	-29.2	-29.2
598	527926.30	5511855.09	402.72	0	250	58.3	58.3	0.0	72.2	1.2	2.3	0.0	0.0	0.0	0.0	-0.0	-17.5	-17.5	-17.5
599	527926.30	5511855.09	402.72	0	500	62.7	62.7	0.0	72.2	2.2	-1.0	0.0	0.0	0.0	0.0	-0.0	-10.8	-10.8	-10.8
600	527926.30	5511855.09	402.72	0	1000	65.9	65.9	0.0	72.2	4.2	-1.1	0.0	0.0	0.0	0.0	-0.0	-9.5	-9.5	-9.5
601	527926.30	5511855.09	402.72	0	2000	66.1	66.1	0.0	72.2	11.1	-1.1	0.0	0.0	0.0	0.0	-0.0	-16.2	-16.2	-16.2
602	527926.30	5511855.09	402.72	0	4000	58.9	58.9	0.0	72.2	37.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-50.1	-50.1	-50.1
603	527926.30	5511855.09	402.72	0	8000	51.8	51.8	0.0	72.2	134.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-154.1	-154.1	-154.1
604	528121.71	5511946.29	398.94	0	32	22.3	22.3	0.0	71.2	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-43.6	-43.6	-43.6
605	528121.71	5511946.29	398.94	0	63	31.5	31.5	0.0	71.2	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-34.5	-34.5	-34.5
606	528121.71	5511946.29	398.94	0	125	47.6	47.6	0.0	71.2	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-29.2	-29.2	-29.2
607	528121.71	5511946.29	398.94	0	250	57.1	57.1	0.0	71.2	1.1	2.3	0.0	0.0	0.0	0.0	-0.0	-17.4	-17.4	-17.4
608	528121.71	5511946.29	398.94	0	500	61.5	61.5	0.0	71.2	2.0	-1.0	0.0	0.0	0.0	0.0	-0.0	-10.6	-10.6	-10.6
609	528121.71	5511946.29	398.94	0	1000	64.7	64.7	0.0	71.2	3.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-9.1	-9.1	-9.1
610	528121.71	5511946.29	398.94	0	2000	64.9	64.9	0.0	71.2	9.9	-1.1	0.0	0.0	0.0	0.0	-0.0	-15.1	-15.1	-15.1
611	528121.71	5511946.29	398.94	0	4000	57.7	57.7	0.0	71.2	33.5	-1.1	0.0	0.0	0.0	0.0	-0.0	-45.8	-45.8	-45.8
612	528121.71	5511946.29	398.94	0	8000	50.6	50.6	0.0	71.2	119.4	-1.1	0.0	0.0	0.0	0.0	-0.0	-138.9	-138.9	-138.9
613	527625.68	5511776.23	394.23	0	32	24.4	24.4	0.0	74.0	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-48.9	-48.9	-48.9
614	527625.68	5511776.23	394.23	0	63	33.6	33.6	0.0	74.0	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-39.8	-39.8	-39.8
615	527625.68	5511776.23	394.23	0	125	49.7	49.7	0.0	74.0	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-30.2	-30.2	-30.2
616	527625.68	5511776.23	394.23	0	250	59.2	59.2	0.0	74.0	1.5	2.3	0.0	0.0	2.5	0.0	-0.0	-21.0	-21.0	-21.0
617	527625.68	5511776.23	394.23	0	500	63.6	63.6	0.0	74.0	2.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-16.8	-16.8	-16.8
618	527625.68	5511776.23	394.23	0	1000	66.8	66.8	0.0	74.0	5.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-16.0	-16.0	-16.0
619	527625.68	5511776.23	394.23	0	2000	67.0	67.0	0.0	74.0	13.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-24.3	-24.3	-24.3
620	527625.68	5511776.23	394.23	0	4000	59.8	59.8	0.0	74.0	46.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-64.1	-64.1	-64.1
621	527625.68	5511776.23	394.23	0	8000	52.7	52.7	0.0	74.0	164.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-189.9	-189.9	-189.9
622	527927.64	5511855.01	402.71	0	32	21.8	21.8	0.0	72.2	0.0	-5.4	0.0	0.0	0.0	0.0	-0.0	-45.0	-45.0	-45.0
623	527927.64	5511855.01	402.71	0	63	31.0	31.0	0.0	72.2	0.1	-5.4	0.0	0.0	0.0	0.0	-0.0	-35.9	-35.9	-35.9
624	527927.64	5511855.01	402.71	0	125	47.1	47.1	0.0	72.2	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-30.8	-30.8	-30.8
625	527927.64	5511855.01	402.71	0	250	56.6	56.6	0.0	72.2	1.2	2.3	0.0	0.0	0.0	0.0	-0.0	-19.1	-19.1	-19.1
626	527927.64	5511855.01	402.71	0	500	61.0	61.0	0.0	72.2	2.2	-1.0	0.0	0.0	0.0	0.0	-0.0	-12.4	-12.4	-12.4
627	527927.64	5511855.01	402.71	0	1000	64.2	64.2	0.0	72.2	4.2	-1.1	0.0	0.0	0.0	0.0	-0.0	-11.1	-11.1	-11.1
628	527927.64	5511855.01	402.71	0	2000	64.4	64.4	0.0	72.2	11.1	-1.1	0.0	0.0	0.0	0.0	-0.0	-17.8	-17.8	-17.8
629	527927.64	5511855.01	402.71	0	4000	57.2	57.2	0.0	72.2	37.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-51.6	-51.6	-51.6
630	527927.64	5511855.01	402.71	0	8000	50.1	50.1	0.0	72.2	134.6	-1.1	0.0	0.0	0.0	0.0	-0.0	-155.6	-155.6	-155.6

Sample Calculation at facade of NR03

Line Source, ISO 9613, Name: "Haul Truck #2", ID: "Htruck2_o"																
Nr.	X	Y	Z	Refl.												

Line Source, ISO 9613, Name: "Haul Truck #3", ID: "Htruck3_o"																			
Nr.	X	Y	Z	Ref1	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afo1	Afous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	dB(A)	dB(A)
24	528265.42	5511968.71	399.35	0	1000	87.8	87.8	0.0	0.0	70.2	3.3	-1.0	0.0	0.0	0.0	0.0	-0.0	15.3	15.3
25	528265.42	5511968.71	399.35	0	2000	88.0	88.0	0.0	0.0	70.2	8.9	-1.0	0.0	0.0	0.0	0.0	-0.0	10.0	10.0
26	528265.42	5511968.71	399.35	0	4000	80.8	80.8	0.0	0.0	70.2	30.0	-1.0	0.0	0.0	0.0	0.0	-0.0	-18.4	-18.4
27	528265.42	5511968.71	399.35	0	8000	73.7	73.7	0.0	0.0	70.2	107.1	-1.0	0.0	0.0	0.0	0.0	-0.0	-102.6	-102.6
28	528500.14	5512172.04	399.39	0	32	45.4	45.4	0.0	0.0	70.2	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-19.6	-19.6
29	528500.14	5512172.04	399.39	0	63	54.6	54.6	0.0	0.0	70.2	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-10.5	-10.5
30	528500.14	5512172.04	399.39	0	125	70.7	70.7	0.0	0.0	70.2	0.4	5.1	0.0	0.0	0.0	0.0	-0.0	-5.0	-5.0
31	528500.14	5512172.04	399.39	0	250	80.2	80.2	0.0	0.0	70.2	1.0	2.3	0.0	0.0	0.0	0.0	-0.0	6.7	6.7
32	528500.14	5512172.04	399.39	0	500	84.6	84.6	0.0	0.0	70.2	1.8	-1.0	0.0	0.0	0.0	0.0	-0.0	13.6	13.6
33	528500.14	5512172.04	399.39	0	1000	87.8	87.8	0.0	0.0	70.2	3.3	-1.0	0.0	0.0	0.0	0.0	-0.0	15.3	15.3
34	528500.14	5512172.04	399.39	0	2000	88.0	88.0	0.0	0.0	70.2	8.8	-1.0	0.0	0.0	0.0	0.0	-0.0	10.0	10.0
35	528500.14	5512172.04	399.39	0	4000	80.8	80.8	0.0	0.0	70.2	29.8	-1.0	0.0	0.0	0.0	0.0	-0.0	-18.2	-18.2
36	528500.14	5512172.04	399.39	0	8000	73.7	73.7	0.0	0.0	70.2	106.4	-1.0	0.0	0.0	0.0	0.0	-0.0	-101.8	-101.8
37	528187.56	5511949.94	399.40	0	32	45.6	45.6	0.0	0.0	70.7	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-19.9	-19.9
38	528187.56	5511949.94	399.40	0	63	54.8	54.8	0.0	0.0	70.7	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-10.8	-10.8
39	528187.56	5511949.94	399.40	0	125	70.9	70.9	0.0	0.0	70.7	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-5.4	-5.4
40	528187.56	5511949.94	399.40	0	250	80.4	80.4	0.0	0.0	70.7	1.0	2.3	0.0	0.0	0.0	0.0	-0.0	6.3	6.3
41	528187.56	5511949.94	399.40	0	500	84.8	84.8	0.0	0.0	70.7	1.9	-1.0	0.0	0.0	0.0	0.0	-0.0	13.2	13.2
42	528187.56	5511949.94	399.40	0	1000	88.0	88.0	0.0	0.0	70.7	3.5	-1.1	0.0	0.0	0.0	0.0	-0.0	14.8	14.8
43	528187.56	5511949.94	399.40	0	2000	88.2	88.2	0.0	0.0	70.7	9.4	-1.1	0.0	0.0	0.0	0.0	-0.0	9.2	9.2
44	528187.56	5511949.94	399.40	0	4000	81.0	81.0	0.0	0.0	70.7	31.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-20.4	-20.4
45	528187.56	5511949.94	399.40	0	8000	73.9	73.9	0.0	0.0	70.7	113.2	-1.1	0.0	0.0	0.0	0.0	-0.0	-109.0	-109.0
46	528515.01	5512205.74	399.73	0	32	44.9	44.9	0.0	0.0	70.4	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-20.3	-20.3
47	528515.01	5512205.74	399.73	0	63	54.1	54.1	0.0	0.0	70.4	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-11.1	-11.1
48	528515.01	5512205.74	399.73	0	125	70.2	70.2	0.0	0.0	70.4	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-5.7	-5.7
49	528515.01	5512205.74	399.73	0	250	79.7	79.7	0.0	0.0	70.4	1.0	2.3	0.0	0.0	0.0	0.0	-0.0	6.0	6.0
50	528515.01	5512205.74	399.73	0	500	84.1	84.1	0.0	0.0	70.4	1.8	-1.0	0.0	0.0	0.0	0.0	-0.0	13.0	13.0
51	528515.01	5512205.74	399.73	0	1000	87.3	87.3	0.0	0.0	70.4	3.4	-1.1	0.0	0.0	0.0	0.0	-0.0	14.6	14.6
52	528515.01	5512205.74	399.73	0	2000	87.5	87.5	0.0	0.0	70.4	9.0	-1.1	0.0	0.0	0.0	0.0	-0.0	9.2	9.2
53	528515.01	5512205.74	399.73	0	4000	80.3	80.3	0.0	0.0	70.4	30.5	-1.1	0.0	0.0	0.0	0.0	-0.0	-19.5	-19.5
54	528515.01	5512205.74	399.73	0	8000	73.2	73.2	0.0	0.0	70.4	108.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-105.0	-105.0
55	528036.06	5512221.13	400.35	0	32	47.2	47.2	0.0	0.0	73.0	0.0	-5.4	0.0	0.0	0.0	0.0	-0.0	-20.4	-20.4
56	528036.06	5512221.13	400.35	0	63	56.4	56.4	0.0	0.0	73.0	0.2	-5.4	0.0	0.0	0.0	0.0	-0.0	-11.3	-11.3
57	528036.06	5512221.13	400.35	0	125	72.5	72.5	0.0	0.0	73.0	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-6.3	-6.3
58	528036.06	5512221.13	400.35	0	250	82.0	82.0	0.0	0.0	73.0	1.3	2.3	0.0	0.0	0.0	0.0	-0.0	5.4	5.4
59	528036.06	5512221.13	400.35	0	500	86.4	86.4	0.0	0.0	73.0	2.4	-1.0	0.0	0.0	0.0	0.0	-0.0	12.0	12.0
60	528036.06	5512221.13	400.35	0	1000	89.6	89.6	0.0	0.0	73.0	4.6	-1.1	0.0	0.0	0.0	0.0	-0.0	13.1	13.1
61	528036.06	5512221.13	400.35	0	2000	89.8	89.8	0.0	0.0	73.0	12.1	-1.1	0.0	0.0	0.0	0.0	-0.0	5.8	5.8
62	528036.06	5512221.13	400.35	0	4000	82.6	82.6	0.0	0.0	73.0	41.1	-1.1	0.0	0.0	0.0	0.0	-0.0	-30.4	-30.4
63	528036.06	5512221.13	400.35	0	8000	75.5	75.5	0.0	0.0	73.0	146.6	-1.1	0.0	0.0	0.0	0.0	-0.0	-143.0	-143.0
64	528445.85	5512144.59	398.43	0	32	44.3	44.3	0.0	0.0	70.3	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-20.8	-20.8
65	528445.85	5512144.59	398.43	0	63	53.5	53.5	0.0	0.0	70.3	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-11.7	-11.7
66	528445.85	5512144.59	398.43	0	125	69.6	69.6	0.0	0.0	70.3	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-6.2	-6.2
67	528445.85	5512144.59	398.43	0	250	79.1	79.1	0.0	0.0	70.3	1.0	2.3	0.0	0.0	0.0	0.0	-0.0	5.5	5.5
68	528445.85	5512144.59	398.43	0	500	83.5	83.5	0.0	0.0	70.3	1.8	-1.0	0.0	0.0	0.0	0.0	-0.0	12.4	12.4
69	528445.85	5512144.59	398.43	0	1000	86.7	86.7	0.0	0.0	70.3	3.4	-1.0	0.0	0.0	0.0	0.0	-0.0	14.1	14.1
70	528445.85	5512144.59	398.43	0	2000	86.9	86.9	0.0	0.0	70.3	8.9	-1.0	0.0	0.0	0.0	0.0	-0.0	8.8	8.8
71	528445.85	5512144.59	398.43	0	4000	79.7	79.7	0.0	0.0	70.3	30.1	-1.0	0.0	0.0	0.0	0.0	-0.0	-19.6	-19.6
72	528445.85	5512144.59	398.43	0	8000	72.6	72.6	0.0	0.0	70.3	107.3	-1.0	0.0	0.0	0.0	0.0	-0.0	-104.0	-104.0
73	528303.87	5511988.43	399.36	0	32	43.9	43.9	0.0	0.0	70.1	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-21.0	-21.0
74	528303.87	5511988.43	399.36	0	63	53.1	53.1	0.0	0.0	70.1	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-11.9	-11.9
75	528303.87	5511988.43	399.36	0	125	69.2	69.2	0.0	0.0	70.1	0.4	5.1	0.0	0.0	0.0	0.0	-0.0	-6.4	-6.4
76	528303.87	5511988.43	399.36	0	250	78.7	78.7	0.0	0.0	70.1	0.9	2.4	0.0	0.0	0.0	0.0	-0.0	5.3	5.3
77	528303.87	5511988.43	399.36	0	500	83.1	83.1	0.0	0.0	70.1	1.7	-1.0	0.0	0.0	0.0	0.0	-0.0	12.3	12.3
78	528303.87	5511988.43	399.36	0	1000	86.3	86.3	0.0	0.0	70.1	3.3	-1.0	0.0	0.0	0.0	0.0	-0.0	14.0	14.0
79	528303.87	5511988.43	399.36	0	2000	86.5	86.5	0.0	0.0	70.1	8.7	-1.0	0.0	0.0	0.0	0.0	-0.0	8.8	8.8
80	528303.87	5511988.43	399.36	0	4000	79.3	79.3	0.0	0.0	70.1	29.5	-1.0	0.0	0.0	0.0	0.0	-0.0	-19.2	-19.2
81	528303.87	5511988.43	399.36	0	8000	72.2	72.2	0.0	0.0	70.1	105.1	-1.0	0.0	0.0	0.0	0.0	-0.0	-102.0	-102.0
82	528141.64	5511949.36	399.14	0	32	44.2	44.2	0.0	0.0	71.0	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-21.6	-21.6
83	528141.64	5511949.36	399.14	0	63	53.4	53.4	0.0	0.0	71.0	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-12.5	-12.5
84	528141.64	5511949.36	399.14	0	125	69.5	69.5	0.0	0.0	71.0	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-7.1	-7.1
85	528141.64	5511949.36	399.14	0	250	79.0	79.0	0.0	0.0	71.0	1.1	2.3	0.0	0.0	0.0	0.0	-0.0	4.6	4.6
86	528141.64	5511949.36	399.14	0	500	83.4	83.4	0.0	0.0	71.0	1.9	-1.0	0.0	0.0	0.0	0.0	-0.0	11.5	11.5

Sample Calculation at facade of NR03

Line Source, ISO 9613, Name: "Haul Truck #3", ID: "Htruck3_o"																			
Nr.	X	Y	Z	Ref1	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afo1	Afous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)														

Line Source, ISO 9613, Name: "Haul Truck #3", ID: "Htruck3_o"																			
Nr.	X	Y	Z	Ref1	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afof	Ahous	Abar	Cmet	RL	LrT	LrN
(m)	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)
150	528023.23	5511910.38	399.29	0	1000	86.2	86.2	0.0	0.0	71.7	4.0	-1.1	0.0	0.0	0.0	0.0	-0.0	5.2	11.5
151	528023.23	5511910.38	399.29	0	2000	86.4	86.4	0.0	0.0	71.7	10.5	-1.1	0.0	0.0	0.0	0.0	-0.0	5.2	5.2
152	528023.23	5511910.38	399.29	0	4000	79.2	79.2	0.0	0.0	71.7	35.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-27.2	-27.2
153	528023.23	5511910.38	399.29	0	8000	72.1	72.1	0.0	0.0	71.7	127.3	-1.1	0.0	0.0	0.0	0.0	-0.0	-125.9	-125.9
154	528065.02	5511945.03	398.02	0	32	43.3	43.3	0.0	0.0	71.6	0.0	-5.3	0.0	0.0	4.8	0.0	-0.0	-27.7	-27.7
155	528065.02	5511945.03	398.02	0	63	52.5	52.5	0.0	0.0	71.6	0.1	-5.3	0.0	0.0	4.8	0.0	-0.0	-18.6	-18.6
156	528065.02	5511945.03	398.02	0	125	68.6	68.6	0.0	0.0	71.6	0.4	5.3	0.0	0.0	0.0	0.0	-0.0	-8.7	-8.7
157	528065.02	5511945.03	398.02	0	250	78.1	78.1	0.0	0.0	71.6	1.1	2.3	0.0	0.0	2.4	0.0	-0.0	0.7	0.7
158	528065.02	5511945.03	398.02	0	500	82.5	82.5	0.0	0.0	71.6	2.1	-1.0	0.0	0.0	4.8	0.0	-0.0	5.1	5.1
159	528065.02	5511945.03	398.02	0	1000	85.7	85.7	0.0	0.0	71.6	3.9	-1.1	0.0	0.0	4.8	0.0	-0.0	6.5	6.5
160	528065.02	5511945.03	398.02	0	2000	85.9	85.9	0.0	0.0	71.6	10.3	-1.1	0.0	0.0	4.8	0.0	-0.0	0.3	0.3
161	528065.02	5511945.03	398.02	0	4000	78.7	78.7	0.0	0.0	71.6	35.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-31.6	-31.6
162	528065.02	5511945.03	398.02	0	8000	71.6	71.6	0.0	0.0	71.6	125.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-128.6	-128.6
163	527862.39	5511871.41	397.38	0	32	44.3	44.3	0.0	0.0	72.7	0.0	-5.4	0.0	0.0	4.8	0.0	-0.0	-27.8	-27.8
164	527862.39	5511871.41	397.38	0	63	53.5	53.5	0.0	0.0	72.7	0.2	-5.4	0.0	0.0	4.8	0.0	-0.0	-18.7	-18.7
165	527862.39	5511871.41	397.38	0	125	69.6	69.6	0.0	0.0	72.7	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-8.9	-8.9
166	527862.39	5511871.41	397.38	0	250	79.1	79.1	0.0	0.0	72.7	1.3	2.3	0.0	0.0	2.5	0.0	-0.0	0.3	0.3
167	527862.39	5511871.41	397.38	0	500	83.5	83.5	0.0	0.0	72.7	2.3	-1.0	0.0	0.0	4.8	0.0	-0.0	4.7	4.7
168	527862.39	5511871.41	397.38	0	1000	86.7	86.7	0.0	0.0	72.7	4.5	-1.1	0.0	0.0	4.8	0.0	-0.0	5.8	5.8
169	527862.39	5511871.41	397.38	0	2000	86.9	86.9	0.0	0.0	72.7	11.8	-1.1	0.0	0.0	4.8	0.0	-0.0	-1.3	-1.3
170	527862.39	5511871.41	397.38	0	4000	79.7	79.7	0.0	0.0	72.7	39.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-36.6	-36.6
171	527862.39	5511871.41	397.38	0	8000	72.6	72.6	0.0	0.0	72.7	142.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-146.1	-146.1
172	527950.52	5511856.87	402.90	0	32	43.6	43.6	0.0	0.0	72.1	0.0	-5.4	0.0	0.0	0.0	0.0	-0.0	-23.1	-23.1
173	527950.52	5511856.87	402.90	0	63	52.8	52.8	0.0	0.0	72.1	0.1	-5.4	0.0	0.0	0.0	0.0	-0.0	-14.1	-14.1
174	527950.52	5511856.87	402.90	0	125	68.9	68.9	0.0	0.0	72.1	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-8.9	-8.9
175	527950.52	5511856.87	402.90	0	250	78.4	78.4	0.0	0.0	72.1	1.2	2.3	0.0	0.0	0.0	0.0	-0.0	2.8	2.8
176	527950.52	5511856.87	402.90	0	500	82.8	82.8	0.0	0.0	72.1	2.2	-1.0	0.0	0.0	0.0	0.0	-0.0	9.6	9.6
177	527950.52	5511856.87	402.90	0	1000	86.0	86.0	0.0	0.0	72.1	4.1	-1.1	0.0	0.0	0.0	0.0	-0.0	10.9	10.9
178	527950.52	5511856.87	402.90	0	2000	86.2	86.2	0.0	0.0	72.1	10.9	-1.1	0.0	0.0	0.0	0.0	-0.0	4.3	4.3
179	527950.52	5511856.87	402.90	0	4000	79.0	79.0	0.0	0.0	72.1	37.1	-1.1	0.0	0.0	0.0	0.0	-0.0	-29.0	-29.0
180	527950.52	5511856.87	402.90	0	8000	71.9	71.9	0.0	0.0	72.1	132.2	-1.1	0.0	0.0	0.0	0.0	-0.0	-131.3	-131.3
181	528339.51	5512029.45	399.37	0	32	41.5	41.5	0.0	0.0	70.1	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-23.4	-23.4
182	528339.51	5512029.45	399.37	0	63	50.7	50.7	0.0	0.0	70.1	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-14.3	-14.3
183	528339.51	5512029.45	399.37	0	125	66.8	66.8	0.0	0.0	70.1	0.4	5.1	0.0	0.0	0.0	0.0	-0.0	-8.8	-8.8
184	528339.51	5512029.45	399.37	0	250	76.3	76.3	0.0	0.0	70.1	0.9	2.4	0.0	0.0	0.0	0.0	-0.0	2.9	2.9
185	528339.51	5512029.45	399.37	0	500	80.7	80.7	0.0	0.0	70.1	1.7	-1.0	0.0	0.0	0.0	0.0	-0.0	9.9	9.9
186	528339.51	5512029.45	399.37	0	1000	83.9	83.9	0.0	0.0	70.1	3.3	-1.0	0.0	0.0	0.0	0.0	-0.0	11.6	11.6
187	528339.51	5512029.45	399.37	0	2000	84.1	84.1	0.0	0.0	70.1	8.7	-1.0	0.0	0.0	0.0	0.0	-0.0	6.3	6.3
188	528339.51	5512029.45	399.37	0	4000	76.9	76.9	0.0	0.0	70.1	29.5	-1.0	0.0	0.0	0.0	0.0	-0.0	-21.7	-21.7
189	528339.51	5512029.45	399.37	0	8000	69.8	69.8	0.0	0.0	70.1	105.3	-1.0	0.0	0.0	0.0	0.0	-0.0	-104.5	-104.5
190	527772.58	5512147.47	402.29	0	32	45.2	45.2	0.0	0.0	74.1	0.1	-5.5	0.0	0.0	0.0	0.0	-0.0	-23.4	-23.4
191	527772.58	5512147.47	402.29	0	63	54.4	54.4	0.0	0.0	74.1	0.2	-5.5	0.0	0.0	0.0	0.0	-0.0	-14.3	-14.3
192	527772.58	5512147.47	402.29	0	125	70.5	70.5	0.0	0.0	74.1	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-9.4	-9.4
193	527772.58	5512147.47	402.29	0	250	80.0	80.0	0.0	0.0	74.1	1.5	2.3	0.0	0.0	0.0	0.0	-0.0	2.2	2.2
194	527772.58	5512147.47	402.29	0	500	84.4	84.4	0.0	0.0	74.1	2.8	-1.1	0.0	0.0	0.0	0.0	-0.0	8.7	8.7
195	527772.58	5512147.47	402.29	0	1000	87.6	87.6	0.0	0.0	74.1	5.2	-1.1	0.0	0.0	0.0	0.0	-0.0	9.4	9.4
196	527772.58	5512147.47	402.29	0	2000	87.8	87.8	0.0	0.0	74.1	13.8	-1.1	0.0	0.0	0.0	0.0	-0.0	1.1	1.1
197	527772.58	5512147.47	402.29	0	4000	80.6	80.6	0.0	0.0	74.1	46.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-39.0	-39.0
198	527772.58	5512147.47	402.29	0	8000	73.5	73.5	0.0	0.0	74.1	166.5	-1.1	0.0	0.0	0.0	0.0	-0.0	-165.9	-165.9
199	528281.08	5512255.35	399.99	0	32	43.1	43.1	0.0	0.0	71.9	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-23.5	-23.5
200	528281.08	5512255.35	399.99	0	63	52.3	52.3	0.0	0.0	71.9	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-14.4	-14.4
201	528281.08	5512255.35	399.99	0	125	68.4	68.4	0.0	0.0	71.9	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-9.2	-9.2
202	528281.08	5512255.35	399.99	0	250	77.9	77.9	0.0	0.0	71.9	1.2	2.3	0.0	0.0	0.0	0.0	-0.0	2.5	2.5
203	528281.08	5512255.35	399.99	0	500	82.3	82.3	0.0	0.0	71.9	2.1	-1.0	0.0	0.0	0.0	0.0	-0.0	9.3	9.3
204	528281.08	5512255.35	399.99	0	1000	85.5	85.5	0.0	0.0	71.9	4.0	-1.1	0.0	0.0	0.0	0.0	-0.0	10.6	10.6
205	528281.08	5512255.35	399.99	0	2000	85.7	85.7	0.0	0.0	71.9	10.7	-1.1	0.0	0.0	0.0	0.0	-0.0	4.2	4.2
206	528281.08	5512255.35	399.99	0	4000	78.5	78.5	0.0	0.0	71.9	36.3	-1.1	0.0	0.0	0.0	0.0	-0.0	-28.6	-28.6
207	528281.08	5512255.35	399.99	0	8000	71.4	71.4	0.0	0.0	71.9	129.3	-1.1	0.0	0.0	0.0	0.0	-0.0	-128.8	-128.8
208	527789.39	5511877.81	398.12	0	32	44.3	44.3	0.0	0.0	73.2	0.0	-5.4	0.0	0.0	4.8	0.0	-0.0	-28.3	-28.3
209	527789.39	5511877.81	398.12	0	63	53.5	53.5	0.0	0.0	73.2	0.2	-5.4	0.0	0.0	4.8	0.0	-0.0	-19.2	-19.2
210	527789.39	5511877.81	398.12	0	125	69.6	69.6	0.0	0.0	73.2	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-9.4	-9.4
211	527789.39	5511877.81	398.12	0	250	79.1	79.1	0.0	0.0	73.2	1.3	2.3	0.0	0.0	2.5	0.0	-0.0	-0.2	-0.2
212	527789.39	5511877.81	398.12	0	500	83.5	83.5	0.0	0.0	73.2	2.5	-1.1	0.0	0.0	4.8	0.0	-0.0	4.1	4.1

Line Source, ISO 9613, Name: "Haul Truck #3", ID: "Htruck3_o"																			
Nr.	X	Y	Z	Ref1	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afof	Ahous	Abar	Cmet	RL	LrT	LrN

Line Source, ISO 9613, Name: "Haul Truck #3", ID: "Htruck3_o"																			
Nr.	X	Y	Z	Refl.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT	LrN
(m)	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	dB(A)	dB(A)
276	528358.44	5512061.77	399.33	0	1000	82.9	82.9	0.0	0.0	70.2	3.3	-1.0	0.0	0.0	0.0	0.0	-0.0	10.4	10.4
277	528358.44	5512061.77	399.33	0	2000	83.1	83.1	0.0	0.0	70.2	8.8	-1.0	0.0	0.0	0.0	0.0	-0.0	5.1	5.1
278	528358.44	5512061.77	399.33	0	4000	75.9	75.9	0.0	0.0	70.2	29.8	-1.0	0.0	0.0	0.0	0.0	-0.0	-23.1	-23.1
279	528358.44	5512061.77	399.33	0	8000	68.8	68.8	0.0	0.0	70.2	106.4	-1.0	0.0	0.0	0.0	0.0	-0.0	-106.8	-106.8
280	528502.55	5512234.69	400.68	0	32	40.9	40.9	0.0	0.0	70.7	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-24.6	-24.6
281	528502.55	5512234.69	400.68	0	63	50.1	50.1	0.0	0.0	70.7	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-15.5	-15.5
282	528502.55	5512234.69	400.68	0	125	66.2	66.2	0.0	0.0	70.7	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-10.1	-10.1
283	528502.55	5512234.69	400.68	0	250	75.7	75.7	0.0	0.0	70.7	1.0	2.3	0.0	0.0	0.0	0.0	-0.0	1.7	1.7
284	528502.55	5512234.69	400.68	0	500	80.1	80.1	0.0	0.0	70.7	1.9	-1.0	0.0	0.0	0.0	0.0	-0.0	8.6	8.6
285	528502.55	5512234.69	400.68	0	1000	83.3	83.3	0.0	0.0	70.7	3.5	-1.1	0.0	0.0	0.0	0.0	-0.0	10.1	10.1
286	528502.55	5512234.69	400.68	0	2000	83.5	83.5	0.0	0.0	70.7	9.3	-1.1	0.0	0.0	0.0	0.0	-0.0	4.5	4.5
287	528502.55	5512234.69	400.68	0	4000	76.3	76.3	0.0	0.0	70.7	31.5	-1.1	0.0	0.0	0.0	0.0	-0.0	-24.9	-24.9
288	528502.55	5512234.69	400.68	0	8000	69.2	69.2	0.0	0.0	70.7	112.5	-1.1	0.0	0.0	0.0	0.0	-0.0	-113.0	-113.0
289	528007.23	5511886.83	400.55	0	32	42.0	42.0	0.0	0.0	71.8	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-24.5	-24.5
290	528007.23	5511886.83	400.55	0	63	51.2	51.2	0.0	0.0	71.8	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-15.4	-15.4
291	528007.23	5511886.83	400.55	0	125	67.3	67.3	0.0	0.0	71.8	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-10.2	-10.2
292	528007.23	5511886.83	400.55	0	250	76.8	76.8	0.0	0.0	71.8	1.1	2.3	0.0	0.0	0.0	0.0	-0.0	1.5	1.5
293	528007.23	5511886.83	400.55	0	500	81.2	81.2	0.0	0.0	71.8	2.1	-1.0	0.0	0.0	0.0	0.0	-0.0	8.3	8.3
294	528007.23	5511886.83	400.55	0	1000	84.4	84.4	0.0	0.0	71.8	4.0	-1.1	0.0	0.0	0.0	0.0	-0.0	9.7	9.7
295	528007.23	5511886.83	400.55	0	2000	84.6	84.6	0.0	0.0	71.8	10.6	-1.1	0.0	0.0	0.0	0.0	-0.0	3.3	3.3
296	528007.23	5511886.83	400.55	0	4000	77.4	77.4	0.0	0.0	71.8	35.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-29.1	-29.1
297	528007.23	5511886.83	400.55	0	8000	70.3	70.3	0.0	0.0	71.8	127.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-128.1	-128.1
298	528397.44	5512122.47	399.61	0	32	40.6	40.6	0.0	0.0	70.4	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-24.6	-24.6
299	528397.44	5512122.47	399.61	0	63	49.8	49.8	0.0	0.0	70.4	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-15.5	-15.5
300	528397.44	5512122.47	399.61	0	125	65.9	65.9	0.0	0.0	70.4	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-10.0	-10.0
301	528397.44	5512122.47	399.61	0	250	75.4	75.4	0.0	0.0	70.4	1.0	2.3	0.0	0.0	0.0	0.0	-0.0	1.7	1.7
302	528397.44	5512122.47	399.61	0	500	79.8	79.8	0.0	0.0	70.4	1.8	-1.0	0.0	0.0	0.0	0.0	-0.0	8.6	8.6
303	528397.44	5512122.47	399.61	0	1000	83.0	83.0	0.0	0.0	70.4	3.4	-1.1	0.0	0.0	0.0	0.0	-0.0	10.3	10.3
304	528397.44	5512122.47	399.61	0	2000	83.2	83.2	0.0	0.0	70.4	9.0	-1.1	0.0	0.0	0.0	0.0	-0.0	4.9	4.9
305	528397.44	5512122.47	399.61	0	4000	76.0	76.0	0.0	0.0	70.4	30.5	-1.1	0.0	0.0	0.0	0.0	-0.0	-23.8	-23.8
306	528397.44	5512122.47	399.61	0	8000	68.9	68.9	0.0	0.0	70.4	108.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-109.1	-109.1
307	528370.53	5512105.04	400.37	0	32	40.5	40.5	0.0	0.0	70.4	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-24.7	-24.7
308	528370.53	5512105.04	400.37	0	63	49.7	49.7	0.0	0.0	70.4	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-15.6	-15.6
309	528370.53	5512105.04	400.37	0	125	65.8	65.8	0.0	0.0	70.4	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-10.2	-10.2
310	528370.53	5512105.04	400.37	0	250	75.3	75.3	0.0	0.0	70.4	1.0	2.3	0.0	0.0	0.0	0.0	-0.0	1.6	1.6
311	528370.53	5512105.04	400.37	0	500	79.7	79.7	0.0	0.0	70.4	1.8	-1.0	0.0	0.0	0.0	0.0	-0.0	8.5	8.5
312	528370.53	5512105.04	400.37	0	1000	82.9	82.9	0.0	0.0	70.4	3.4	-1.1	0.0	0.0	0.0	0.0	-0.0	10.1	10.1
313	528370.53	5512105.04	400.37	0	2000	83.1	83.1	0.0	0.0	70.4	9.0	-1.1	0.0	0.0	0.0	0.0	-0.0	4.7	4.7
314	528370.53	5512105.04	400.37	0	4000	75.9	75.9	0.0	0.0	70.4	30.6	-1.1	0.0	0.0	0.0	0.0	-0.0	-24.1	-24.1
315	528370.53	5512105.04	400.37	0	8000	68.8	68.8	0.0	0.0	70.4	109.2	-1.1	0.0	0.0	0.0	0.0	-0.0	-109.8	-109.8
316	527529.67	5511755.36	395.83	0	32	44.3	44.3	0.0	0.0	74.5	0.1	-5.5	0.0	0.0	0.0	0.0	-0.0	-29.5	-29.5
317	527529.67	5511755.36	395.83	0	63	53.5	53.5	0.0	0.0	74.5	0.2	-5.5	0.0	0.0	0.0	0.0	-0.0	-20.4	-20.4
318	527529.67	5511755.36	395.83	0	125	69.6	69.6	0.0	0.0	74.5	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-10.8	-10.8
319	527529.67	5511755.36	395.83	0	250	79.1	79.1	0.0	0.0	74.5	1.6	2.3	0.0	0.0	0.0	0.0	-0.0	-1.7	-1.7
320	527529.67	5511755.36	395.83	0	500	83.5	83.5	0.0	0.0	74.5	2.9	-1.1	0.0	0.0	0.0	0.0	-0.0	2.4	2.4
321	527529.67	5511755.36	395.83	0	1000	86.7	86.7	0.0	0.0	74.5	5.5	-1.1	0.0	0.0	0.0	0.0	-0.0	-3.1	-3.1
322	527529.67	5511755.36	395.83	0	2000	86.9	86.9	0.0	0.0	74.5	14.5	-1.1	0.0	0.0	0.0	0.0	-0.0	-5.7	-5.7
323	527529.67	5511755.36	395.83	0	4000	79.7	79.7	0.0	0.0	74.5	49.1	-1.1	0.0	0.0	0.0	0.0	-0.0	-47.6	-47.6
324	527529.67	5511755.36	395.83	0	8000	72.6	72.6	0.0	0.0	74.5	175.2	-1.1	0.0	0.0	0.0	0.0	-0.0	-180.7	-180.7
325	527893.81	5511865.88	398.70	0	32	42.3	42.3	0.0	0.0	72.5	0.0	-5.4	0.0	0.0	0.0	0.0	-0.0	-29.7	-29.7
326	527893.81	5511865.88	398.70	0	63	51.5	51.5	0.0	0.0	72.5	0.1	-5.4	0.0	0.0	0.0	0.0	-0.0	-20.6	-20.6
327	527893.81	5511865.88	398.70	0	125	67.6	67.6	0.0	0.0	72.5	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-10.7	-10.7
328	527893.81	5511865.88	398.70	0	250	77.1	77.1	0.0	0.0	72.5	1.2	2.3	0.0	0.0	0.0	0.0	-0.0	-1.4	-1.4
329	527893.81	5511865.88	398.70	0	500	81.5	81.5	0.0	0.0	72.5	2.3	-1.0	0.0	0.0	0.0	0.0	-0.0	2.9	2.9
330	527893.81	5511865.88	398.70	0	1000	84.7	84.7	0.0	0.0	72.5	4.3	-1.1	0.0	0.0	0.0	0.0	-0.0	4.1	4.1
331	527893.81	5511865.88	398.70	0	2000	84.9	84.9	0.0	0.0	72.5	11.5	-1.1	0.0	0.0	0.0	0.0	-0.0	-2.8	-2.8
332	527893.81	5511865.88	398.70	0	4000	77.7	77.7	0.0	0.0	72.5	38.9	-1.1	0.0	0.0	0.0	0.0	-0.0	-37.4	-37.4
333	527893.81	5511865.88	398.70	0	8000	70.6	70.6	0.0	0.0	72.5	138.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-144.3	-144.3
334	527853.15	5512155.47	403.00	0	32	43.3	43.3	0.0	0.0	73.7	0.0	-5.5	0.0	0.0	0.0	0.0	-0.0	-24.9	-24.9
335	527853.15	5512155.47	403.00	0	63	52.5	52.5	0.0	0.0	73.7	0.2	-5.5	0.0	0.0	0.0	0.0	-0.0	-15.9	-15.9
336	527853.15	5512155.47	403.00	0	125	68.6	68.6	0.0	0.0	73.7	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-10.9	-10.9
337	527853.15	5512155.47	403.00	0	250	78.1	78.1	0.0	0.0	73.7	1.4	2.3	0.0	0.0	0.0	0.0	-0.0	0.7	0.7
338	527853.15	5512155.47	403.00	0	500	82.5	82.5	0.0	0.0	73.7	2.6	-1.1	0.0	0.0	0.0	0.0	-0.0	7.3	7.3

Sample Calculation at facade of NR03

Line Source, ISO 9613, Name: "Haul Truck #3", ID: "Htruck3_o"																			
Nr.	X	Y	Z	Refl.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT	LrN

Line Source, ISO 9613, Name: "Haul Truck #3", ID: "Htruck3_o"																			
Nr.	X (m)	Y (m)	Z (m)	Refi.	Freq. (Hz)	LxT dB(A)	LxN dB(A)	K0 (dB)	Dc (dB)	Aadv (dB)	Aatm (dB)	Agr (dB)	Afol (dB)	Ahous (dB)	Abar (dB)	Cmet (dB)	RL (dB)	LrT dB(A)	LrN dB(A)
402	527915.62	5511861.00	401.49	0	1000	83.8	83.8	0.0	0.0	72.3	4.3	-1.1	0.0	0.0	0.0	0.0	-0.0	8.3	8.3
403	527915.62	5511861.00	401.49	0	2000	84.0	84.0	0.0	0.0	72.3	11.3	-1.1	0.0	0.0	0.0	0.0	-0.0	1.5	1.5
404	527915.62	5511861.00	401.49	0	4000	76.8	76.8	0.0	0.0	72.3	38.2	-1.1	0.0	0.0	0.0	0.0	-0.0	-32.6	-32.6
405	527915.62	5511861.00	401.49	0	8000	69.7	69.7	0.0	0.0	72.3	136.1	-1.1	0.0	0.0	0.0	0.0	-0.0	-137.6	-137.6
406	528352.65	5512048.99	399.35	0	32	39.2	39.2	0.0	0.0	70.1	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-25.8	-25.8
407	528352.65	5512048.99	399.35	0	63	48.4	48.4	0.0	0.0	70.1	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-16.7	-16.7
408	528352.65	5512048.99	399.35	0	125	64.5	64.5	0.0	0.0	70.1	0.4	5.1	0.0	0.0	0.0	0.0	-0.0	-11.2	-11.2
409	528352.65	5512048.99	399.35	0	250	74.0	74.0	0.0	0.0	70.1	0.9	2.4	0.0	0.0	0.0	0.0	-0.0	0.5	0.5
410	528352.65	5512048.99	399.35	0	500	78.4	78.4	0.0	0.0	70.1	1.8	-1.0	0.0	0.0	0.0	0.0	-0.0	7.5	7.5
411	528352.65	5512048.99	399.35	0	1000	81.6	81.6	0.0	0.0	70.1	3.3	-1.0	0.0	0.0	0.0	0.0	-0.0	9.2	9.2
412	528352.65	5512048.99	399.35	0	2000	81.8	81.8	0.0	0.0	70.1	8.8	-1.0	0.0	0.0	0.0	0.0	-0.0	3.9	3.9
413	528352.65	5512048.99	399.35	0	4000	74.6	74.6	0.0	0.0	70.1	29.7	-1.0	0.0	0.0	0.0	0.0	-0.0	-24.2	-24.2
414	528352.65	5512048.99	399.35	0	8000	67.5	67.5	0.0	0.0	70.1	105.8	-1.0	0.0	0.0	0.0	0.0	-0.0	-107.4	-107.4
415	528384.03	5512116.38	400.40	0	32	39.4	39.4	0.0	0.0	70.4	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-25.8	-25.8
416	528384.03	5512116.38	400.40	0	63	48.6	48.6	0.0	0.0	70.4	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-16.7	-16.7
417	528384.03	5512116.38	400.40	0	125	64.7	64.7	0.0	0.0	70.4	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-11.3	-11.3
418	528384.03	5512116.38	400.40	0	250	74.2	74.2	0.0	0.0	70.4	1.0	2.3	0.0	0.0	0.0	0.0	-0.0	0.5	0.5
419	528384.03	5512116.38	400.40	0	500	78.6	78.6	0.0	0.0	70.4	1.8	-1.0	0.0	0.0	0.0	0.0	-0.0	7.4	7.4
420	528384.03	5512116.38	400.40	0	1000	81.8	81.8	0.0	0.0	70.4	3.4	-1.1	0.0	0.0	0.0	0.0	-0.0	9.0	9.0
421	528384.03	5512116.38	400.40	0	2000	82.0	82.0	0.0	0.0	70.4	9.0	-1.1	0.0	0.0	0.0	0.0	-0.0	3.6	3.6
422	528384.03	5512116.38	400.40	0	4000	74.8	74.8	0.0	0.0	70.4	30.6	-1.1	0.0	0.0	0.0	0.0	-0.0	-25.2	-25.2
423	528384.03	5512116.38	400.40	0	8000	67.7	67.7	0.0	0.0	70.4	109.2	-1.1	0.0	0.0	0.0	0.0	-0.0	-110.8	-110.8
424	527927.95	5512177.01	402.45	0	32	42.0	42.0	0.0	0.0	73.4	0.0	-5.5	0.0	0.0	0.0	0.0	-0.0	-26.0	-26.0
425	527927.95	5512177.01	402.45	0	63	51.2	51.2	0.0	0.0	73.4	0.2	-5.5	0.0	0.0	0.0	0.0	-0.0	-16.9	-16.9
426	527927.95	5512177.01	402.45	0	125	67.3	67.3	0.0	0.0	73.4	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-11.9	-11.9
427	527927.95	5512177.01	402.45	0	250	76.8	76.8	0.0	0.0	73.4	1.4	2.3	0.0	0.0	0.0	0.0	-0.0	-0.3	-0.3
428	527927.95	5512177.01	402.45	0	500	81.2	81.2	0.0	0.0	73.4	2.5	-1.1	0.0	0.0	0.0	0.0	-0.0	6.3	6.3
429	527927.95	5512177.01	402.45	0	1000	84.4	84.4	0.0	0.0	73.4	4.8	-1.1	0.0	0.0	0.0	0.0	-0.0	7.3	7.3
430	527927.95	5512177.01	402.45	0	2000	84.6	84.6	0.0	0.0	73.4	12.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-0.4	-0.4
431	527927.95	5512177.01	402.45	0	4000	77.4	77.4	0.0	0.0	73.4	43.0	-1.1	0.0	0.0	0.0	0.0	-0.0	-37.9	-37.9
432	527927.95	5512177.01	402.45	0	8000	70.3	70.3	0.0	0.0	73.4	153.3	-1.1	0.0	0.0	0.0	0.0	-0.0	-155.3	-155.3
433	528363.60	5512093.03	399.48	0	32	38.9	38.9	0.0	0.0	70.4	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-26.3	-26.3
434	528363.60	5512093.03	399.48	0	63	48.1	48.1	0.0	0.0	70.4	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-17.1	-17.1
435	528363.60	5512093.03	399.48	0	125	64.2	64.2	0.0	0.0	70.4	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-11.7	-11.7
436	528363.60	5512093.03	399.48	0	250	73.7	73.7	0.0	0.0	70.4	1.0	2.3	0.0	0.0	0.0	0.0	-0.0	0.0	0.0
437	528363.60	5512093.03	399.48	0	500	78.1	78.1	0.0	0.0	70.4	1.8	-1.0	0.0	0.0	0.0	0.0	-0.0	7.0	7.0
438	528363.60	5512093.03	399.48	0	1000	81.3	81.3	0.0	0.0	70.4	3.4	-1.1	0.0	0.0	0.0	0.0	-0.0	8.6	8.6
439	528363.60	5512093.03	399.48	0	2000	81.5	81.5	0.0	0.0	70.4	9.0	-1.1	0.0	0.0	0.0	0.0	-0.0	3.2	3.2
440	528363.60	5512093.03	399.48	0	4000	74.3	74.3	0.0	0.0	70.4	30.5	-1.1	0.0	0.0	0.0	0.0	-0.0	-25.5	-25.5
441	528363.60	5512093.03	399.48	0	8000	67.2	67.2	0.0	0.0	70.4	108.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-110.8	-110.8
442	527666.66	5511819.93	394.51	0	32	42.3	42.3	0.0	0.0	73.8	0.0	-5.5	0.0	0.0	0.0	0.0	-0.0	-30.8	-30.8
443	527666.66	5511819.93	394.51	0	63	51.5	51.5	0.0	0.0	73.8	0.2	-5.5	0.0	0.0	0.0	0.0	-0.0	-21.7	-21.7
444	527666.66	5511819.93	394.51	0	125	67.6	67.6	0.0	0.0	73.8	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-12.1	-12.1
445	527666.66	5511819.93	394.51	0	250	77.1	77.1	0.0	0.0	73.8	1.4	2.3	0.0	0.0	0.0	0.0	-0.0	-2.9	-2.9
446	527666.66	5511819.93	394.51	0	500	81.5	81.5	0.0	0.0	73.8	2.7	-1.1	0.0	0.0	0.0	0.0	-0.0	1.3	1.3
447	527666.66	5511819.93	394.51	0	1000	84.7	84.7	0.0	0.0	73.8	5.1	-1.1	0.0	0.0	0.0	0.0	-0.0	2.2	2.2
448	527666.66	5511819.93	394.51	0	2000	84.9	84.9	0.0	0.0	73.8	13.4	-1.1	0.0	0.0	0.0	0.0	-0.0	-5.9	-5.9
449	527666.66	5511819.93	394.51	0	4000	77.7	77.7	0.0	0.0	73.8	45.4	-1.1	0.0	0.0	0.0	0.0	-0.0	-45.1	-45.1
450	527666.66	5511819.93	394.51	0	8000	70.6	70.6	0.0	0.0	73.8	161.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-168.6	-168.6
451	527759.43	5511874.61	397.68	0	32	41.5	41.5	0.0	0.0	73.4	0.0	-5.5	0.0	0.0	0.0	0.0	-0.0	-31.2	-31.2
452	527759.43	5511874.61	397.68	0	63	50.7	50.7	0.0	0.0	73.4	0.2	-5.5	0.0	0.0	0.0	0.0	-0.0	-22.1	-22.1
453	527759.43	5511874.61	397.68	0	125	66.8	66.8	0.0	0.0	73.4	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-12.4	-12.4
454	527759.43	5511874.61	397.68	0	250	76.3	76.3	0.0	0.0	73.4	1.4	2.3	0.0	0.0	0.0	0.0	-0.0	-3.2	-3.2
455	527759.43	5511874.61	397.68	0	500	80.7	80.7	0.0	0.0	73.4	2.5	-1.1	0.0	0.0	0.0	0.0	-0.0	1.1	1.1
456	527759.43	5511874.61	397.68	0	1000	83.9	83.9	0.0	0.0	73.4	4.8	-1.1	0.0	0.0	0.0	0.0	-0.0	2.0	2.0
457	527759.43	5511874.61	397.68	0	2000	84.1	84.1	0.0	0.0	73.4	12.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-5.6	-5.6
458	527759.43	5511874.61	397.68	0	4000	76.9	76.9	0.0	0.0	73.4	43.1	-1.1	0.0	0.0	0.0	0.0	-0.0	-43.2	-43.2
459	527759.43	5511874.61	397.68	0	8000	69.8	69.8	0.0	0.0	73.4	153.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-160.9	-160.9
460	528115.84	5511949.36	398.89	0	32	39.4	39.4	0.0	0.0	71.2	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-26.6	-26.6
461	528115.84	5511949.36	398.89	0	63	48.6	48.6	0.0	0.0	71.2	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-17.5	-17.5
462	528115.84	5511949.36	398.89	0	125	64.7	64.7	0.0	0.0	71.2	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-12.2	-12.2
463	528115.84	5511949.36	398.89	0	250	74.2	74.2	0.0	0.0	71.2	1.1	2.3	0.0	0.0	0.0	0.0	-0.0	-0.5	-0.5
464	528115.84	5511949.36	398.89	0	500	78.6	78.6	0.0	0.0	71.2	2.0	-1.0	0.0	0.0	0.0	0.0	-0.0	6.4	6.4

Sample Calculation at facade of NR03

Line Source, ISO 9613, Name: "Haul Truck #3", ID: "Htruck3_o"																			
Nr.	X (m)	Y (m)	Z (m)	Refi.	Freq. (Hz)	LxT dB(A)	LxN dB(A)	K0 (dB)	Dc (dB)	Aadv (dB)	Aatm (dB)	Agr (dB)	Afol (dB)	Ahous (dB)	Abar (dB)	Cmet (dB)	RL (dB)	LrT dB(A)	LrN dB(A)



Line Source, ISO 9613, Name: "Haul Truck #3", ID: "Htruck3_o"																			
Nr.	X	Y	Z	RefI	Freq.	LxT	LxN	K0	Dc	Aadv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)	(dB(A))	(dB(A))	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB(A))	(dB(A))
528	528078.65	5512237.87	400.46	0	1000	82.7	82.7	0.0	0.0	72.8	4.5	-1.1	0.0	0.0	0.0	0.0	-0.0	6.4	6.4
529	528078.65	5512237.87	400.46	0	2000	82.9	82.9	0.0	0.0	72.8	11.9	-1.1	0.0	0.0	0.0	0.0	-0.0	-0.8	-0.8
530	528078.65	5512237.87	400.46	0	4000	75.7	75.7	0.0	0.0	72.8	40.4	-1.1	0.0	0.0	0.0	0.0	-0.0	-36.5	-36.5
531	528078.65	5512237.87	400.46	0	8000	68.6	68.6	0.0	0.0	72.8	144.2	-1.1	0.0	0.0	0.0	0.0	-0.0	-147.3	-147.3
532	528103.79	5512241.06	402.66	0	32	40.0	40.0	0.0	0.0	72.7	0.0	-5.4	0.0	0.0	0.0	0.0	-0.0	-27.3	-27.3
533	528103.79	5512241.06	402.66	0	63	49.2	49.2	0.0	0.0	72.7	0.2	-5.4	0.0	0.0	0.0	0.0	-0.0	-18.2	-18.2
534	528103.79	5512241.06	402.66	0	125	65.3	65.3	0.0	0.0	72.7	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-13.2	-13.2
535	528103.79	5512241.06	402.66	0	250	74.8	74.8	0.0	0.0	72.7	1.3	2.3	0.0	0.0	0.0	0.0	-0.0	-1.5	-1.5
536	528103.79	5512241.06	402.66	0	500	79.2	79.2	0.0	0.0	72.7	2.3	-1.0	0.0	0.0	0.0	0.0	-0.0	5.2	5.2
537	528103.79	5512241.06	402.66	0	1000	82.4	82.4	0.0	0.0	72.7	4.5	-1.1	0.0	0.0	0.0	0.0	-0.0	6.3	6.3
538	528103.79	5512241.06	402.66	0	2000	82.6	82.6	0.0	0.0	72.7	11.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-0.8	-0.8
539	528103.79	5512241.06	402.66	0	4000	75.4	75.4	0.0	0.0	72.7	39.9	-1.1	0.0	0.0	0.0	0.0	-0.0	-36.1	-36.1
540	528103.79	5512241.06	402.66	0	8000	68.3	68.3	0.0	0.0	72.7	142.3	-1.1	0.0	0.0	0.0	0.0	-0.0	-145.6	-145.6
541	527708.22	5511851.01	394.10	0	32	40.7	40.7	0.0	0.0	73.6	0.0	-5.5	0.0	0.0	4.8	0.0	-0.0	-32.3	-32.3
542	527708.22	5511851.01	394.10	0	63	49.9	49.9	0.0	0.0	73.6	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-23.2	-23.2
543	527708.22	5511851.01	394.10	0	125	66.0	66.0	0.0	0.0	73.6	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-13.5	-13.5
544	527708.22	5511851.01	394.10	0	250	75.5	75.5	0.0	0.0	73.6	1.4	2.3	0.0	0.0	2.5	0.0	-0.0	-4.3	-4.3
545	527708.22	5511851.01	394.10	0	500	79.9	79.9	0.0	0.0	73.6	2.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-0.1	-0.1
546	527708.22	5511851.01	394.10	0	1000	83.1	83.1	0.0	0.0	73.6	5.0	-1.1	0.0	0.0	4.8	0.0	-0.0	0.8	0.8
547	527708.22	5511851.01	394.10	0	2000	83.3	83.3	0.0	0.0	73.6	13.1	-1.1	0.0	0.0	4.8	0.0	-0.0	-7.1	-7.1
548	527708.22	5511851.01	394.10	0	4000	76.1	76.1	0.0	0.0	73.6	44.4	-1.1	0.0	0.0	4.8	0.0	-0.0	-45.6	-45.6
549	527708.22	5511851.01	394.10	0	8000	69.0	69.0	0.0	0.0	73.6	158.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-166.6	-166.6
550	527683.52	5511832.73	394.67	0	32	40.8	40.8	0.0	0.0	73.8	0.0	-5.5	0.0	0.0	4.8	0.0	-0.0	-32.3	-32.3
551	527683.52	5511832.73	394.67	0	63	50.0	50.0	0.0	0.0	73.8	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-23.3	-23.3
552	527683.52	5511832.73	394.67	0	125	66.1	66.1	0.0	0.0	73.8	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-13.6	-13.6
553	527683.52	5511832.73	394.67	0	250	75.6	75.6	0.0	0.0	73.8	1.4	2.3	0.0	0.0	2.5	0.0	-0.0	-4.4	-4.4
554	527683.52	5511832.73	394.67	0	500	80.0	80.0	0.0	0.0	73.8	2.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-0.2	-0.2
555	527683.52	5511832.73	394.67	0	1000	83.2	83.2	0.0	0.0	73.8	5.0	-1.1	0.0	0.0	4.8	0.0	-0.0	0.7	0.7
556	527683.52	5511832.73	394.67	0	2000	83.4	83.4	0.0	0.0	73.8	13.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-7.3	-7.3
557	527683.52	5511832.73	394.67	0	4000	76.2	76.2	0.0	0.0	73.8	45.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-46.2	-46.2
558	527683.52	5511832.73	394.67	0	8000	69.1	69.1	0.0	0.0	73.8	160.4	-1.1	0.0	0.0	4.8	0.0	-0.0	-168.7	-168.7
559	528320.95	5512001.82	399.35	0	32	36.9	36.9	0.0	0.0	70.0	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-27.9	-27.9
560	528320.95	5512001.82	399.35	0	63	46.1	46.1	0.0	0.0	70.0	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-18.8	-18.8
561	528320.95	5512001.82	399.35	0	125	62.2	62.2	0.0	0.0	70.0	0.4	5.1	0.0	0.0	0.0	0.0	-0.0	-13.3	-13.3
562	528320.95	5512001.82	399.35	0	250	71.7	71.7	0.0	0.0	70.0	0.9	2.4	0.0	0.0	0.0	0.0	-0.0	-1.6	-1.6
563	528320.95	5512001.82	399.35	0	500	76.1	76.1	0.0	0.0	70.0	1.7	-1.0	0.0	0.0	0.0	0.0	-0.0	5.4	5.4
564	528320.95	5512001.82	399.35	0	1000	79.3	79.3	0.0	0.0	70.0	3.3	-1.0	0.0	0.0	0.0	0.0	-0.0	7.1	7.1
565	528320.95	5512001.82	399.35	0	2000	79.5	79.5	0.0	0.0	70.0	8.7	-1.0	0.0	0.0	0.0	0.0	-0.0	1.9	1.9
566	528320.95	5512001.82	399.35	0	4000	72.3	72.3	0.0	0.0	70.0	29.3	-1.0	0.0	0.0	0.0	0.0	-0.0	-26.0	-26.0
567	528320.95	5512001.82	399.35	0	8000	65.2	65.2	0.0	0.0	70.0	104.7	-1.0	0.0	0.0	0.0	0.0	-0.0	-108.4	-108.4
568	527591.39	5511765.26	395.15	0	32	41.0	41.0	0.0	0.0	74.2	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-32.5	-32.5
569	527591.39	5511765.26	395.15	0	63	50.2	50.2	0.0	0.0	74.2	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-23.4	-23.4
570	527591.39	5511765.26	395.15	0	125	66.3	66.3	0.0	0.0	74.2	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-13.8	-13.8
571	527591.39	5511765.26	395.15	0	250	75.8	75.8	0.0	0.0	74.2	1.5	2.3	0.0	0.0	2.5	0.0	-0.0	-4.7	-4.7
572	527591.39	5511765.26	395.15	0	500	80.2	80.2	0.0	0.0	74.2	2.8	-1.1	0.0	0.0	4.8	0.0	-0.0	-0.5	-0.5
573	527591.39	5511765.26	395.15	0	1000	83.4	83.4	0.0	0.0	74.2	5.3	-1.1	0.0	0.0	4.8	0.0	-0.0	0.3	0.3
574	527591.39	5511765.26	395.15	0	2000	83.6	83.6	0.0	0.0	74.2	13.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-8.2	-8.2
575	527591.39	5511765.26	395.15	0	4000	76.4	76.4	0.0	0.0	74.2	47.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-47.7	-47.7
576	527591.39	5511765.26	395.15	0	8000	69.3	69.3	0.0	0.0	74.2	168.5	-1.1	0.0	0.0	4.8	0.0	-0.0	-177.0	-177.0
577	528347.11	5512041.14	399.38	0	32	36.9	36.9	0.0	0.0	70.1	0.0	-5.2	0.0	0.0	0.0	0.0	-0.0	-28.1	-28.1
578	528347.11	5512041.14	399.38	0	63	46.1	46.1	0.0	0.0	70.1	0.1	-5.2	0.0	0.0	0.0	0.0	-0.0	-18.9	-18.9
579	528347.11	5512041.14	399.38	0	125	62.2	62.2	0.0	0.0	70.1	0.4	5.1	0.0	0.0	0.0	0.0	-0.0	-13.5	-13.5
580	528347.11	5512041.14	399.38	0	250	71.7	71.7	0.0	0.0	70.1	0.9	2.4	0.0	0.0	0.0	0.0	-0.0	-1.7	-1.7
581	528347.11	5512041.14	399.38	0	500	76.1	76.1	0.0	0.0	70.1	1.7	-1.0	0.0	0.0	0.0	0.0	-0.0	5.2	5.2
582	528347.11	5512041.14	399.38	0	1000	79.3	79.3	0.0	0.0	70.1	3.3	-1.0	0.0	0.0	0.0	0.0	-0.0	6.9	6.9
583	528347.11	5512041.14	399.38	0	2000	79.5	79.5	0.0	0.0	70.1	8.7	-1.0	0.0	0.0	0.0	0.0	-0.0	1.7	1.7
584	528347.11	5512041.14	399.38	0	4000	72.3	72.3	0.0	0.0	70.1	29.6	-1.0	0.0	0.0	0.0	0.0	-0.0	-26.4	-26.4
585	528347.11	5512041.14	399.38	0	8000	65.2	65.2	0.0	0.0	70.1	105.6	-1.0	0.0	0.0	0.0	0.0	-0.0	-109.5	-109.5
586	527727.04	5511861.91	395.21	0	32	40.2	40.2	0.0	0.0	73.5	0.0	-5.5	0.0	0.0	4.8	0.0	-0.0	-32.7	-32.7
587	527727.04	5511861.91	395.21	0	63	49.4	49.4	0.0	0.0	73.5	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-23.7	-23.7
588	527727.04	5511861.91	395.21	0	125	65.5	65.5	0.0	0.0	73.5	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-13.9	-13.9
589	527727.04	5511861.91	395.21	0	250	75.0	75.0	0.0	0.0	73.5	1.4	2.3	0.0	0.0	2.5	0.0	-0.0	-4.7	-4.7
590	527727.04	5511861.91	395.21	0	500	79.4	79.4	0.0	0.0	73.5	2.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-0.4	-0.4

Sample Calculation at facade of NR03

Line Source, ISO 9613, Name: "Haul Truck #3", ID: "Htruck3_o"																			
Nr.	X	Y	Z	RefI	Freq.	LxT	LxN	K0	Dc	Aadv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT	L

Line Source, ISO 9613, Name: "Haul Truck #3", ID: "Htruck3_o"																			
Nr.	X	Y	Z	Refl.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afof	Ahous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)	dB(A)
654	527497.67	5511788.52	396.10	0	1000	83.3	83.3	0.0	0.0	74.7	5.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-0.7	-0.7
655	527497.67	5511788.52	396.10	0	2000	83.5	83.5	0.0	0.0	74.7	14.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-9.8	-9.8
656	527497.67	5511788.52	396.10	0	4000	76.3	76.3	0.0	0.0	74.7	50.4	-1.1	0.0	0.0	4.8	0.0	-0.0	-52.5	-52.5
657	527497.67	5511788.52	396.10	0	8000	69.2	69.2	0.0	0.0	74.7	179.8	-1.1	0.0	0.0	4.8	0.0	-0.0	-189.0	-189.0
658	528261.55	5512253.61	400.19	0	32	38.1	38.1	0.0	0.0	72.0	0.0	-5.4	0.0	0.0	0.0	0.0	-0.0	-28.5	-28.5
659	528261.55	5512253.61	400.19	0	63	47.3	47.3	0.0	0.0	72.0	0.1	-5.4	0.0	0.0	0.0	0.0	-0.0	-19.4	-19.4
660	528261.55	5512253.61	400.19	0	125	63.4	63.4	0.0	0.0	72.0	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-14.3	-14.3
661	528261.55	5512253.61	400.19	0	250	72.9	72.9	0.0	0.0	72.0	1.2	2.3	0.0	0.0	0.0	0.0	-0.0	-2.5	-2.5
662	528261.55	5512253.61	400.19	0	500	77.3	77.3	0.0	0.0	72.0	2.2	-1.0	0.0	0.0	0.0	0.0	-0.0	4.2	4.2
663	528261.55	5512253.61	400.19	0	1000	80.5	80.5	0.0	0.0	72.0	4.1	-1.1	0.0	0.0	0.0	0.0	-0.0	5.5	5.5
664	528261.55	5512253.61	400.19	0	2000	80.7	80.7	0.0	0.0	72.0	10.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-1.0	-1.0
665	528261.55	5512253.61	400.19	0	4000	73.5	73.5	0.0	0.0	72.0	36.6	-1.1	0.0	0.0	0.0	0.0	-0.0	-34.0	-34.0
666	528261.55	5512253.61	400.19	0	8000	66.4	66.4	0.0	0.0	72.0	130.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-135.1	-135.1
667	527557.01	5511752.46	395.45	0	32	40.3	40.3	0.0	0.0	74.4	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-33.3	-33.3
668	527557.01	5511752.46	395.45	0	63	49.5	49.5	0.0	0.0	74.4	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-24.3	-24.3
669	527557.01	5511752.46	395.45	0	125	65.6	65.6	0.0	0.0	74.4	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-14.6	-14.6
670	527557.01	5511752.46	395.45	0	250	75.1	75.1	0.0	0.0	74.4	1.5	2.3	0.0	0.0	2.5	0.0	-0.0	-5.5	-5.5
671	527557.01	5511752.46	395.45	0	500	79.5	79.5	0.0	0.0	74.4	2.8	-1.1	0.0	0.0	4.8	0.0	-0.0	-1.4	-1.4
672	527557.01	5511752.46	395.45	0	1000	82.7	82.7	0.0	0.0	74.4	5.4	-1.1	0.0	0.0	4.8	0.0	-0.0	-0.7	-0.7
673	527557.01	5511752.46	395.45	0	2000	82.9	82.9	0.0	0.0	74.4	14.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-9.3	-9.3
674	527557.01	5511752.46	395.45	0	4000	75.7	75.7	0.0	0.0	74.4	48.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-50.5	-50.5
675	527557.01	5511752.46	395.45	0	8000	68.6	68.6	0.0	0.0	74.4	172.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-181.4	-181.4
676	527696.03	5511841.74	394.34	0	32	39.7	39.7	0.0	0.0	73.7	0.0	-5.5	0.0	0.0	4.8	0.0	-0.0	-33.4	-33.4
677	527696.03	5511841.74	394.34	0	63	48.9	48.9	0.0	0.0	73.7	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-24.3	-24.3
678	527696.03	5511841.74	394.34	0	125	65.0	65.0	0.0	0.0	73.7	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-14.6	-14.6
679	527696.03	5511841.74	394.34	0	250	74.5	74.5	0.0	0.0	73.7	1.4	2.3	0.0	0.0	2.5	0.0	-0.0	-5.4	-5.4
680	527696.03	5511841.74	394.34	0	500	78.9	78.9	0.0	0.0	73.7	2.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-1.2	-1.2
681	527696.03	5511841.74	394.34	0	1000	82.1	82.1	0.0	0.0	73.7	5.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-0.3	-0.3
682	527696.03	5511841.74	394.34	0	2000	82.3	82.3	0.0	0.0	73.7	13.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-8.3	-8.3
683	527696.03	5511841.74	394.34	0	4000	75.1	75.1	0.0	0.0	73.7	44.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-47.7	-47.7
684	527696.03	5511841.74	394.34	0	8000	68.0	68.0	0.0	0.0	73.7	159.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-168.7	-168.7
685	528091.48	5512239.50	401.24	0	32	38.4	38.4	0.0	0.0	72.8	0.0	-5.4	0.0	0.0	0.0	0.0	-0.0	-28.9	-28.9
686	528091.48	5512239.50	401.24	0	63	47.6	47.6	0.0	0.0	72.8	0.2	-5.4	0.0	0.0	0.0	0.0	-0.0	-19.9	-19.9
687	528091.48	5512239.50	401.24	0	125	63.7	63.7	0.0	0.0	72.8	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-14.8	-14.8
688	528091.48	5512239.50	401.24	0	250	73.2	73.2	0.0	0.0	72.8	1.3	2.3	0.0	0.0	0.0	0.0	-0.0	-3.1	-3.1
689	528091.48	5512239.50	401.24	0	500	77.6	77.6	0.0	0.0	72.8	2.4	-1.0	0.0	0.0	0.0	0.0	-0.0	3.6	3.6
690	528091.48	5512239.50	401.24	0	1000	80.8	80.8	0.0	0.0	72.8	4.5	-1.1	0.0	0.0	0.0	0.0	-0.0	4.7	4.7
691	528091.48	5512239.50	401.24	0	2000	81.0	81.0	0.0	0.0	72.8	11.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-2.5	-2.5
692	528091.48	5512239.50	401.24	0	4000	73.8	73.8	0.0	0.0	72.8	40.1	-1.1	0.0	0.0	0.0	0.0	-0.0	-38.0	-38.0
693	528091.48	5512239.50	401.24	0	8000	66.7	66.7	0.0	0.0	72.8	143.2	-1.1	0.0	0.0	0.0	0.0	-0.0	-148.1	-148.1
694	528115.69	5512242.58	401.91	0	32	38.3	38.3	0.0	0.0	72.6	0.0	-5.4	0.0	0.0	0.0	0.0	-0.0	-29.0	-29.0
695	528115.69	5512242.58	401.91	0	63	47.5	47.5	0.0	0.0	72.6	0.2	-5.4	0.0	0.0	0.0	0.0	-0.0	-19.9	-19.9
696	528115.69	5512242.58	401.91	0	125	63.6	63.6	0.0	0.0	72.6	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-14.9	-14.9
697	528115.69	5512242.58	401.91	0	250	73.1	73.1	0.0	0.0	72.6	1.3	2.3	0.0	0.0	0.0	0.0	-0.0	-3.1	-3.1
698	528115.69	5512242.58	401.91	0	500	77.5	77.5	0.0	0.0	72.6	2.3	-1.0	0.0	0.0	0.0	0.0	-0.0	3.5	3.5
699	528115.69	5512242.58	401.91	0	1000	80.7	80.7	0.0	0.0	72.6	4.4	-1.1	0.0	0.0	0.0	0.0	-0.0	4.7	4.7
700	528115.69	5512242.58	401.91	0	2000	80.9	80.9	0.0	0.0	72.6	11.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-2.4	-2.4
701	528115.69	5512242.58	401.91	0	4000	73.7	73.7	0.0	0.0	72.6	39.6	-1.1	0.0	0.0	0.0	0.0	-0.0	-37.5	-37.5
702	528115.69	5512242.58	401.91	0	8000	66.6	66.6	0.0	0.0	72.6	141.4	-1.1	0.0	0.0	0.0	0.0	-0.0	-146.4	-146.4
703	527911.78	5512171.96	403.00	0	32	38.7	38.7	0.0	0.0	73.4	0.0	-5.5	0.0	0.0	0.0	0.0	-0.0	-29.3	-29.3
704	527911.78	5512171.96	403.00	0	63	47.9	47.9	0.0	0.0	73.4	0.2	-5.5	0.0	0.0	0.0	0.0	-0.0	-20.3	-20.3
705	527911.78	5512171.96	403.00	0	125	64.0	64.0	0.0	0.0	73.4	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-15.3	-15.3
706	527911.78	5512171.96	403.00	0	250	73.5	73.5	0.0	0.0	73.4	1.4	2.3	0.0	0.0	0.0	0.0	-0.0	-3.6	-3.6
707	527911.78	5512171.96	403.00	0	500	77.9	77.9	0.0	0.0	73.4	2.5	-1.1	0.0	0.0	0.0	0.0	-0.0	3.0	3.0
708	527911.78	5512171.96	403.00	0	1000	81.1	81.1	0.0	0.0	73.4	4.8	-1.1	0.0	0.0	0.0	0.0	-0.0	3.9	3.9
709	527911.78	5512171.96	403.00	0	2000	81.3	81.3	0.0	0.0	73.4	12.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-3.8	-3.8
710	527911.78	5512171.96	403.00	0	4000	74.1	74.1	0.0	0.0	73.4	43.3	-1.1	0.0	0.0	0.0	0.0	-0.0	-41.6	-41.6
711	527911.78	5512171.96	403.00	0	8000	67.0	67.0	0.0	0.0	73.4	154.5	-1.1	0.0	0.0	0.0	0.0	-0.0	-159.8	-159.8
712	527873.92	5512160.13	402.92	0	32	38.8	38.8	0.0	0.0	73.6	0.0	-5.5	0.0	0.0	0.0	0.0	-0.0	-29.3	-29.3
713	527873.92	5512160.13	402.92	0	63	48.0	48.0	0.0	0.0	73.6	0.2	-5.5	0.0	0.0	0.0	0.0	-0.0	-20.3	-20.3
714	527873.92	5512160.13	402.92	0	125	64.1	64.1	0.0	0.0	73.6	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-15.3	-15.3
715	527873.92	5512160.13	402.92	0	250	73.6	73.6	0.0	0.0	73.6	1.4	2.3	0.0	0.0	0.0	0.0	-0.0	-3.7	-3.7
716	527873.92	5512160.13	402.92	0	500	78.0	78.0	0.0	0.0	73.6	2.6	-1.1	0.0	0.0	0.0	0.0	-0.0	2.9	2.9

Sample Calculation at facade of NR03

Line Source, ISO 9613, Name: "Haul Truck #3", ID: "Htruck3_o"																		
Nr.	X	Y	Z	Refl.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afof	Ahous	Abar	Cmet	RL	

Line Source, ISO 9613, Name: "Haul Truck #3", ID: "Htruck3_o"																			
Nr.	X	Y	Z	Refl.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)
780	527500.87	5511810.33	395.79	0	1000	80.9	80.9	0.0	0.0	74.8	5.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-3.1	-3.1
781	527500.87	5511810.33	395.79	0	2000	81.1	81.1	0.0	0.0	74.8	14.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-12.2	-12.2
782	527500.87	5511810.33	395.79	0	4000	73.9	73.9	0.0	0.0	74.8	50.5	-1.1	0.0	0.0	4.8	0.0	-0.0	-55.0	-55.0
783	527500.87	5511810.33	395.79	0	8000	66.8	66.8	0.0	0.0	74.8	180.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-191.7	-191.7
784	527992.92	5511874.84	401.40	0	32	35.6	35.6	0.0	0.0	71.8	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-30.9	-30.9
785	527992.92	5511874.84	401.40	0	63	44.8	44.8	0.0	0.0	71.8	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-21.8	-21.8
786	527992.92	5511874.84	401.40	0	125	60.9	60.9	0.0	0.0	71.8	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-16.7	-16.7
787	527992.92	5511874.84	401.40	0	250	70.4	70.4	0.0	0.0	71.8	1.2	2.3	0.0	0.0	0.0	0.0	-0.0	-4.9	-4.9
788	527992.92	5511874.84	401.40	0	500	74.8	74.8	0.0	0.0	71.8	2.1	-1.0	0.0	0.0	0.0	0.0	-0.0	1.9	1.9
789	527992.92	5511874.84	401.40	0	1000	78.0	78.0	0.0	0.0	71.8	4.0	-1.1	0.0	0.0	0.0	0.0	-0.0	3.2	3.2
790	527992.92	5511874.84	401.40	0	2000	78.2	78.2	0.0	0.0	71.8	10.6	-1.1	0.0	0.0	0.0	0.0	-0.0	-3.2	-3.2
791	527992.92	5511874.84	401.40	0	4000	71.0	71.0	0.0	0.0	71.8	36.0	-1.1	0.0	0.0	0.0	0.0	-0.0	-35.8	-35.8
792	527992.92	5511874.84	401.40	0	8000	63.9	63.9	0.0	0.0	71.8	128.6	-1.1	0.0	0.0	0.0	0.0	-0.0	-135.4	-135.4
793	527496.51	5511801.32	395.96	0	32	38.2	38.2	0.0	0.0	74.8	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-35.9	-35.9
794	527496.51	5511801.32	395.96	0	63	47.4	47.4	0.0	0.0	74.8	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-26.8	-26.8
795	527496.51	5511801.32	395.96	0	125	63.5	63.5	0.0	0.0	74.8	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-17.2	-17.2
796	527496.51	5511801.32	395.96	0	250	73.0	73.0	0.0	0.0	74.8	1.6	2.3	0.0	0.0	2.5	0.0	-0.0	-8.2	-8.2
797	527496.51	5511801.32	395.96	0	500	77.4	77.4	0.0	0.0	74.8	3.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-4.1	-4.1
798	527496.51	5511801.32	395.96	0	1000	80.6	80.6	0.0	0.0	74.8	5.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-3.5	-3.5
799	527496.51	5511801.32	395.96	0	2000	80.8	80.8	0.0	0.0	74.8	14.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-12.6	-12.6
800	527496.51	5511801.32	395.96	0	4000	73.6	73.6	0.0	0.0	74.8	50.5	-1.1	0.0	0.0	4.8	0.0	-0.0	-55.4	-55.4
801	527496.51	5511801.32	395.96	0	8000	66.5	66.5	0.0	0.0	74.8	180.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-192.2	-192.2
802	527996.94	5511877.67	401.18	0	32	34.9	34.9	0.0	0.0	71.8	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-31.6	-31.6
803	527996.94	5511877.67	401.18	0	63	44.1	44.1	0.0	0.0	71.8	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-22.5	-22.5
804	527996.94	5511877.67	401.18	0	125	60.2	60.2	0.0	0.0	71.8	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-17.3	-17.3
805	527996.94	5511877.67	401.18	0	250	69.7	69.7	0.0	0.0	71.8	1.2	2.3	0.0	0.0	0.0	0.0	-0.0	-5.6	-5.6
806	527996.94	5511877.67	401.18	0	500	74.1	74.1	0.0	0.0	71.8	2.1	-1.0	0.0	0.0	0.0	0.0	-0.0	1.2	1.2
807	527996.94	5511877.67	401.18	0	1000	77.3	77.3	0.0	0.0	71.8	4.0	-1.1	0.0	0.0	0.0	0.0	-0.0	2.6	2.6
808	527996.94	5511877.67	401.18	0	2000	77.5	77.5	0.0	0.0	71.8	10.6	-1.1	0.0	0.0	0.0	0.0	-0.0	-3.8	-3.8
809	527996.94	5511877.67	401.18	0	4000	70.3	70.3	0.0	0.0	71.8	36.0	-1.1	0.0	0.0	0.0	0.0	-0.0	-36.4	-36.4
810	527996.94	5511877.67	401.18	0	8000	63.2	63.2	0.0	0.0	71.8	128.3	-1.1	0.0	0.0	0.0	0.0	-0.0	-135.8	-135.8
811	528082.71	5511947.37	398.56	0	32	34.6	34.6	0.0	0.0	71.5	0.0	-5.3	0.0	0.0	4.8	0.0	-0.0	-36.4	-36.4
812	528082.71	5511947.37	398.56	0	63	43.8	43.8	0.0	0.0	71.5	0.1	-5.3	0.0	0.0	4.8	0.0	-0.0	-27.3	-27.3
813	528082.71	5511947.37	398.56	0	125	59.9	59.9	0.0	0.0	71.5	0.4	5.3	0.0	0.0	0.0	0.0	-0.0	-17.3	-17.3
814	528082.71	5511947.37	398.56	0	250	69.4	69.4	0.0	0.0	71.5	1.1	2.3	0.0	0.0	2.4	0.0	-0.0	-8.0	-8.0
815	528082.71	5511947.37	398.56	0	500	73.8	73.8	0.0	0.0	71.5	2.0	-1.0	0.0	0.0	4.8	0.0	-0.0	-3.5	-3.5
816	528082.71	5511947.37	398.56	0	1000	77.0	77.0	0.0	0.0	71.5	3.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-2.1	-2.1
817	528082.71	5511947.37	398.56	0	2000	77.2	77.2	0.0	0.0	71.5	10.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-8.2	-8.2
818	528082.71	5511947.37	398.56	0	4000	70.0	70.0	0.0	0.0	71.5	34.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-39.8	-39.8
819	528082.71	5511947.37	398.56	0	8000	62.9	62.9	0.0	0.0	71.5	123.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-135.6	-135.6
820	527579.41	5511759.88	395.47	0	32	37.3	37.3	0.0	0.0	74.2	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-36.2	-36.2
821	527579.41	5511759.88	395.47	0	63	46.5	46.5	0.0	0.0	74.2	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-27.2	-27.2
822	527579.41	5511759.88	395.47	0	125	62.6	62.6	0.0	0.0	74.2	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-17.5	-17.5
823	527579.41	5511759.88	395.47	0	250	72.1	72.1	0.0	0.0	74.2	1.5	2.3	0.0	0.0	2.5	0.0	-0.0	-8.4	-8.4
824	527579.41	5511759.88	395.47	0	500	76.5	76.5	0.0	0.0	74.2	2.8	-1.1	0.0	0.0	4.8	0.0	-0.0	-4.2	-4.2
825	527579.41	5511759.88	395.47	0	1000	79.7	79.7	0.0	0.0	74.2	5.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-3.5	-3.5
826	527579.41	5511759.88	395.47	0	2000	79.9	79.9	0.0	0.0	74.2	14.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-12.0	-12.0
827	527579.41	5511759.88	395.47	0	4000	72.7	72.7	0.0	0.0	74.2	47.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-52.8	-52.8
828	527579.41	5511759.88	395.47	0	8000	65.6	65.6	0.0	0.0	74.2	169.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-182.0	-182.0
829	528099.47	5511949.36	398.73	0	32	33.9	33.9	0.0	0.0	71.4	0.0	-5.3	0.0	0.0	0.0	0.0	-0.0	-32.2	-32.2
830	528099.47	5511949.36	398.73	0	63	43.1	43.1	0.0	0.0	71.4	0.1	-5.3	0.0	0.0	0.0	0.0	-0.0	-23.1	-23.1
831	528099.47	5511949.36	398.73	0	125	59.2	59.2	0.0	0.0	71.4	0.4	5.2	0.0	0.0	0.0	0.0	-0.0	-17.9	-17.9
832	528099.47	5511949.36	398.73	0	250	68.7	68.7	0.0	0.0	71.4	1.1	2.3	0.0	0.0	0.0	0.0	-0.0	-6.1	-6.1
833	528099.47	5511949.36	398.73	0	500	73.1	73.1	0.0	0.0	71.4	2.0	-1.0	0.0	0.0	0.0	0.0	-0.0	-0.7	-0.7
834	528099.47	5511949.36	398.73	0	1000	76.3	76.3	0.0	0.0	71.4	3.8	-1.1	0.0	0.0	0.0	0.0	-0.0	2.1	2.1
835	528099.47	5511949.36	398.73	0	2000	76.5	76.5	0.0	0.0	71.4	10.1	-1.1	0.0	0.0	0.0	0.0	-0.0	-3.9	-3.9
836	528099.47	5511949.36	398.73	0	4000	69.3	69.3	0.0	0.0	71.4	34.1	-1.1	0.0	0.0	0.0	0.0	-0.0	-35.2	-35.2
837	528099.47	5511949.36	398.73	0	8000	62.2	62.2	0.0	0.0	71.4	121.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-129.9	-129.9
838	527717.82	5511857.12	394.08	0	32	35.8	35.8	0.0	0.0	73.6	0.0	-5.5	0.0	0.0	4.8	0.0	-0.0	-37.1	-37.1
839	527717.82	5511857.12	394.08	0	63	45.0	45.0	0.0	0.0	73.6	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-28.1	-28.1
840	527717.82	5511857.12	394.08	0	125	61.1	61.1	0.0	0.0	73.6	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-18.3	-18.3
841	527717.82	5511857.12	394.08	0	250	70.6	70.6	0.0	0.0	73.6	1.4	2.3	0.0	0.0	2.5	0.0	-0.0	-9.2	-9.2
842	527717.82	5511857.12	394.08	0	500	75.0	75.0	0.0	0.0	73.6	2.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-4.9	-4.9

Sample Calculation at facade of NR03

Line Source, ISO 9613, Name: "Haul Truck #3", ID: "Htruck3_o"																		
Nr.	X	Y	Z	Refl.	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT

Line Source, ISO 9613, Name: "Haul Truck #3", ID: "Htruck3_o"																			
Nr.	X	Y	Z	Refl	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr	Afol	Ahous	Abar	Cmet	RL	LrT	LrN
	(m)	(m)	(m)		(Hz)	dB(A)	dB(A)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	(dB)	dB(A)	dB(A)
906	527903.31	5512169.31	403.34	0	1000	73.9	73.9	0.0	0.0	73.5	4.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-3.3	-3.3
907	527903.31	5512169.31	403.34	0	2000	74.1	74.1	0.0	0.0	73.5	12.8	-1.1	0.0	0.0	0.0	0.0	-0.0	-11.0	-11.0
908	527903.31	5512169.31	403.34	0	4000	66.9	66.9	0.0	0.0	73.5	43.5	-1.1	0.0	0.0	0.0	0.0	-0.0	-48.9	-48.9
909	527903.31	5512169.31	403.34	0	8000	59.8	59.8	0.0	0.0	73.5	155.1	-1.1	0.0	0.0	0.0	0.0	-0.0	-167.6	-167.6
910	527504.07	5511815.57	395.68	0	32	31.6	31.6	0.0	0.0	74.7	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-42.5	-42.5
911	527504.07	5511815.57	395.68	0	63	40.8	40.8	0.0	0.0	74.7	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-33.4	-33.4
912	527504.07	5511815.57	395.68	0	125	56.9	56.9	0.0	0.0	74.7	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-23.8	-23.8
913	527504.07	5511815.57	395.68	0	250	66.4	66.4	0.0	0.0	74.7	1.6	2.3	0.0	0.0	2.5	0.0	-0.0	-14.8	-14.8
914	527504.07	5511815.57	395.68	0	500	70.8	70.8	0.0	0.0	74.7	3.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-10.7	-10.7
915	527504.07	5511815.57	395.68	0	1000	74.0	74.0	0.0	0.0	74.7	5.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-10.1	-10.1
916	527504.07	5511815.57	395.68	0	2000	74.2	74.2	0.0	0.0	74.7	14.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-19.1	-19.1
917	527504.07	5511815.57	395.68	0	4000	67.0	67.0	0.0	0.0	74.7	50.4	-1.1	0.0	0.0	4.8	0.0	-0.0	-61.9	-61.9
918	527504.07	5511815.57	395.68	0	8000	59.9	59.9	0.0	0.0	74.7	179.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-198.4	-198.4
919	527623.35	5511779.62	394.29	0	32	30.0	30.0	0.0	0.0	74.0	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-43.3	-43.3
920	527623.35	5511779.62	394.29	0	63	39.2	39.2	0.0	0.0	74.0	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-34.2	-34.2
921	527623.35	5511779.62	394.29	0	125	55.3	55.3	0.0	0.0	74.0	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-24.6	-24.6
922	527623.35	5511779.62	394.29	0	250	64.8	64.8	0.0	0.0	74.0	1.5	2.3	0.0	0.0	2.5	0.0	-0.0	-15.4	-15.4
923	527623.35	5511779.62	394.29	0	500	69.2	69.2	0.0	0.0	74.0	2.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-11.2	-11.2
924	527623.35	5511779.62	394.29	0	1000	72.4	72.4	0.0	0.0	74.0	5.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-10.4	-10.4
925	527623.35	5511779.62	394.29	0	2000	72.6	72.6	0.0	0.0	74.0	13.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-18.7	-18.7
926	527623.35	5511779.62	394.29	0	4000	65.4	65.4	0.0	0.0	74.0	46.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-58.6	-58.6
927	527623.35	5511779.62	394.29	0	8000	58.3	58.3	0.0	0.0	74.0	165.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-184.6	-184.6
928	528162.71	5512248.55	400.49	0	32	28.4	28.4	0.0	0.0	72.4	0.0	-5.4	0.0	0.0	0.0	0.0	-0.0	-38.7	-38.7
929	528162.71	5512248.55	400.49	0	63	37.6	37.6	0.0	0.0	72.4	0.1	-5.4	0.0	0.0	0.0	0.0	-0.0	-29.6	-29.6
930	528162.71	5512248.55	400.49	0	125	53.7	53.7	0.0	0.0	72.4	0.5	5.3	0.0	0.0	0.0	0.0	-0.0	-24.5	-24.5
931	528162.71	5512248.55	400.49	0	250	63.2	63.2	0.0	0.0	72.4	1.2	2.3	0.0	0.0	0.0	0.0	-0.0	-12.8	-12.8
932	528162.71	5512248.55	400.49	0	500	67.6	67.6	0.0	0.0	72.4	2.3	-1.0	0.0	0.0	0.0	0.0	-0.0	-6.0	-6.0
933	528162.71	5512248.55	400.49	0	1000	70.8	70.8	0.0	0.0	72.4	4.3	-1.1	0.0	0.0	0.0	0.0	-0.0	-4.8	-4.8
934	528162.71	5512248.55	400.49	0	2000	71.0	71.0	0.0	0.0	72.4	11.4	-1.1	0.0	0.0	0.0	0.0	-0.0	-11.7	-11.7
935	528162.71	5512248.55	400.49	0	4000	63.8	63.8	0.0	0.0	72.4	38.7	-1.1	0.0	0.0	0.0	0.0	-0.0	-46.2	-46.2
936	528162.71	5512248.55	400.49	0	8000	56.7	56.7	0.0	0.0	72.4	138.0	-1.1	0.0	0.0	0.0	0.0	-0.0	-152.6	-152.6
937	527523.55	5511818.41	395.26	0	32	30.3	30.3	0.0	0.0	74.6	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-43.6	-43.6
938	527523.55	5511818.41	395.26	0	63	39.5	39.5	0.0	0.0	74.6	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-34.6	-34.6
939	527523.55	5511818.41	395.26	0	125	55.6	55.6	0.0	0.0	74.6	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-25.0	-25.0
940	527523.55	5511818.41	395.26	0	250	65.1	65.1	0.0	0.0	74.6	1.6	2.3	0.0	0.0	2.5	0.0	-0.0	-15.9	-15.9
941	527523.55	5511818.41	395.26	0	500	69.5	69.5	0.0	0.0	74.6	2.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-11.8	-11.8
942	527523.55	5511818.41	395.26	0	1000	72.7	72.7	0.0	0.0	74.6	5.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-11.2	-11.2
943	527523.55	5511818.41	395.26	0	2000	72.9	72.9	0.0	0.0	74.6	14.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-20.1	-20.1
944	527523.55	5511818.41	395.26	0	4000	65.7	65.7	0.0	0.0	74.6	49.8	-1.1	0.0	0.0	4.8	0.0	-0.0	-62.4	-62.4
945	527523.55	5511818.41	395.26	0	8000	58.6	58.6	0.0	0.0	74.6	177.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-197.4	-197.4
946	527600.30	5511769.27	394.91	0	32	29.0	29.0	0.0	0.0	74.1	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-44.4	-44.4
947	527600.30	5511769.27	394.91	0	63	38.2	38.2	0.0	0.0	74.1	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-35.3	-35.3
948	527600.30	5511769.27	394.91	0	125	54.3	54.3	0.0	0.0	74.1	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-25.7	-25.7
949	527600.30	5511769.27	394.91	0	250	63.8	63.8	0.0	0.0	74.1	1.5	2.3	0.0	0.0	2.5	0.0	-0.0	-16.6	-16.6
950	527600.30	5511769.27	394.91	0	500	68.2	68.2	0.0	0.0	74.1	2.8	-1.1	0.0	0.0	4.8	0.0	-0.0	-12.4	-12.4
951	527600.30	5511769.27	394.91	0	1000	71.4	71.4	0.0	0.0	74.1	5.2	-1.1	0.0	0.0	4.8	0.0	-0.0	-11.6	-11.6
952	527600.30	5511769.27	394.91	0	2000	71.6	71.6	0.0	0.0	74.1	13.9	-1.1	0.0	0.0	4.8	0.0	-0.0	-20.0	-20.0
953	527600.30	5511769.27	394.91	0	4000	64.4	64.4	0.0	0.0	74.1	47.0	-1.1	0.0	0.0	4.8	0.0	-0.0	-60.3	-60.3
954	527600.30	5511769.27	394.91	0	8000	57.3	57.3	0.0	0.0	74.1	167.6	-1.1	0.0	0.0	4.8	0.0	-0.0	-188.0	-188.0
955	527575.52	5511758.12	395.57	0	32	25.9	25.9	0.0	0.0	74.3	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-47.7	-47.7
956	527575.52	5511758.12	395.57	0	63	35.1	35.1	0.0	0.0	74.3	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-38.6	-38.6
957	527575.52	5511758.12	395.57	0	125	51.2	51.2	0.0	0.0	74.3	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-29.0	-29.0
958	527575.52	5511758.12	395.57	0	250	60.7	60.7	0.0	0.0	74.3	1.5	2.3	0.0	0.0	2.5	0.0	-0.0	-19.9	-19.9
959	527575.52	5511758.12	395.57	0	500	65.1	65.1	0.0	0.0	74.3	2.8	-1.1	0.0	0.0	4.8	0.0	-0.0	-15.7	-15.7
960	527575.52	5511758.12	395.57	0	1000	68.3	68.3	0.0	0.0	74.3	5.3	-1.1	0.0	0.0	4.8	0.0	-0.0	-15.0	-15.0
961	527575.52	5511758.12	395.57	0	2000	68.5	68.5	0.0	0.0	74.3	14.1	-1.1	0.0	0.0	4.8	0.0	-0.0	-23.5	-23.5
962	527575.52	5511758.12	395.57	0	4000	61.3	61.3	0.0	0.0	74.3	47.7	-1.1	0.0	0.0	4.8	0.0	-0.0	-64.3	-64.3
963	527575.52	5511758.12	395.57	0	8000	54.2	54.2	0.0	0.0	74.3	170.1	-1.1	0.0	0.0	4.8	0.0	-0.0	-193.8	-193.8
964	527575.80	5511758.25	395.56	0	32	15.0	15.0	0.0	0.0	74.3	0.1	-5.5	0.0	0.0	4.8	0.0	-0.0	-58.6	-58.6
965	527575.80	5511758.25	395.56	0	63	24.2	24.2	0.0	0.0	74.3	0.2	-5.5	0.0	0.0	4.8	0.0	-0.0	-49.5	-49.5
966	527575.80	5511758.25	395.56	0	125	40.3	40.3	0.0	0.0	74.3	0.6	5.3	0.0	0.0	0.0	0.0	-0.0	-39.8	-39.8
967	527575.80	5511758.25	395.56	0	250	49.8	49.8	0.0	0.0	74.3	1.5	2.3	0.0	0.0	2.5	0.0	-0.0	-30.7	-30.7
968	527575.80	5511758.25	395.56	0	500	54.2	54.2	0.0	0.0	74.3	2.8	-1.1	0.0	0.0	4.8	0.0	-0.0	-26.6	-26.6

Line Source, ISO 9613, Name: "Haul Truck #3", ID: "Htruck3_o"																
Nr.	X	Y	Z	Refl	Freq.	LxT	LxN	K0	Dc	Adiv	Aatm	Agr				



Treasury Metals  
Revised EIS Report  
Goliath Gold Project  
August 2017



## **APPENDIX H-4**

### **ENVIRONMENTAL NOISE ASSESSMENT**



CONSULTING ENGINEERS  
& SCIENTISTS

Tel: 519.823.1311  
Fax: 519.823.1316

RWDI AIR Inc.  
650 Woodlawn Road West  
Guelph, Ontario, Canada  
N1K 1B8



## Treasury Metals Inc. – Goliath Gold Project Wabigoon, Ontario

# Final Report

## Environmental Noise Assessment

RWDI #1401701  
October 16, 2014

### SUBMITTED TO:

**Mark Wheeler, P.Eng.**  
Senior Mining Engineer

**Treasury Metals Incorporated**  
130 King Street West  
Suite 3680  
P.O. Box 99, The Exchange Tower  
Toronto, ON M5X 1B1

### SUBMITTED BY:

**Melissa Annett, d.E.T.**  
Project Manager / Associate  
[melissa.annett@rwdi.com](mailto:melissa.annett@rwdi.com)

**John DeYoe, B.A., d.E.T.**  
Senior Specialist / Principal  
[john.deyoe@rwdi.com](mailto:john.deyoe@rwdi.com)

**Kyle Hellewell, P.Eng.**  
Senior Engineer  
[kyle.hellewell@rwdi.com](mailto:kyle.hellewell@rwdi.com)

**Khalid Hussein, B.Eng.**  
Project Scientist  
[khalid.hussein@rwdi.com](mailto:khalid.hussein@rwdi.com)

This document is intended for the sole use of the party to whom it is addressed and may contain information that is privileged and/or confidential. If you have received this in error, please notify us immediately.

© RWDI name and logo are registered trademarks in Canada and the United States of America



CONSULTING ENGINEERS  
& SCIENTISTS

Treasury Metals Inc. – Goliath Gold Project  
Noise Assessment  
RWDI #1401701  
October 16, 2014

## EXECUTIVE SUMMARY

---

Treasury Metals Inc. retained RWDI AIR Inc. (RWDI) to complete an environmental noise assessment in support of the Goliath Gold Project (the Project). The Project is a proposed gold mine near Wabigoon, Ontario. This report assesses anticipated noise emissions from the mine against the applicable criteria.

As a federal Environmental Assessment, noise guidelines developed by Health Canada for Environmental Assessments are applicable. As a development in the province of Ontario, the Ministry of Environment and Climate Change noise criteria are also applicable.

Modelling inputs include source type and locations, and sound levels. Source types and locations were taken from information provided in the Goliath Gold project description, and from Treasury Metals personnel. Sound levels were taken from information on file at RWDI, or were calculated based on equipment specifications. At this early stage of development, information can be limited therefore, where necessary, modelling has been conducted using sound levels for typical sources at a mine.

Noise sensitive receptors identified in the area are houses (seasonal or otherwise). Forty-four individual receptors were identified. Noise modelling software was used to predict the effects of the Project at the nearest receptors, representing the worst case (loudest) impacts.

In some circumstances, sound levels of specific sources were found to cause noncompliance at noise sensitive receptors. Quieter than average equipment will be required for some pieces to achieve compliance. This equipment is commercially available. Treasury Metals has committed to ensuring that sound levels from these pieces of equipment meet these requirements.

Based on the commitment described above to limit sound levels of certain equipment, the Goliath Gold Project is predicted to be in compliance with both the Health Canada and Ministry of Environment and Climate Change guidelines at all receptors.





CONSULTING ENGINEERS  
& SCIENTISTS

Treasury Metals Inc. – Goliath Gold Project  
Noise Assessment  
RWDI #1401701  
October 16, 2014

## TABLE OF CONTENTS

---

<b>1. INTRODUCTION.....</b>	<b>1</b>
1.1 Overview .....	1
1.1.1 Noise Considerations .....	1
1.1.2 Regional Setting .....	1
1.1.2.1 Local Study Area .....	1
<b>2. VALUED COMPONENTS.....</b>	<b>2</b>
2.1 Selected Valued Components and Indicators.....	2
2.1.1 Noise Metrics & Magnitude of Effects .....	2
2.1.2 Duration & Reversibility .....	5
2.1.3 Direction .....	5
2.1.4 Frequency and Timing.....	5
<b>3. STUDY METHODOLOGY .....</b>	<b>5</b>
3.1 Baseline Study .....	5
3.2 Data Collection .....	5
3.3 Modelling .....	5
3.3.1 Continuous Sources (ISO-9316) .....	5
3.3.2 Blasting.....	6
3.4 Evaluation of Impacts.....	7
<b>4. ASSESSMENT CRITERIA .....</b>	<b>8</b>
4.1 Ministry of Environment and Climate Change Guidelines .....	8
4.1.1 Continuous Sources .....	8
4.1.1.1 Points of Reception.....	8
4.1.1.2 Evaluation Criteria .....	10
4.1.1.3 Sound Quality Adjustments .....	10
4.1.2 Blasting.....	10
4.1.2.1 Points of Reception.....	11
4.1.2.2 Evaluation Criteria .....	11
4.2 Health Canada Noise Guidelines .....	11
4.2.1 Continuous Sources .....	11
4.2.1.1 Points of Reception.....	11
4.2.1.2 Evaluation Criteria .....	11
4.2.2 Blasting.....	12
<b>5. BASELINE STUDIES .....</b>	<b>12</b>
5.1 Baseline Monitoring Locations .....	12
5.2 Noise Environment.....	14
5.2.1 Temporal Variation .....	15
5.3 Applicability .....	15
<b>6. CONSTRUCTION AND SITE PREPARATION PHASE .....</b>	<b>15</b>
6.1 Description of Continuous Operations .....	15
6.2 Noise Source Summary .....	16



CONSULTING ENGINEERS  
& SCIENTISTS

Treasury Metals Inc. – Goliath Gold Project  
Noise Assessment  
RWDI #1401701  
October 16, 2014

6.2.1	Continuous Sources .....	16
6.2.2	Blasting .....	17
6.3	Predicted Sound Levels .....	17
6.3.1	Assessment to MOECC Guidelines .....	18
6.3.1.1	Continuous Sources .....	18
6.3.1.2	Blasting .....	19
6.3.2	Assessment to Health Canada Guidelines .....	20
6.4	Mitigation .....	20
6.5	Residual Effects .....	21
6.6	Conclusions .....	21
<b>7.</b>	<b>OPERATIONS PHASE .....</b>	<b>21</b>
7.1	Description of Continuous Operations .....	21
7.2	Noise Source Summary .....	22
7.2.1	Continuous Sources .....	22
7.2.2	Blasting .....	23
7.3	Predicted Sound Levels .....	24
7.3.1	Assessment to MOECC Guidelines .....	24
7.3.1.1	Continuous Sources .....	24
7.3.1.2	Blasting .....	26
7.3.2	Assessment to Health Canada Guidelines .....	26
7.4	Mitigation .....	27
7.5	Residual Effects .....	27
7.6	Conclusions .....	28
<b>8.</b>	<b>CLOSURE, DECOMMISSIONING AND RESTORATION PHASE .....</b>	<b>28</b>
8.1	Description of Continuous Operations .....	28
8.2	Noise Source Summary .....	28
8.3	Predicted Sound Levels .....	30
8.3.1	Assessment to MOECC Guidelines .....	31
8.3.2	Assessment to Health Canada Guidelines .....	32
8.4	Mitigation .....	33
8.5	Residual Effects .....	33
8.6	Conclusions .....	34
<b>9.</b>	<b>UNCERTAINTY .....</b>	<b>34</b>
<b>10.</b>	<b>MONITORING .....</b>	<b>34</b>
<b>11.</b>	<b>SUMMARY AND CONCLUSIONS .....</b>	<b>35</b>
<b>12.</b>	<b>REFERENCES .....</b>	<b>36</b>



CONSULTING ENGINEERS  
& SCIENTISTS

Treasury Metals Inc. – Goliath Gold Project  
Noise Assessment  
RWDI #1401701  
October 16, 2014

## Tables

---

Table 1: Valued Components .....	2
Table 2: Typical Sound Levels of Common Noise Sources.....	4
Table 3: Parameters Used in ISO-9613 Modelling .....	6
Table 4: Baseline Study Results .....	15
Table 5: Modelled Noise Sources for the Construction and Site Preparation Phase .....	16
Table 6: Assessment of Construction and Site Preparation Noise to MOECC Guidelines .....	19
Table 7: Predicted Sound Levels from Blasting .....	19
Table 8: Assessment of Construction and Site Preparation Noise to HC Guidelines .....	20
Table 9: Modelled Noise Sources for the Operations Phase.....	22
Table 10: Assessment of Operating Phase Noise to MOECC Guidelines .....	25
Table 11: Assessment of Operating Phase Generator Testing Noise to MOECC Guidelines .....	25
Table 12: Predicted Sound Levels from Blasting .....	26
Table 13: Assessment of Operating Noise to HC Guidelines .....	27
Table 14: Modelled Noise Sources for the Closure, Decommissioning and Restoration Phase.....	29
Table 15: Assessment of Closure, Decommissioning and Restoration Noise to MOECC Guidelines .....	32
Table 16: Assessment of Closure, Decommissioning and Restoration Noise to HC Guidelines .....	33

## Figures

---

Figure 1: Noise Sensitive Receptor Locations .....	9
Figure 2: Baseline Monitoring Locations, Winter 2011 .....	13
Figure 3: Baseline Monitoring Locations, Summer 2013 .....	14
Figure 4: Source Locations, Construction and Site Preparation Phase .....	17
Figure 5: Predicted Sound Levels, Construction and Site Preparation Phase .....	18
Figure 6: Source Locations, Operations Phase .....	23
Figure 7: Predicted Sound Levels, Operations Phase .....	24
Figure 8: Source Locations, Decommissioning and Restoration Phase.....	30
Figure 9: Predicted Sound Levels, Closure, Decommissioning and Restoration Phase .....	31

## Appendices

---

- Appendix A: Glossary of Environmental Noise Terminology
- Appendix B: Modelling Output Files and Calculations



CONSULTING ENGINEERS  
& SCIENTISTS

## 1. INTRODUCTION

---

### 1.1 Overview

Treasury Metals Incorporated (Treasury) has been exploring and developing the Thunder Lake Gold deposit known as the Goliath Gold Project (the Project), located near Dryden, Ontario. The Project involves the construction, operation, closure, and reclamation of a 4.5 million tonne-per-annum (Mt/a) open pit and underground mine that will operate for 12 years. This report focuses on the environmental noise emissions over the life of the project, and is intended to support the federal Environmental Assessment process.

#### 1.1.1 Noise Considerations

The Project is located in a rural area of Northern Ontario and is not near any existing sources of industrial noise. The Goliath Gold Project will add new sources of noise to the area. Noise has the potential to affect wildlife species and human receptors in the nearby environment. This assessment addresses human impacts, and provides a quantitative evaluation of noise effects which can be used to understand the magnitude of effects on wildlife species in the vicinity of the project.

This report identifies the existing noise environment in the project area and describes the potential impacts of the Project. The potential effects associated with the development of the mine were evaluated and compared to both the Health Canada and Ministry of the Environment and Climate Change guidelines (HC, 2011 and MOE, 2013).

This assessment concentrates on comparisons with guideline limits and impacts on human receptors. The effects of potential noise and vibration impacts on other biophysical components, including wildlife, vegetation and human health are addressed separately by the appropriate disciplines.

#### 1.1.2 Regional Setting

The Project is located in northwestern Ontario, approximately 125 kilometers (km) east of the City of Kenora, 20 km east of the City of Dryden and 325 km northwest of the City of Thunder Bay. The total area of the Project is 4,991 hectares (50 km<sup>2</sup>) covering portions of Hartman and Zealand townships east of the city of Dryden, Ontario. The Project is located approximately 3 km north of the Trans-Canada Highway, and is accessible by road.

##### 1.1.2.1 Local Study Area

The Local Study Area was selected to represent areas where noise impacts associated with the project are likely to occur. In practice, noise impacts from a project of this magnitude are anticipated to be negligible at distances 1.5 km and greater from the nearest active project area. The study therefore focuses on areas within 1.5 km of the main features of the mine; namely the open pit mine, mill, vent raises, stockpiles, and haul truck routes.



## 2. VALUED COMPONENTS

### 2.1 Selected Valued Components and Indicators

High levels of environmental noise can affect people by impairing their enjoyment of using the land. High noise levels can also affect wildlife, causing changes in behaviour or avoidance of affected areas, for at least temporary periods of time. Environmental sound levels are therefore a Valued Component (VC) selected for study.

**Table 1:** Valued Components

VC	Reason for Selection of VC	Indicator
Environmental sound levels	Minimize effects on human dwellings within the region Minimize disturbance of natural terrestrial wildlife use patterns in the region	A-Weighted Sound Levels ( $L_{EQ}$ dBA) Increase in Percent Highly Annoyed as a result of changing sound levels

#### 2.1.1 Noise Metrics & Magnitude of Effects

Environmental sound levels vary continuously over time. To account for both daily and short-term variations in sound levels, several single numerical descriptors have been developed based on large-scale psycho-acoustic studies of annoyance with environmental noise. These allow sound monitoring to be conducted for a constantly varying sound environment over an extended period, with the results described as a single number that accurately describes the environment. Terms relating to environmental noise are defined in Appendix A.

The single number descriptor commonly used in most international standards for environmental sound measurements is the energy equivalent sound level ( $L_{EQ}$ ). The  $L_{EQ}$  value, expressed in dBA, is the energy-averaged, A-weighted sound level for the complete measurement interval. It is the steady, continuous sound level over a given period that has the same acoustic energy as the actual varying sound levels occurring over the same period in the measured environment. The  $L_{EQ}$  is one of the most common and useful predictors of human response to noise, and is the noise descriptor that is used in the majority of environmental noise criteria. The A-weighting accounts for the frequency content of the measured sound based on a frequency response similar to that heard by the human ear.

Another single metric descriptor which inherently accounts for additional noise sensitivity during nighttime hours is the DNL or  $L_{DN}$ . The  $L_{DN}$  is a 24-hour  $L_{EQ}$ , where 10 dB is added (arithmetically) to the nighttime sound levels during the hours of 2200h to 0700h.



CONSULTING ENGINEERS  
& SCIENTISTS

The  $L_{EQ}$  can be used to calculate another metric known as Percent Highly Annoyed. High annoyance is a widely accepted indicator of human health effects resulting from exposure to environmental noise. Of particular interest is the change in Percent Highly Annoyed resulting from increases in environmental noise from The Project. There is a non-linear relationship between Percent Highly Annoyed and  $L_{EQ}$ . As a result, a project in a relatively quiet environment will not increase the Percent Highly Annoyed as much as the same project in a relatively noisy environment.

The descriptors specific to this study are:

- the 15-hour A-weighted energy equivalent sound level,  $L_D$  or  $L_{EQ}$  (day, 15), referred to as the daytime sound level;
- the 9-hour A-weighted energy equivalent sound level,  $L_N$  or  $L_{EQ}$  (night, 9), referred to as the nighttime sound level;
- the 1-hour A-weighted energy equivalent sound level,  $L_{EQ}$  (1), referred to as the hourly sound level
- the 24-hour time-weighted energy equivalent sound level, DNL or  $L_{DN}$ ; and
- the change in Percent Highly Annoyed.

For reference, ranges of typical sound levels are presented in Table 2.



CONSULTING ENGINEERS  
& SCIENTISTS

**Table 2:** Typical Sound Levels of Common Noise Sources

Sound Level	dBA	Common Noise Sources
<b>Deafening</b>	<b>120</b>	Threshold of pain
	115	Maximum noise level at a hard rock concert
	<b>110</b>	Accelerating motorcycle at 1 m
	105	Loud auto horn at 3 m
<b>Very Loud</b>	<b>100</b>	Dance club; Maximum human vocal output at 1 m
	95	Jackhammer at 15 m
	<b>90</b>	Inside a noisy factory
	85	Heavy truck pass-by at 15 m
<b>Loud</b>	<b>80</b>	School cafeteria; Noisy bar
	75	Near edge of major highway; Inside automobile travelling at 60 km/h
	<b>70</b>	Vacuum cleaner at 1.5 m
	65	Normal human speech, i.e., an un-raised voice, at 1 m
<b>Moderate</b>	<b>60</b>	Typical background noise levels in a large department store; Hair dryer
	55	Running tap water
	<b>50</b>	Clothes dryer; Air conditioner
	45	Typical background noise level in an office caused by HVAC; Flowing stream; MOECC guideline for daytime & evening noise in a rural setting
<b>Faint</b>	<b>40</b>	Typical background noise level in a library; MOECC guideline for nighttime noise in a rural setting
	35	Average whisper; Typical quiet outdoors
	<b>30</b>	Broadcast studio
	25	
<b>Very Faint</b>	<b>20</b>	Deep woods on a calm day
	15	
	<b>10</b>	
	5	Human breathing
	<b>0</b>	Threshold of hearing, i.e., quietest sound that can be heard





CONSULTING ENGINEERS  
& SCIENTISTS

### **2.1.2 Duration & Reversibility**

Noise is temporary in nature, and stops when the source ceases to exist. Noise itself has no long-term presence and the acoustic environment will revert to a natural state with no intervention required.

### **2.1.3 Direction**

Noise sources are directional in nature, and the directivity of a source is accounted for where appropriate in modelling. Overall, there is minimal directivity effect from the entire site due to the large number of noise sources which will collectively emit noise in all directions.

### **2.1.4 Frequency and Timing**

Noise will be emitted throughout the life of the project, when any activities take place. Noise is therefore considered to be frequent, and continuous.

## **3. STUDY METHODOLOGY**

---

### **3.1 Baseline Study**

A baseline study was conducted in the winter of 2011 and the summer of 2013. Three sites were monitored in 2013 and one site in 2011. Further details are provided in section 5. Data from the baseline study is used to determine the appropriate sound level limits resulting from the existing natural environment sound levels.

### **3.2 Data Collection**

Best-available data regarding future construction, operations, and decommissioning were collected from Treasury Metals, and used to predict sound levels for the Project. The basis for model inputs was primarily obtained from the project description (Treasury, 2012). Further information was gathered from Treasury through from May, June, and July 2014. Equipment sizes for sources such as the excavators and bulldozers have not yet been defined. Therefore, sizes were estimated from production levels and sound levels were predicted using numerical modelling techniques, or taken from manufacturer data for typical equipment. Where limited data was available on equipment, typical levels were selected from the RWDI library.

### **3.3 Modelling**

#### **3.3.1 Continuous Sources (ISO-9316)**

Modelling of sound level propagation for continuous sources to the receptors was conducted using Cadna/A, a commercially available implementation of the ISO 9613 (ISO, 1994b and ISO, 1996) algorithms. Cadna/A is produced by Datakustik GmbH. The modelling took into account the following factors:

- Source sound power level and directivity;



CONSULTING ENGINEERS  
& SCIENTISTS

- Distance attenuation;
- Source-receptor geometry including heights, elevations and topography;
- Barrier effects of the site and surrounding buildings;
- Duration of events;
- Ground and air (atmospheric) attenuation; and
- Meteorological effects on sound propagation.

The ISO-9613 algorithms are the current international standard for airborne sound propagation, and are widely used in noise impact assessments in Ontario and Canadian jurisdictions. Modelling parameters have been selected to conform to the preferred parameters of the Ministry of Environment and Climate Change (MOECC). These parameters introduce some additional conservatism to the modelling beyond that which would be achieved with strict conformance to the ISO standard, meaning that sound levels are predicted to be slightly higher than they otherwise would be. Parameters used in the modelling are presented in Table 3.

**Table 3:** Parameters Used in ISO-9613 Modelling

Parameter	Model Settings	Description/Notes
Calculation Standard	ISO-9613	All sources and attenuators are treated as required by the cited standard
Source Directivity	Directivities applied	Applied to stationary sources with significant directivity.
Ground Absorption	0.8 (index value 0 to 1)	Area outside project infrastructure is primarily soft ground and occasional hard ground.
Temperature/Humidity	10°C/70% Relative Humidity	Average conditions for area
Wind Conditions	Default ISO-9613	The propagation conditions in the ISO (1996) standard are valid for wind speeds between 4 and 18 km/h; all points are considered downwind
	ISO 1996 – moderate inversion condition	
Terrain	Terrain applied	Terrain in the area is modelled at 10 m resolution to account for any natural barriers within the noise study area
Reflections	0	No significant reflections from buildings on site

### 3.3.2 Blasting

Modelling of blasting sound levels was conducted using numerical modelling techniques presented in the International Society of Explosives Engineers Blaster’s Handbook (ISEE, 2011). Airborne vibration due to blasting activities attenuates from a site at a slower rate than ground vibrations. The distribution of this air vibration energy from a blast is also strongly influenced by the prevailing weather conditions during the blast. Other factors influencing airborne vibration propagation include:



CONSULTING ENGINEERS  
& SCIENTISTS

- charge-weight per delay;
- depth of burial;
- volume of displaced rock;
- delay time intervals;
- type of explosive;
- atmospheric conditions; and,
- topography.

Further definition of these terms is provided in Appendix A.

The rate at which blast noise decays or attenuates from a blast site is dependent upon the scaled distance as follows:

- scaled distance ( $SD_3$ ) =  $R / \sqrt[3]{W}$ 
  - where R = distance (metres) from the blast to a point of interest; and,
  - W = charge-weight (kilograms) detonated within any 8-millisecond delay period.

Prediction of maximum blast noise was based on the following equation which assumes average burial of the explosive:

- $P = 37.1 \times SD_3^{-0.97}$ 
  - where P = peak air pressure (Pascals); and,
  - $SD_3$  = scaled distance (metres per kilogram [ $m/kg^{1/3}$ ]).

This equation produces a pressure in pascals, which is then converted to decibels (dB) as shown in the following equation:

- $dB = 20 \log(P/P_0)$ 
  - where  $P_0$  is the reference pressure ( $2 \times 10^{-5}$  Pa).

### 3.4 Evaluation of Impacts

The effects of the Project are ultimately evaluated by comparing modelled results to the applicable guidelines. In this study, the following comparisons will be made:

- Hourly  $L_{EQ}$  values to MOECC criteria;
- Blasting sound levels to MOECC criteria; and
- Change in Percent Highly Annoyed to Health Canada criteria.



CONSULTING ENGINEERS  
& SCIENTISTS

## 4. ASSESSMENT CRITERIA

---

The federal assessment criteria for the Project are outlined by Health Canada (HC, 2011). As the Project falls within Ontario provincial jurisdiction, and thus the MOECC guideline NPC-300 (MOE, 2013) will also be used. The HC and MOECC guidelines both focus on reducing environmental impacts as result of new developments. The HC guidelines further address the potential human health impacts associated with elevated noise levels. The specific criteria are discussed in the following sections.

### 4.1 Ministry of Environment and Climate Change Guidelines

Note that the Ministry of Environment changed its name in the summer of 2014 to the Ministry of Environment and Climate Change. There may be apparent inconsistency between the use of acronyms “MOE” and “MOECC” in this report, however, the use of the acronym MOECC refers to the current ministry, while the acronym MOE is used only when referring to publications by the former Ministry of Environment.

#### 4.1.1 Continuous Sources

The MOECC guidance for continuous noise sources comes from several documents in the Noise Pollution Control or NPC series of publications. NPC-300 is referenced frequently in this section, as it presents receptor criteria and limits, and references many of the other documents in the NPC series.

##### 4.1.1.1 Points of Reception

Sound levels from sources at the Project are required to be assessed at receptors located on noise-sensitive land uses. Noise-sensitive land uses are defined in the MOECC’s environmental noise guideline, Publication NPC-300, as the property of a person that accommodates a dwelling, a noise-sensitive commercial building or a noise-sensitive institutional building. Vacant lots are considered noise-sensitive, provided they are zoned to allow a sensitive use and are accessible by road. A noise-sensitive land use may have one or more receptors.

Residential receptors include houses, cottages, and the like, whether continuously occupied or seasonal. For existing residential properties, sound levels are assessed at the façade of the building at a height of 4.5 m above local grade and an outdoor POR at a height of 1.5 m. The point of assessment for the outdoor receptors is a point 30 m from the building façade, or the property line in cases where the 30 m setback would exceed the size of the property.

Commercial and institutional receptors include hotels, churches, daycares, schools, clinics, and the like. The point of assessment for these types of receptors is at the façade of the building only; Outdoor receptors are not assessed for commercial and institutional noise-sensitive land uses.

Properties that are zoned to permit a noise-sensitive land use but are currently vacant need to be assessed as if a noise-sensitive land use exists at that location. For these noise sensitive areas, the receptors are typically considered in a location consistent with typical local building patterns, at a height of 4.5 m above local grade. In the case of unincorporated land without a minister’s zoning order, the land is





CONSULTING ENGINEERS  
& SCIENTISTS

generally understood to allow noise-sensitive uses, and would be assessed in the same way as land that is zoned for a noise sensitive use.

Forty-four individual noise-sensitive receptors were identified within the local study area. Where the surface mining rights have been secured by Treasury Metals, land use was assumed to be non-noise-sensitive and no receptors were identified. All other vacant lands in the vicinity of the Project that were found to be inaccessible (except by a rough cut-in through the forest) were not considered as receptors. Forty-two of the receptors were identified as houses. One was identified as the campground at Aaron Provincial Park. One receptor is a trailer located on otherwise vacant land. There are no receptors identified within the local study area to the north east, because Treasury Metals has surface rights to all land in that direction.

Since noise impacts decrease with distance from the source, the nearest receptors to the Project are considered the worst-case, and are evaluated explicitly. Other receptors are not evaluated explicitly, but effects can be seen noise contour maps. Locations of all identified receptors are presented in Figure 1. Only receptors that are explicitly evaluated are presented with labels in Figure 1.




Figure 1: Noise Sensitive Receptor Locations

#### 4.1.1.2 Evaluation Criteria

The applicable guideline limits for the receptors in the vicinity of the Project are the "Stationary Source" guidelines for Class 3 area, set out in MOE Publication NPC-300. These guidelines state that one-hour sound exposures (A-Weighted hourly  $L_{EQ}$  values) from stationary sources in Class 3 area shall not exceed that of the background, where the background is defined as the sound level present in the environment produced by sources other than those associated with the project under assessment. The MOE Publication NPC-300 minimum sound level limits at the façade (or plane of window) are summarized as follows:

- The higher of 45 dBA or background sound, during the daytime hours (0700-1900h);
- The higher of 40 dBA or background sound, during the evening hours (1900-2300h); and
- The higher of 40 dBA or background sound, during the night-time hours (2300-0700h).

The MOE Publication NPC-300 sound level limits at an outdoor POR are applicable during the daytime and evening hours only. These limits are summarized as follows:

- The higher of 45 dBA or background sound, during the daytime hours (0700-1900h); and
- The higher of 40 dBA or background sound, during the evening hours (1900-2300h).

The applicable criterion is the higher of the background sound level and the default minimum sound level limit. Measured background sound levels, as shown in section 5, are below the minimum sound level limits. The minimum sound level limits are therefore applicable.

Operation of emergency equipment, such as generators, is not considered except during planned testing. Sound levels of planned testing of emergency equipment are evaluated separately from all other noise from the Project. In the case where multiple pieces of emergency equipment are tested together, their combined impact is evaluated against the limit. The limits for emergency equipment testing are 5 dB above the limits for other stationary sources discussed above.

#### 4.1.1.3 Sound Quality Adjustments

Sources that have characteristics considered to be particularly annoying receive additional consideration in accordance with MOE publication NPC-104 (MOE, 1978). These guidelines specify that a penalty is applicable for tonal, cyclically varying, or quasi-steady impulsive sound characteristics. The adjustment is based on assessment at the receptor, as described in MOE Publication NPC-103 (MOE, 1978). No sources were identified to exhibit annoying sound emissions.

#### 4.1.2 Blasting

Blasting is evaluated separately under MOECC guidelines. Guidance for noise from blasting is taken mainly from two publications, NPC-119 (MOE, 1977) and Guidelines on Information Required for the Assessment of Blasting Noise and Vibration (MOE, 1985).

#### 4.1.2.1 Points of Reception

The receptors for assessment of blasting noise are the same as for continuous noise, as described in section 4.1.1.1.

#### 4.1.2.2 Evaluation Criteria

Blasting activities are identified as a source for sound due to airborne vibration (concussion). The level of sound experienced at a receptor is assessed using the Peak Pressure Level measured in linear (un-weighted) decibels (dB). MOE publication NPC-119 introduces two limits, the cautionary limit, and the peak pressure level limit. The cautionary limit is 120 dB and can be applied in cases where there is no monitoring of sound levels from blasting. The peak pressure limit is 128 dB, and can only be used when sound level monitoring is conducted during blasting. The cautionary limit is used as the criteria for airborne blast noise for the Project.

## 4.2 Health Canada Noise Guidelines

### 4.2.1 Continuous Sources

The applicable federal criteria for this assessment were developed by Health Canada, and presented in Guidance for Evaluating Human Health Impacts in Environmental Assessment: Noise (HC, 2011). These guidelines are specifically intended for use in federal Environmental Assessments.

#### 4.2.1.1 Points of Reception

The Health Canada guidelines do not provide specific guidance with respect to choosing noise sensitive receptor locations. It is clear throughout the document that it is intended for the assessment of noise as it relates to human health, therefore receptor locations should be those occupied by humans. In the absence of further guidance, the MOECC definition of a noise sensitive receptor is used in this assessment, meaning that the receptor locations for both MOECC assessment and HC assessment are the same.

#### 4.2.1.2 Evaluation Criteria

Sound levels at receptors are evaluated against the baseline noise level in the area. The assessment method utilizes the change in Percent Highly Annoyed metric, which aims to predict change in the proportion of people that would be highly annoyed due to the elevated noise levels. The change in Percent Highly Annoyed is influenced by the absolute level of the sound experienced at the receptor. There is a non-linear relationship between Percent Highly Annoyed and  $L_{EQ}$ . In practice this means that in a quiet area, an increase in sound level will result in a lower change in percent highly annoyed than the same change in sound level in a louder area. Since The Project is in a relatively quiet area, the change in Percent Highly Annoyed would typically be expected to be low. The practical result of this is that the MOECC assessment criteria discussed in section 4.1 are the more stringent of the two guidelines.

The Health Canada noise assessment criteria are as follows:

- Maximum  $L_{DN}$  of 75 dBA





CONSULTING ENGINEERS  
& SCIENTISTS

- Maximum Allowed Increase in Percent Highly Annoyed of 6.5%

The Health Canada guidelines require that all baseline noise assessments and project-related noise emissions be evaluated in terms of the  $L_{DN}$  which accounts for full day exposures.

The guidelines apply to the construction, operational, and closure phases of the project. The inclusion of the construction and closure phases is required as those phases of the project will be longer than one year in duration.

#### **4.2.2 Blasting**

Blasting is considered a “High Energy Impulse” under the Health Canada noise guidelines. The guidelines dictate that the assessment of impulsive noise is to be combined with the assessment of steady state noise. A 12 dB penalty is added to the high energy impulsive component of the combined total.

## **5. BASELINE STUDIES**

---

A baseline study was conducted in the winter of 2011 and the summer of 2013. Three sites were monitored in 2013 and one site in 2011. Further details are provided in section 5. Data from the baseline study is used to determine the appropriate sound level limits resulting from the sound levels in the existing natural environment.


The more detailed baseline assessment completed in 2013, was used as the basis for this project, and is documented in detail the Baseline Noise Assessment Report (RWDI, 2013). The baseline study did not present the  $L_D$ ,  $L_N$ , or  $L_{DN}$  levels. These have been calculated from the raw data and are presented in this section along with the original baseline data. Key items from that report are summarized in this section.

### **5.1 Baseline Monitoring Locations**

Long-term measurements of background ambient sound levels at one location were conducted from December 5 to December 7, 2011, near the project site as shown in Figure 2.



CONSULTING ENGINEERS  
& SCIENTISTS



**Figure 2:** Baseline Monitoring Locations, Winter 2011

Additional monitoring at three representative locations to the west of the site was conducted from July 3 to July 9, 2013. The locations of baseline monitoring stations are shown in Figure 3.



CONSULTING ENGINEERS  
 & SCIENTISTS




Figure 3: Baseline Monitoring Locations, Summer 2013

## 5.2 Noise Environment

The study area is in a rural location outside a small northern community with low levels of human activity. Noise observed during the study consisted of mostly wind, small animals, bird noise and noise from the TransCanada Highway which runs in near proximity to the study area.

Background ambient sound levels in remote areas are typically low, ranging from about 25 to 40 dBA. These values are similar to those measured for the Project. At these levels, noise would be described as faint.





**Table 4:** Baseline Study Results

Location	Lowest Hourly L <sub>EQ</sub> (dBA)			L <sub>D</sub> (Day, 15h) (dBA)	L <sub>N</sub> (Night, 9h) (dBA)	L <sub>DN</sub> (dBA)
	Daytime <sup>[1]</sup>	Evening <sup>[1]</sup>	Nighttime <sup>[1]</sup>			
Site 1	39	38	35	49	46	48
Site 2	38	37	32	44	43	44
Site 3	32	35	28	45	41	44
Site 4 <sup>[2]</sup>	28	34	30	-	-	-

**Notes:**

- Daytime refers to 0700-1900h; Evening refers to 1900-2300h; and Nighttime refers to 2300-0700h.
- The LD and LN, and LDN have not been calculated for the 2011 field program, as the monitoring location is not representative of receptor locations.

### 5.2.1 Temporal Variation

The difference between daytime and nighttime sound levels were generally small, and are attributed mainly to very low level of noise from human activity which could not be screened out.

### 5.3 Applicability

The measured ambient sound levels will be used in the Percent Highly Annoyed analysis, and the determination of background levels for evaluation in the MOECC guidelines.

The measurement sites that are of most interest are those which most closely represent the sound levels at the noise sensitive receptors. Of the four measurements, the measurement at Site 2 is most representative of the acoustical environment of the noise sensitive receptors. The sound environment at site 1 is mainly dominated by noise from the Trans-Canada Highway, whereas site 3 has very little influence from the highway both of which are not representative for the worst case receptors assessed. Site 2 data will be used in the assessment for all receptors.

## 6. CONSTRUCTION AND SITE PREPARATION PHASE

### 6.1 Description of Continuous Operations

Construction and Site Preparation phases will include tree clearing, grubbing, stripping of overburden, crushing of aggregate for road construction, blasting, and construction of project facilities. Many of these activities have the potential for local noise impacts. The duration of the Site Preparation and the Construction phase is estimated to be 3 years. HC guidelines suggest that for construction operation with durations greater than 1 year, noise should be assessed in the same way as operational noise, and thus entailing quantitative assessment. It is conservatively assumed in the assessment of Construction and Site Preparation that these activities would occur 24-hours per day, with no change in the nature of the operations during daytime, evening, or nighttime.



CONSULTING ENGINEERS  
& SCIENTISTS

## 6.2 Noise Source Summary

### 6.2.1 Continuous Sources

For the most part, details regarding specific equipment to be used during the Construction and Site Preparation Phase were not yet available at the time of this assessment. It was assumed that, where possible, Treasury Metals would attempt to secure heavy equipment that would later be used in the Operations Phase. The heavy equipment modelled for the Construction and Site Preparation phase is therefore a subset of the equipment that was modelled for the operations phase, with a portable rock crusher added as an additional piece of equipment. Table 5 shows the sources that were modelled in this phase, including quantity of each type of source, and respective sound power levels.

**Table 5:** Modelled Noise Sources for the Construction and Site Preparation Phase

Equipment	Qty	Octave Band Sound Power Level (dB)									Overall dBA
		31.5	63	125	250	500	1000	2000	4000	8000	
Drill	1	101	96	103	103	100	102	101	97	89	107
Excavator	1	95	118	110	100	97	93	94	90	85	101
Haul Truck	6	100	96	102	104	103	103	102	95	90	107
Bulldozer	2	96	96	101	94	95	95	94	88	79	100
Front end loader	1	98	97	105	102	97	94	91	88	82	100
Dewatering Pump	1	78	79	80	82	83	85	83	79	72	89
Portable Crusher	1	113	122	116	108	109	107	105	103	99	113

Sound power levels for all mobile equipment were obtained from representative sound power data on file. The sound power level for the dewatering pump was calculated based on typical specifications.

During the construction phase, work is expected to progress simultaneously across most areas of the site. To account for this, the modelling approach used was to average the cumulative sound power level of all Construction and Site Preparation sources across the entire site area. This accounts for the very mobile nature of the sources, and provides a good indication of average sound levels in the absence of a detailed construction plan. Figure 4 shows the location of the area source used for the prediction of sound levels from this phase.



CONSULTING ENGINEERS  
 & SCIENTISTS




Figure 4: Source Locations, Construction and Site Preparation Phase

### 6.2.2 Blasting

Blasting during the Construction and Site Preparation phase is expected to take place once per day in the area of the open pit mine during construction. Sound levels from blasting were calculated as described in section 3.3.2.

In order to accurately assess sound levels from blasting, the blast is assumed to happen at the edge of the pit closest to each receptor. That is, for each receptor location, the worst-case blast location is chosen.

At the time of the assessment, limited details regarding the expected blast configurations were available, therefore the modelling assumed a maximum charge per delay of 100 kg.

### 6.3 Predicted Sound Levels

Sound contours (isopleths of equal sound level) resulting from the Construction and Site Preparation phase are presented in Figure 5. A modelling output file showing the details of a sample calculation at NR03 is included in Appendix B.





CONSULTING ENGINEERS  
 & SCIENTISTS




Figure 5: Predicted Sound Levels, Construction and Site Preparation Phase

### 6.3.1 Assessment to MOECC Guidelines

#### 6.3.1.1 Continuous Sources

Sound levels were assessed at the five worst-case receptors as discussed in section 4.1.1.1. All levels are predicted to be in compliance with the NPC-300 (MOE, 2013) minimum sound level limits for a class 3 area. Table 6 shows the predicted sound levels and applicable limits.





**Table 6:** Assessment of Construction and Site Preparation Noise to MOECC Guidelines

Receptor		Limits			Sound Level at Receptor L <sub>EQ</sub> (dBA)
ID	Description	Daytime	Evening	Nighttime	
NR03	House - owned by Mcleish	45	45	40	40
NR03_O	Outdoor receptor- Mcleish	45	40	-	39
NR04	House - owned by Nystroms	45	45	40	33
NR04_O	Outdoor receptor- Nystroms	45	40	-	32
NR30	House - East Thunder Lake Road	45	45	40	33
NR30_O	Outdoor receptor - East Thunder Lake Road	45	40	-	32
NR44	House - Near Trans-Canada Highway	45	45	40	29
NR44_O	Outdoor receptor - Near Trans-Canada Highway	45	45	-	28
NR47	House - East Thunder Lake Road	45	45	40	29
NR47_O	Outdoor receptor - East Thunder Lake Road	45	40	-	28

### 6.3.1.2 Blasting

Sound levels from blasting were evaluated separately from sounds due to continuous noise sources as per the guidance. Levels were assessed at the five worst-case receptors as discussed in section 4.1.1.1. A radius of influence was also determined, which is the distance from a blast where the sound levels will fall off to the precautionary limit. The radius of influence is 95 m in all directions from the blasting. Any receptor further than 95 m from a blast will therefore experience effects lower than the NPC-119 precautionary limit.

All levels at receptors are predicted to be in compliance with the NPC-300 minimum sound level limits for a class 3 area. Table 7 shows the predicted sound levels and applicable limits.

**Table 7:** Predicted Sound Levels from Blasting

Receptor	Distance (m)	Peak Sound Pressure Level (dB)
Cautionary Limit	95	120
NR03	1813	78
NR04	3000	71
NR30	2373	75
NR44	3734	68
NR47	3187	70



CONSULTING ENGINEERS  
& SCIENTISTS

### 6.3.2 Assessment to Health Canada Guidelines

Change in Percent Highly Annoyed was assessed at the five worst-case receptors as discussed in section 4.1.1.1. Site 2 from the 2013 baseline study was used as the basis for the ambient noise data as it best represents the acoustic environment at all receptor locations. 10 dB penalties were applied to both the baseline and project noise levels to account for the rural nature of the site location.

The change in Percent Highly Annoyed at each receptor is predicted to be below the 6.5% threshold, and absolute sound levels are predicted to be below the 75 dBA threshold. Table 8 shows the predicted sounds levels and change in Percent Highly Annoyed.

Blasting at the site is to take place no more than once per day, during daytime hours only. Since the Health Canada guidelines average sound levels over a 24-hour period, with additional penalty for the nighttime period, a single blast per day was considered to be infrequent and was not further assessed against these guidelines.

**Table 8:** Assessment of Construction and Site Preparation Noise to HC Guidelines

Receptor	L <sub>DN</sub> (dBA)	Change in Percent Highly Annoyed	Complies with HC Guidelines?
NR03	56	1.6	Yes
NR03_O	56	1.4	Yes
NR04	49	0.4	Yes
NR04_O	48	0.3	Yes
NR30	49	0.3	Yes
NR30_O	48	0.3	Yes
NR44	45	0.1	Yes
NR44_O	44	0.1	Yes
NR47	45	0.1	Yes
NR47_O	44	0.1	Yes

Details of the L<sub>DN</sub> and Percent Highly Annoyed calculations are included in Appendix B.

### 6.4 Mitigation

In order to achieve compliance at all receptors, the sound power levels of equipment were limited in some cases. The limited power levels are still within the accepted range of power levels from this type of equipment from different manufacturers and of different ages, but are quieter than average. The sound power levels presented in Table 5 reflect these reduced levels. Treasury Metals has committed to ensuring that sound levels from these pieces of equipment meet these requirements.

Treasury metals will ensure that best practices are followed during the Construction and Site Preparation phase to ensure that sound levels are minimized. These best practices will include:



CONSULTING ENGINEERS  
& SCIENTISTS

- Conduct heavy construction activity between the hours of 07:00 and 22:00 if possible to reduce the potential impact of construction noise;
- Advise nearby residents of significant noise-causing activities such as mine blasts and schedule these events to reduce disruption to them;
- Ensure that all internal combustion engines are fitted with appropriate muffler systems; and
- Employ controlled blasting methods such as penetrating cone fracture.

## 6.5 Residual Effects

Residual effects are those that remain when all mitigation options have been incorporated into the project design and operation. As all sound levels are predicted to comply with the applicable criteria, it is not anticipated that there will be residual effects for this site.

## 6.6 Conclusions

The results of the noise assessment for the Construction and Site Preparation Phase can be summarized as follows:

- Predicted worst case hourly noise levels range from 28 to 40 dBA at worst-case receptors;
- Predicted  $L_{DN}$  levels range from 44 to 56 dBA at worst-case receptors;
- Predicted increase in Percent Highly Annoyed range from 0.1 to 1.6 at worst-case receptors; and
- Predicted radius of influence from blasting is 95 m in all directions from the blasting site which is predicted to comply with the exclusionary limit at any receptor.

Predicted sound levels are shown to be below the guideline limits at each of the receptors for the Construction and Site Preparation phase. The Construction and Site Preparation phase is predicted to comply with the requirements of Health Canada and the MOECC guidelines.

## 7. OPERATIONS PHASE

---

The assessment of noise from the operation phase focuses on the predictable worst-case year, which includes both open pit and underground mining. Other activities that may take place during the operating life of the mine, such as remediation of the open pit, are anticipated to generate lesser noise, and are not explicitly assessed.

### 7.1 Description of Continuous Operations

The operations phases will include both underground and open face mining activities. The open face mining activities include drilling, blasting, dozing, excavating and the transportation of rock material around site. The underground activities include the operation of intake and exhaust vent raises and the transportation of rock material to the surface. Emergency power generation occurs on site and testing of emergency generators occurs only during the daytime hours. Many of these activities have the potential for local noise impacts. The duration of the operations phase is estimated to be 10 years. It is



CONSULTING ENGINEERS  
& SCIENTISTS

conservatively assumed in the assessment of operations that these activities would occur 24-hours per day, with no change in the nature of the operations during daytime, evening, or nighttime, other than the generator testing.

## 7.2 Noise Source Summary

### 7.2.1 Continuous Sources

For the most part, limited details regarding types of equipment used during the operations phase were available at the time of this assessment. Sound power levels for all mobile equipment were obtained from representative sound power data on file. The sound power level for the dewatering pump and aeration tank blower were conservatively calculated based on typical specifications. The sound power level for the exhaust louvers on the mill building were calculated assuming an indoor sound power level of 85 dB within the mill facility. This is a typical objective for indoor sound levels in order to comply with occupational health and safety regulations. The calculations are based on 3.0 m/s air velocities and six air changes per hour within the building. Where appropriate, source emissions were time-weighted based on typical operating assumptions. Table 9 shows the sources that were modelled in this phase, including number each type of source, and sound power levels. Power levels shown in Table 9 do not account for time weighting.

**Table 9:** Modelled Noise Sources for the Operations Phase

Equipment	Qty.	Octave Band Sound Power Level (dB)									Overall dBA
		31.5	63	125	250	500	1000	2000	4000	8000	
150 kW Emergency Generator	1	-	102	95	98	108	107	106	102	100	112
600 kW Emergency Generator	1	-	83	95	103	108	109	107	103	99	113
Aeration Tank Blower	1	109	104	99	94	89	84	79	74	69	91
Jaw Crusher	1	89	87	88	91	94	95	94	90	83	99
Exhaust Louver for Mill	14	-	-	-	-	64	-	-	-	-	61
Furnace Exhaust	1	-	85	85	75	70	68	63	58	53	74
Kiln Fan	1	-	95	93	93	93	90	85	79	72	94
Front End Loader	1	98	97	105	102	97	94	91	88	82	100
Rock Drop at Crusher	1	114	116	121	122	113	114	111	106	100	119
Dewatering Pump	1	90	90	92	94	96	97	95	91	84	101
Drill	2	101	96	103	103	100	102	101	97	89	107
Bulldozer	3	96	96	101	94	95	95	94	88	79	100
Hydraulic Excavator	2	95	118	110	100	97	93	94	90	85	101
Rock Drop at Stockpiles	3	100	106	116	107	109	103	104	103	103	112
Exhaust Vent Raise	2	-	117	117	114	108	105	100	94	87	111
Fresh Air Intake Vent Raise	1	-	117	117	114	108	105	100	94	87	111
50 Ton Haul Truck	14	100	96	102	104	103	103	102	95	90	107





CONSULTING ENGINEERS  
 & SCIENTISTS

All sources other than haul truck noise were modelled as point sources. Haul truck noise was modelling using line sources. Noise source locations were chosen to represent a predictable worst-case level of impacts. As an example of this, the majority of haul truck traffic is modelled on the longest haul route. All open pit mine sources were modelled at ground level, to represent the beginning of a new pit, or the remediation afterwards.

In the operating phase, ground contours have been modelled accounting for a 2 m high berm around the perimeter of the pit, a minimum height of 3 m at the low grade stockpile, and a minimum height of 10 m at the overburden pile.




Figure 6: Source Locations, Operations Phase

## 7.2.2 Blasting

Blasting during the operations phase is expected to take place once per day in the area of the open pit mine. Sound levels from blasting were calculated as described in section 3.3.2.

In order to accurately assess sound levels from blasting, the blast is assumed to happen at the edge of the pit closest to each receptor. That is, for each receptor location, the worst-case blast location is chosen.





CONSULTING ENGINEERS  
& SCIENTISTS

At the time of the assessment, limited details regarding the expected blast configurations were available, therefore the modelling assumed a maximum charge per delay of 100 kg.

### 7.3 Predicted Sound Levels

Sound contours (isopleths of equal sound level) resulting from the Operation phase are presented in Figure 7. These contours include the effects of all continuous noise sources except for emergency generator testing. A modelling output file showing the details of a sample calculation at NR03 is included in Appendix B.




Figure 7: Predicted Sound Levels, Operations Phase

#### 7.3.1 Assessment to MOECC Guidelines

##### 7.3.1.1 Continuous Sources

Sound levels were assessed at the five worst-case receptors as discussed in section 4.1.1.1. All levels are predicted to be in compliance with the NPC-300 (MOE, 2013) minimum sound level limits for a class 3 area. Table 10 shows the predicted sound levels and applicable limits for continuous sources except for generator testing. Generator testing is assessed separately, and the results of that assessment are shown in Table 11.





**Table 10:** Assessment of Operating Phase Noise to MOECC Guidelines

Receptor		Limits			Sound Level at Receptor L <sub>EQ</sub> (dBA)
ID	Description	Daytime	Evening	Nighttime	
NR03	House - owned by Mcleish	45	45	40	40
NR03_O	Outdoor receptor- Mcleish	45	40	-	38
NR04	House - owned by Nystroms	45	45	40	34
NR04_O	Outdoor receptor- Nystroms	45	40	-	33
NR30	House - East Thunder Lake Road	45	45	40	34
NR30_O	Outdoor receptor - East Thunder Lake Road	45	40	-	33
NR44	House - Near Trans-Canada Highway	45	45	40	30
NR44_O	Outdoor receptor - Near Trans-Canada Highway	45	45	-	30
NR47	House - East Thunder Lake Road	45	45	40	31
NR47_O	Outdoor receptor - East Thunder Lake Road	45	40	-	30

**Table 11:** Assessment of Operating Phase Generator Testing Noise to MOECC Guidelines

Receptor		Limits			Sound Level at Receptor L <sub>EQ</sub> (dBA)
ID	Description	Daytime	Evening	Nighttime	
NR03	House - owned by Mcleish	50	-	-	43
NR03_O	Outdoor receptor- Mcleish	50	-	-	43
NR04	House - owned by Nystroms	50	-	-	36
NR04_O	Outdoor receptor- Nystroms	50	-	-	33
NR30	House - East Thunder Lake Road	50	-	-	28
NR30_O	Outdoor receptor - East Thunder Lake Road	50	-	-	27
NR44	House - Near Trans-Canada Highway	50	-	-	31
NR44_O	Outdoor receptor - Near Trans-Canada Highway	50	-	-	28
NR47	House - East Thunder Lake Road	50	-	-	25
NR47_O	Outdoor receptor - East Thunder Lake Road	50	-	-	25



CONSULTING ENGINEERS  
& SCIENTISTS

### 7.3.1.2 Blasting

Sound levels from blasting were evaluated separately from sound from continuous noise sources. Levels were assessed at the five worst-case receptors as discussed in section 4.1.1.1. A radius of influence was also determined, which is the distance from a blast where the sound levels will fall off to the precautionary limit. The radius of influence is 95 m in all directions from the blasting. Any receptor further than 95 m from a blast will therefore experience effects lower than the NPC-119 precautionary limit.

All levels at receptors are predicted to be in compliance with the NPC-300 minimum sound level limits for a class 3 area. Table 12 shows the predicted sound levels and applicable limits.

**Table 12:** Predicted Sound Levels from Blasting

Receptor	Distance (m)	Peak Sound Pressure Level (dB)
Cautionary Limit	95	120
NR03	1813	78
NR04	3000	71
NR30	2373	75
NR44	3734	68
NR47	3187	70

### 7.3.2 Assessment to Health Canada Guidelines

Change in Percent Highly Annoyed was assessed at the five worst-case receptors as discussed in section 4.1.1.1. Site 2 from the 2013 baseline study was used as the basis for the ambient noise data as it best represents the acoustic environment at all receptor locations. 10 dB penalties were applied to both the baseline and project noise levels to account for the rural nature of the site location.

The change in Percent Highly Annoyed at each receptor is predicted to be below the 6.5% threshold, and absolute sound levels are predicted to be below the 75 dBA threshold. Table 9 shows the predicted sounds levels and change in Percent Highly Annoyed.

Blasting at the site is to take place no more than once per day, during daytime hours only. Since the Health Canada guidelines average sound levels over a 24-hour period, with additional penalty for the nighttime period, a single blast per day was considered to be infrequent and was not further assessed against these guidelines.



**Table 13:** Assessment of Operating Noise to HC Guidelines

Receptor	L <sub>DN</sub> (dBA)	Change in Percent Highly Annoyed	Complies with HC Guidelines?
NR03	57	1.8	Yes
NR03_O	55	1.4	Yes
NR04	51	0.5	Yes
NR04_O	50	0.4	Yes
NR30	50	0.4	Yes
NR30_O	50	0.4	Yes
NR44	47	0.2	Yes
NR44_O	46	0.2	Yes
NR47	47	0.2	Yes
NR47_O	46	0.2	Yes

Details of the L<sub>DN</sub> and Percent Highly Annoyed calculations are included in Appendix B.

## 7.4 Mitigation

In order to achieve compliance at all receptors, the sound power levels of equipment were limited in some cases. The limited power levels are still within the accepted range of power levels from these types of equipment from different manufacturers and of different ages, but are quieter than average. The sound power levels presented in Table 9 reflect these reduced levels. Treasury Metals has committed to ensuring that sound levels from these pieces of equipment meet these requirements.

Treasury metals will ensure that best practices are followed during the Operations phase to ensure that sound levels are minimized. These best practices will include:

- Conduct heavy construction activity between the hours of 07:00 and 22:00 if possible to reduce the potential impact of construction noise;
- Advise nearby residents of significant noise-causing activities such as mine blasts and schedule these events to reduce disruption to them;
- Ensure that all internal combustion engines are fitted with appropriate muffler systems; and
- Employ controlled blasting methods such as penetrating cone fracture.

## 7.5 Residual Effects

Residual effects are those that remain when all mitigation options have been incorporated into the project design and operation. As all sound levels are predicted to comply with the applicable criteria, it is not anticipated that there will be residual effects for this site.



CONSULTING ENGINEERS  
& SCIENTISTS

## 7.6 Conclusions

The results of the noise assessment for the operations phase can be summarized as follows:

- Predicted worst case hourly noise levels range from 30 to 40 dBA at worst-case receptors; and
- Predicted worst case hourly noise levels during generator testing range from 25 to 43 dBA at worst-case receptors; and
- Predicted  $L_{DN}$  levels range from 46 to 57 dBA at worst-case receptors; and
- Predicted increase in Percent Highly Annoyed range from 0.2 to 1.8 at worst-case receptors.
- Predicted radius of influence from blasting is 95 m in all directions from the blasting site which is predicted to comply with the exclusionary limit at any receptor.

Predicted sound levels are shown to be below the guideline limits at each of the receptors for the operations. The operations phase is predicted to comply with the requirements of Health Canada and the MOECC guidelines.

## 8. CLOSURE, DECOMMISSIONING AND RESTORATION PHASE

Activities directly related to closure of mining operations on site, as well as any ongoing remediation activities are assessed together in the closure phase.

### 8.1 Description of Continuous Operations

Closure, Decommissioning and Restoration phases will include backfilling and flooding of the open pits and underground mine area, disassembling of infrastructure and equipment as well as overall site maintenance. Many of these activities have the potential for local noise impacts. The duration of the Closure, Decommissioning and Restoration phase is estimated to be 2 years. It is conservatively assumed in the assessment of Closure, Decommissioning and Restoration that these activities would occur 24-hours per day, with no change in the nature of the operations during daytime, evening, and nighttime. No blasting would take place during this phase.

### 8.2 Noise Source Summary

Details regarding types of equipment used during the closure phase were not yet available at the time of this assessment. It was assumed that Treasury Metals would use the same types of equipment used in both the previous phases. The heavy equipment modelled for the Closure, Decommissioning and Restoration phase is therefore a subset of the equipment that was modelled for the operations phase. Table 14 shows the sources that were modelled in this phase, including number of sources, and sound power levels.



**Table 14:** Modelled Noise Sources for the Closure, Decommissioning and Restoration Phase

Equipment	Qty	Octave Band Sound Power Level (dB)									Overall dBA
		31.5	63	125	250	500	1000	2000	4000	8000	
Excavator	2	95	118	110	100	97	93	94	90	85	101
Haul Truck	6	100	96	102	104	103	103	102	95	90	107
Bulldozer	2	96	96	101	94	95	95	94	88	79	100
Front end loader	1	98	97	105	102	97	94	91	88	82	100
Dewatering Pump	1	90	90	92	94	96	97	96	91	84	102

Sound power levels for all mobile equipment were obtained from representative sound power data on file. The sound power level for the dewatering pump was calculated based on typical specifications.

During the closure phase, work is expected to progress simultaneously across most areas of the site. To account for this, the modelling approached used was to average the cumulative sound power level of all closure sources across the entire site area. This accounts for the very mobile nature of the sources, and provides a good indication of average sound levels in the absence of a detailed closure plan. Figure 8 shows the location of the area source used for the prediction of sound levels from this phase.





CONSULTING ENGINEERS  
 & SCIENTISTS




Figure 8: Source Locations, Decommissioning and Restoration Phase

### 8.3 Predicted Sound Levels

Sound contours (isopleths of equal sound level) resulting from the Closure, Decommissioning and Restoration Phase are presented in Figure 9. A modelling output file showing the details of a sample calculation at NR03 is included in Appendix B.





CONSULTING ENGINEERS  
 & SCIENTISTS




Figure 9: Predicted Sound Levels, Closure, Decommissioning and Restoration Phase

### 8.3.1 Assessment to MOECC Guidelines

Sound levels were assessed at the five worst-case receptors as discussed in section 4.1.1.1. All levels are predicted to be in compliance with the NPC-300 (MOE, 2013) minimum sound level limits for a class 3 area. Table 15 shows the predicted sound levels and applicable limits.



**Table 15:** Assessment of Closure, Decommissioning and Restoration Noise to MOECC Guidelines

Receptor		Limits			Sound Level at Receptor L <sub>EQ</sub> (dBA)
ID	Description	Daytime	Evening	Nighttime	
NR03	House - owned by Mcleish	45	45	40	39
NR03_O	Outdoor receptor- Mcleish	45	40	-	39
NR04	House - owned by Nystroms	45	45	40	31
NR04_O	Outdoor receptor- Nystroms	45	40	-	31
NR30	House - East Thunder Lake Road	45	45	40	31
NR30_O	Outdoor receptor - East Thunder Lake Road	45	40	-	30
NR44	House - Near Trans-Canada Highway	45	45	40	27
NR44_O	Outdoor receptor - Near Trans-Canada Highway	45	45	-	25
NR47	House - East Thunder Lake Road	45	45	40	27
NR47_O	Outdoor receptor - East Thunder Lake Road	45	40	-	26

### 8.3.2 Assessment to Health Canada Guidelines

Change in Percent Highly Annoyed was assessed at the five worst-case receptors as discussed in section 4.1.1.1. Site 2 from the 2013 baseline study was used as the basis for the ambient noise data as it best represents the acoustic environment at all receptor locations. 10 dB penalties were applied to both the baseline and project noise levels to account for the rural nature of the site location.

The change in Percent Highly Annoyed at each receptor is predicted to be below the 6.5% threshold, and absolute sound levels are predicted to be below the 75 dBA threshold. Table 16 shows the predicted sounds levels and change in Percent Highly Annoyed.



**Table 16:** Assessment of Closure, Decommissioning and Restoration Noise to HC Guidelines

Receptor	L <sub>DN</sub> (dBA)	Change in Percent Highly Annoyed	Complies with HC Guidelines?
NR03	55	1.3	Yes
NR03_O	55	1.2	Yes
NR04	48	0.3	Yes
NR04_O	47	0.2	Yes
NR30	47	0.2	Yes
NR30_O	46	0.2	Yes
NR44	43	0.1	Yes
NR44_O	42	0.1	Yes
NR47	43	0.1	Yes
NR47_O	42	0.1	Yes

Details of the L<sub>DN</sub> and Percent Highly Annoyed calculations are included in Appendix B.

## 8.4 Mitigation

In order to achieve compliance at all receptors, the sound power levels of equipment were limited in some cases. The limited power levels are still within the accepted range of power levels from these type of equipment from different manufacturers and of different ages, but are quieter than average. The sound power levels presented in Table 5 reflect these reduced levels. Treasury Metals has committed to ensuring that sound levels from these pieces of equipment meet these requirements.

Treasury metals will ensure that best practices are followed during the Closure, Decommissioning and Restoration phase to ensure that sound levels are minimized. These best practices will include:

- Conduct heavy construction activity between the hours of 07:00 and 22:00 if possible to reduce the potential impact of construction noise;
- Advise nearby residents of significant noise-causing activities and schedule these events to reduce disruption to them; and
- Ensure that all internal combustion engines are fitted with appropriate muffler systems.

## 8.5 Residual Effects

Residual effects are those that remain when all mitigation options have been incorporated into the project design and operation. As all sound levels are predicted to comply with the applicable criteria, it is not anticipated that there will be residual effects for this site.



CONSULTING ENGINEERS  
& SCIENTISTS

## 8.6 Conclusions

The results of the noise assessment for the Closure, Decommissioning and Restoration phase can be summarized as follows:

- Predicted worst case hourly noise levels range from 26 to 39 dBA at worst-case receptors; and
- Predicted  $L_{DN}$  levels range from 42 to 55 dBA at worst-case receptors; and
- Predicted increase in Percent Highly Annoyed range from 0.1 to 1.3 at worst-case receptors.

Predicted sound levels are shown to be below the guideline limits at each of the receptors for the Closure, Decommissioning and Restoration phase. The Closure, Decommissioning and Restoration phase is predicted to comply with the requirements of Health Canada and the MOECC guidelines.

## 9. UNCERTAINTY

---

The modelling used in this assessment has an overall prediction accuracy that is dependent on two factors: the accuracy of the acoustical source data, and the accuracy of the noise propagation model.

The sound level data used in this assessment is based on manufacturers data, engineering calculations, or data from similar equipment, and would be expected to have a high degree of accuracy. Efforts should be made when procuring equipment for the Project to verify that equipment sound levels are similar to those modelled.

The ISO 9613 propagation algorithms have a published accuracy of + 3 dBA over source-receiver distances between 100 and 1000 m. A similar degree of accuracy would be expected over the distances considered in this assessment. This is considered to be an excellent agreement for an environmental noise model over such a large distance. A 3 dBA increase or decrease would be considered imperceptible to humans.

In addition, the ISO 9613 model produces results that are representative of meteorological conditions favouring sound propagation (e.g., downwind and/or inversion conditions). These conditions do not occur all the time, and therefore, the model predictions will be conservative, and actual sound levels at the receptors may be less than indicated for much of the time.

Based on the above, the overall model prediction confidence is expected to be high.

## 10. MONITORING

---

Health Canada recommends monitoring when predicted noise levels verge upon the level where adverse human health effects can potentially occur. Since the predicted levels are well below that point, monitoring is not recommended under the Health Canada guidelines.





CONSULTING ENGINEERS  
& SCIENTISTS

Monitoring and follow up studies are not required by NPC-300 (MOE, 2013), but may be requested by the MOECC as part of an Environmental Compliance Approval. Details of this monitoring would be determined in the Environmental Compliance Approval application process.

Monitoring of blasting sound levels is required only where sound levels are predicted to be above the NPC-119 precautionary limits. Since impacts are not anticipated to exceed the precautionary limits, no blast monitoring is required.

No ongoing monitoring is recommended. However, in the event that noise complaints are received during the life of the Project, it is recommended that actions are taken promptly to monitor sound levels. Sound levels must be monitored for a sufficient length of time as to determine the validity and cause of the complaint. Details of a monitoring program in the case of a complaint will be determined on case-by-case basis, as the location of the complainant and status of the Project will influence the best practices in monitoring.

## 11. SUMMARY AND CONCLUSIONS

---

A systematic approach was adopted to identify potential noise sources and quantify the emissions due to Project activities at the Goliath Gold site. Best-available data regarding future construction, operations, and decommissioning were collected from Treasury Metals, and used to predict sound levels for the Project. Sound levels from blasting were evaluated separately from sound from continuous noise sources.

This assessment concentrates on comparisons with guideline limits and impacts on human receptors. The effects of potential noise impacts on other biophysical components, including wildlife, vegetation and human health are addressed separately by the appropriate disciplines.

The results of the noise assessment for the Project can be summarized as follows:

- Predicted worst case hourly noise levels range from 26 to 40 dBA at worst-case receptors; and
- Predicted  $L_{DN}$  levels range from 42 to 57 dBA at worst-case receptors; and
- Predicted increase in Percent Highly Annoyed range from 0.1 to 1.8 at worst-case receptors.
- Predicted radius of influence from blasting is 95 m in all directions from the blasting site which is predicted to comply with the exclusionary limit at any receptor.

Predicted sound levels are shown to be below the guideline limits at each of the receptors for all phases. The Project is predicted to comply with the requirements of Health Canada guidelines (HC, 2011) and the NPC-300 (MOE, 2013) guidelines.



CONSULTING ENGINEERS  
& SCIENTISTS

## 12. REFERENCES

---

Health Canada (HC), 2011, *Guidance for Evaluating Human Health Impacts in Environmental Assessment: Noise*. Draft, January 2011.

International Organization for Standardization (ISO), 1994b, International Standard ISO 9613-1:1994, *Acoustics – Attenuation of Sound during propagation outdoors. Part 1: Calculation of the absorption of sound by the atmosphere*.

International Organization for Standardization (ISO), 1996, International Standard ISO 9613-2:1996, *Acoustics – Attenuation of sound during propagation outdoors – Part 2: General method of calculation*

International Society of Explosives Engineers (ISEE), 2011. *Blaster's Handbook*, 18th edition, Stiehr, J.F., Ohio USA.

Ontario Ministry of the Environment (MOE), 1978, *Model Municipal Noise Control Bylaw*, which includes *Publication NPC-103 – Procedures*, *Publication NPC-104 – Sound Level Adjustments*, and *NPC-119 – Blasting*.

Ontario Ministry of the Environment (MOE), 1985, *Guidelines on Information Required for the Assessment of Blasting Noise and Vibration*

Ontario Ministry of the Environment (MOE), August 2013, Publication NPC-300, *Environmental Noise Guideline Stationary and Transportation Sources – Approval and Planning*

Treasury Metals Incorporated (Treasury), November 26, 2012. *Project Description, Goliath Gold Project*

RWDI AIR Inc, January 2014, *Treasury Metals Inc. - Goliath Gold Project – Noise Baseline Study*